SOLICITATION/CONTRACT/ORDER FOR COMMERCIAL PRODUCTS AND COMMERCIAL SERVICES

NOTE: OFFEROR TO COMPLETE BLOCKS 12, 17, 23, 24 AND 30.

1. REQUISITION NUMBER	PAGE 1 OF
	30

2. CONTRACT NUMBER	3. AWARD/EFFECTIVE DATE	4. ORDER NUMBER	5. SOLICITATION NUMBER	6. SOLICITATION ISSUE DATE
			15B51426Q00000025	08/26/2026

7. FOR SOLICITATION INFORMATION CALL:	a. NAME	b. TELEPHONE NUMBER (*No collect calls*)	8. OFFER DUE DATE / LOCAL TIME
	C. Gonzalez c9gonzalez@bop.gov		09/16/2026 10:00 CT

9. ISSUED BY — CODE 15B514
Federal Bureau of Prisons
FCI Seagoville
2113 N HWY 175
SEAGOVILLE, TX 75159-2237

10. THE ACQUISITION IS
- [X] SMALL BUSINESS
- [ ] HUBZONE SMALL BUSINESS
- [ ] SERVICE-DISABLED VETERAN-OWNED SMALL BUSINESS (SDVOSB)
- [ ] UNRESTRICTED OR
- [ ] WOMEN-OWNED SMALL BUSINESS (WOSB)
- [ ] ECONOMICALLY DISADVANTAGED WOMEN-OWNED SMALL BUSINESS (EDWOSB)
- [ ] 8(A)
- [X] SET ASIDE: 100.00 % FOR

NORTH AMERICAN INDUSTRY CLASSIFICATION STANDARD (NAICS): 236220
SIZE STANDARD:

11. DELIVERY FOR FREE ON BOARD (FOB) DESTINATION UNLESS BLOCK IS MARKED
- [ ] SEE SCHEDULE

12. DISCOUNT TERMS

- [ ] 13a. THIS CONTRACT IS A RATED ORDER UNDER THE DEFENSE PRIORITIES AND ALLOCATIONS SYSTEM - DPAS (15 CFR 700)

13b. RATING

14. METHOD OF SOLICITATION
- [X] REQUEST FOR QUOTE (RFQ)
- [ ] INVITATION FOR BID (IFB)
- [ ] REQUEST FOR PROPOSAL (RFP)

15. DELIVER TO — CODE 15B514
Federal Bureau of Prisons
FCI Seagoville
2113 N HWY 175
SEAGOVILLE, TX 75159-2237

16. ADMINISTERED BY — CODE 15B514
Federal Bureau of Prisons
FCI Seagoville
2113 N HWY 175
SEAGOVILLE, TX 75159-2237

17a. CONTRACTOR/ OFFEROR — CODE — FACILITY CODE

TELEPHONE NUMBER

- [ ] 17b. CHECK IF REMITTANCE IS DIFFERENT AND PUT SUCH ADDRESS IN OFFER

18a. PAYMENT WILL BE MADE BY — CODE 15B514
Federal Bureau of Prisons
FCI Seagoville
2113 N HWY 175
SEAGOVILLE, TX 75159-2237

- [ ] 18b. SUBMIT INVOICES TO ADDRESS SHOWN IN BLOCK 18a UNLESS BLOCK BELOW IS CHECKED — SEE ADDENDUM

19. ITEM NUMBER	20. SCHEDULE OF SUPPLIES/SERVICES	21. QUANTITY	22. UNIT	23. UNIT PRICE	24. AMOUNT
	FCI Seagoville Building Elevator Renovation - 26Z5AP9 OFFERORS MUST READ AND COMPLETE ALL SECTIONS OF THE SOLICITATION PACKET Firm Fixed Price See Continuation Sheet(s) (*Use Reverse and/or Attach Additional Sheets as Necessary*)				

25. ACCOUNTING AND APPROPRIATION DATA

26. TOTAL AWARD AMOUNT (*For Government Use Only*)

- [X] 27a. SOLICITATION INCORPORATES BY REFERENCE (FEDERAL ACQUISITION REGULATION) FAR 52.212-1, 52.212-4. FAR 52.212-3 AND 52.212-5 ARE ATTACHED. ADDENDA — [ ] ARE [X] ARE NOT ATTACHED
- [ ] 27b. CONTRACT/PURCHASE ORDER INCORPORATES BY REFERENCE FAR 52.212-4. FAR 52.212-5 IS ATTACHED. ADDENDA — [ ] ARE [ ] ARE NOT ATTACHED

- [ ] 28. CONTRACTOR IS REQUIRED TO SIGN THIS DOCUMENT AND RETURN ____ COPIES TO ISSUING OFFICE. CONTRACTOR AGREES TO FURNISH AND DELIVER ALL ITEMS SET FORTH OR OTHERWISE IDENTIFIED ABOVE AND ON ANY ADDITIONAL SHEETS SUBJECT TO THE TERMS AND CONDITIONS SPECIFIED.

- [ ] 29. AWARD OF CONTRACT: REFERENCE _____ OFFER DATED _____ . YOUR OFFER ON SOLICITATION (BLOCK 5) INCLUDING ANY ADDITIONS OR CHANGES WHICH ARE SET FORTH HEREIN, IS ACCEPTED AS TO ITEMS:

30a. SIGNATURE OF OFFEROR/CONTRACTOR	31a. UNITED STATES OF AMERICA (*SIGNATURE OF CONTRACTING OFFICER*)

30b. NAME AND TITLE OF SIGNER (*Type or print*)	30c. DATE SIGNED	31b. NAME OF THE CONTRACTING OFFICER (*Type or print*)	31c. DATE SIGNED

FCI Seagoville

Solicitation Packet

Project 26Z5AP9

Building Elevator Renovation

2113 N Highway 175,
Seagoville, TX 75159

PLEASE REVIEW AND COMPLETE ALL SECTIONS OF THE PACKET

Contractor Information Sheet

Please complete all sections

Contractor Name: _____

Contractor Address: _____

Contractor Phone Number: _____

Tax Identification Number: _____

Unique Entity Identifier: _____

(Formerly Duns)

Cage Code: _____

Contractor Signature: _____

Dear Offeror:

Please review all sections of this solicitation packet, the solicitation, and all attachments. This information is essential to submit a valid and complete offer.

The Federal Bureau of Prisons (FBOP) is issuing solicitation 15B51426Q00000025 for the award of a firm-fixed-price construction contract for a project entitled **Building Elevator Renovation** at the Federal Correctional Institution (FCI Seagoville), located in Seagoville, TX.

FCI Seagoville is a federal correctional facility located at 2113 N Highway 175, Seagoville, TX 75159. The Work of Project is defined by the Contract Documents and consists of the following:

All offers must come with an offer guarantee. All offers are also subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference. Offers must provide a minimum of 30 calendar days for Government acceptance after the date that offers are due. Offers that do not provide this minimum acceptance timeframe may be rejected. Should the offer be accepted within 30 calendar days following the date offers are due, offerors must also perform the work at the prices they specify on the attached SF-1449 solicitation document in strict accordance with the solicitation. The contractor will provide all necessary equipment, labor, materials, and incidentals unless stated otherwise in the Statement of Work. The successful Contractor shall provide all necessary engineering, specialized labor, certified materials, and equipment required to deliver a fully operational system. The modernized elevator must adhere to all ASME A17.1/CSA B44 Safety Codes, ADA Standards, and Manufacturer's Recommended Installation Practices located in Building 9.

There are no additional square footage or modifications to the primary structure, nor changes to the utilities to this project. See the Statement of

Work included with the solicitation posting for the complete requirements list.

The contractor is expected to begin work within 10 days of receiving the notice to proceed. The performance period for the project will be 336 Calendar Days from issuance of the notice to proceed.
The NAICS code for this requirement is 236220. Pursuant to Justice Acquisition Regulation (JAR) 2836.204, the estimated magnitude of the project lies between $100,000.00 and $170,000.00. (NOTE: This range is one of 5 available ranges from JAR 2836.204 and is not meant to imply that the project has necessarily been estimated/budgeted to the maximum of the selected range. It merely conveys that the estimate/budget lies somewhere within that range.)

IMPORTANT: Any contractor interested in obtaining a contract award with the Federal Bureau of Prisons must be registered in https://www.sam.gov. In order to qualify for award, your business size metrics information entered in your www.sam.gov SAM registration must be less than or equal to the size standard specified above.

Each offeror’s www.sam.gov registration will be reviewed by the Government to confirm that your business size meets the small business size standard requirement. All offerors are urged to double check their www.sam.gov registration and update as necessary, including the size metrics information.

This is a 100 percent small business set-aside. You must be registered in www.sam.gov as a small business for the applicable NAICS code (see FAR provision 52.219-1 in the Representations & Certifications section of your www.sam.gov registration).

System updates may lag policy updates. The System for Award Management (SAM) may continue to require entities to complete

representations based on provisions that are not included in agency solicitations. Examples include:
• 52.222-25, Affirmative Action Compliance, and
• 52.212-3, Offeror Representations and Certifications—Commercial Products and Commercial Services, paragraph (d).
• 52.223-22, Public Disclosure of Greenhouse Gas Emissions and Reduction Goals— Representation, and
• Paragraph (t) of 52.212-3, Offeror Representations and Certifications—Commercial Products and Commercial Services. Contracting officers will not consider these representations when making award decisions or enforce requirements. Entities are not required to, nor are they able to, update their entity registration to remove these representations in SAM

Pre-Bid Site Visit

(a) An organized site visit will be scheduled for September 8, 2026 at 9am. All potential bidders are highly encouraged to attend.
(b) Participants will meet at 2113 N Highway 175, Seagoville, TX 75159.
(c) A criminal history check must be completed for all site visit attendees, and all site visit attendees must pass the criminal history check. For convenience, the applicable form has been included to the attachments of this solicitation named “Criminal History Check Form”. Forms must be submitted to Camille Gonzalez at (c9gonzalez@bop.gov). All documents must be sent in PDF format.

Evaluation Factors

This acquisition will be utilizing FAR policy 15.101-1, Tradeoff process. Therefore, the award will be made on the basis of the lowest evaluated price of proposals meeting or exceeding the requirements for acceptability. To establish minimum requirements of performance, past performance and technical acceptability will also be evaluated.

Best Value Tradeoff

Under this method, the Government will evaluate quotes using the best value trade-off approach. The following evaluation factors that will be used are listed in descending order of importance:

Factor I – Technical / Management Approach: Evaluation of the Offeror's understanding of the work, construction phasing, site coordination, staffing plan, safety and quality control approach, and ability to perform while the facility remains operational. Offerors are required to provide a technical proposal addressing ability to perform all sections of the statement of work (SOW).

Factor II – Specialized Experience: Evaluation of the relevance and depth of experience on projects of similar size, scope, complexity, and security environment.

Factor III – Schedule: Evaluation of the realism, completeness, and feasibility of the proposed construction schedule, including identification of critical path activities.

Factor IV – Past Performance: Evaluation of prior performance information obtained from CPARS, PPQs, and other Government sources for similar construction projects.

Factor V – Price: Evaluation of price for reasonableness and consistency with the proposed technical approach.

Proposal Submission

All submissions must be emailed to Camille Gonzalez at (c9gonzalez@bop.gov). No call or fax submissions will be accepted for this acquisition. All documents must be sent in PDF format. All proposal submissions must be turned into this email no later than September 16, 2026, at 10:00 AM CST. Any late submissions are subject to not being accepted.

19. ITEM NUMBER	20. SCHEDULE OF SUPPLIES/SERVICES	21. QUANTITY	22. UNIT	23. UNIT PRICE	24. AMOUNT

32a. QUANTITY IN COLUMN 21 HAS BEEN

☐ RECEIVED ☐ INSPECTED ☐ ACCEPTED, AND CONFORMS TO THE CONTRACT, EXCEPT AS NOTED: _____

32b. SIGNATURE OF AUTHORIZED GOVERNMENT REPRESENTATIVE	32c. DATE	32d. PRINTED NAME AND TITLE OF AUTHORIZED GOVERNMENT REPRESENTATIVE
32e. MAILING ADDRESS OF AUTHORIZED GOVERNMENT REPRESENTATIVE		32f. TELEPHONE NUMBER OF AUTHORIZED GOVERNMENT REPRESENTATIVE 32g. E-MAIL OF AUTHORIZED GOVERNMENT REPRESENTATIVE

33. SHIP NUMBER ☐ PARTIAL ☐ FINAL	34. VOUCHER NUMBER	35. AMOUNT VERIFIED CORRECT FOR	36. PAYMENT ☐ COMPLETE ☐ PARTIAL ☐ FINAL	37. CHECK NUMBER
38. S/R ACCOUNT NUMBER	39. S/R VOUCHER NUMBER	40. PAID BY		

41a. I CERTIFY THIS ACCOUNT IS CORRECT AND PROPER FOR PAYMENT		42a. RECEIVED BY *(Print)*	
41b. SIGNATURE AND TITLE OF CERTIFYING OFFICER	41c. DATE	42b. RECEIVED AT *(Location)*	
		42c. DATE REC'D *(YY/MM/DD)*	42d. TOTAL CONTAINERS

Table of Contents

Section	Description	Page Number
	Solicitation/Contract Form	1
1	Commodity or Services Schedule	6
2	Contract Clauses	7
	52.202-1 Definitions (Jun 2020)	7
	52.203-3 Gratuities (Apr 1984)	7
	52.203-5 Covenant Against Contingent Fees (May 2014)	7
	52.203-6 Restrictions on Subcontractor Sales to the Government (Jun 2020)	7
	52.203-7 Anti-Kickback Procedures (Jun 2020)	7
	52.203-8 Cancellation, Rescission, and Recovery of Funds for Illegal or Improper Activity (May 2014)	7
	52.203-10 Price or Fee Adjustment for Illegal or Improper Activity (May 2014)	7
	52.203-12 Limitation On Payments to Influence Certain Federal Transactions (Jun 2020)	7
	52.203-17 Contractor Employee Whistleblower Rights (Nov 2023)	7
	52.204-9 Personal Identity Verification of Contractor Personnel (Jan 2011)	7
	52.204-13 (DEV) System for Award Management-Maintenance (Oct 2018) (DEVIATION NOV 2025)	7
	52.204-14 (DEV) Service Contract Reporting Requirements (Oct 2016) (DEVIATION NOV 2025)	7
	52.204-19 Incorporation by Reference of Representations and Certifications (Dec 2014)	8
	52.209-6 (DEV) Protecting the Government's Interest When Subcontracting with Contractors Debarred, Suspended, Proposed for Debarment, or Voluntarily Excluded (Jan 2025) (DEVIATION NOV 2025)	8
	52.209-9 (DEV) Updates of Publicly Available Information Regarding Responsibility Matters (Oct 2018) (DEVIATION NOV 2025)	8
	52.209-10 (DEV) Prohibition on Contracting With Inverted Domestic Corporations (Nov 2015) (DEVIATION NOV 2025)	8
	52.211-12 Liquidated Damages-Construction (Sept 2000)	8
	52.212-4 (DEV) Terms and Conditions-Commercial Products and Commercial Services (Nov 2023) (DEVIATION NOV 2025)	8
	52.215-21 (DEV) Requirements for Certified Cost or Pricing Data and Data Other Than Certified Cost or Pricing Data-Modifications (Nov 2021) (DEVIATION DEC 2025)	8
	52.215-21 Alt I (DEV) Requirements for Certified Cost or Pricing Data and Data Other Than Certified Cost or Pricing Data-Modifications (Nov 2021) - Alternate I (DEVIATION DEC 2025)	8
	52.219-14 (DEV) Limitations on Subcontracting (Oct 2022) (DEVIATION DEC 2025)	8
	52.222-1 (DEV) Notice to the Government of Labor Disputes (Feb 1997) (DEVIATION DEC 2025)	8
	52.222-3 (DEV) Convict Labor (June 2003) (DEVIATION DEC 2025)	8
	52.222-4 (DEV) Contract Work Hours and Safety Standards--Overtime Compensation (May 2018) (DEVIATION DEC 2025)	8
	52.222-7 (DEV) Withholding of Funds (May 2014) (DEVIATION DEC 2025)	8
	52.222-8 (DEV) Payrolls and Basic Records (Jul 2021) (DEVIATION DEC 2025)	9
	52.222-9 (DEV) Apprentices and Trainees (July 2005) (DEVIATION DEC 2025)	9
	52.222-10 (DEV) Compliance with Copeland Act Requirements (Feb 1988) (DEVIATION DEC 2025)	9
	52.222-11 (DEV) Subcontracts (Labor Standards) (May 2014) (DEVIATION DEC 2025)	9
	52.222-12 Contract Termination - Debarment (May 2014)	9
	52.222-14 (DEV) Disputes Concerning Labor Standards (Feb 1988) (DEVIATION DEC 2025)	9
	52.222-15 Certification of Eligibility (May 2014)	9
	52.222-35 (DEV) Equal Opportunity for Veterans (Jun 2020) (DEVIATION DEC 2025)	9
	52.222-37 (DEV) Employment Reports on Veterans (Jun 2020) (DEVIATION DEC 2025)	9
	52.222-40 (DEV) Notification of Employee Rights Under the National Labor Relations Act (Dec 2010) (DEVIATION DEC 2025)	9
	52.222-50 Alt I (DEV) Combating Trafficking in Persons (Oct 2025) - Alternate I (Mar 2015) (DEVIATION DEC 2025)	9

52.222-54 (DEV) Employment Eligibility Verification (Jan 2025) (DEVIATION DEC 2025)..... 9
52.222-55 (DEV) Minimum Wages for Contractor Workers Under Executive Order 14026 (Jan 2022) (DEVIATION DEC 2025)..... 9
52.222-62 (DEV) Paid Sick Leave Under Executive Order 13706 (Jan 2022) (DEVIATION DEC 2025)..... 9
52.222-90 Addressing DEI Discrimination by Federal Contractors (APR 2026)..... 9
52.223-5 Pollution Prevention and Right-to-Know Information (May 2024)..... 10
52.223-23 (DEV) Sustainable Products (May 2024) (DEVIATION DEC 2025)..... 10
52.226-7 Drug-Free Workplace (May 2024)..... 10
52.226-8 Encouraging Contractor Policies To Ban Text Messaging While Driving (May 2024)..... 10
52.227-1 Authorization and Consent (Jun 2020)..... 10
52.227-2 Notice and Assistance Regarding Patent and Copyright Infringement (Jun 2020)..... 10
52.228-2 Additional Bond Security (Oct 1997)..... 10
52.228-5 Insurance-Work on a Government Installation (Jan 1997)..... 10
52.228-11 Individual Surety-Pledge of Assets (Feb 2021)..... 10
52.228-12 Prospective Subcontractor Requests for Bonds (Dec 2022)..... 10
52.228-14 Irrevocable Letter of Credit (Nov 2014)..... 10
52.229-3 (DEV) Federal, State, And Local Taxes (Feb 2013) (DEVIATION AUG 2025)..... 10
52.229-12 (DEV) Tax on Certain Foreign Procurements (Feb 2021) (DEVIATION AUG 2025)..... 10
52.232-17 Interest (May 2014)..... 10
52.232-23 Assignment of Claims (May 2014)..... 10
52.232-33 Payment by Electronic Funds Transfer-System for Award Management (Oct 2018)..... 10
52.232-39 Unenforceability of Unauthorized Obligations (Jun 2013)..... 10
52.232-40 Providing Accelerated Payments to Small Business Subcontractors (Mar 2023)..... 10
52.233-1 Alt I (DEV) Disputes (May 2014) - Alternate I (Dec 1991) (DEVIATION NOV 2025)..... 10
52.233-3 (DEV) Protest after Award (Aug 1996) (DEVIATION NOV 2025)..... 11
52.233-4 (DEV) Applicable Law for Breach of Contract Claim (Oct 2004) (DEVIATION NOV 2025)..... 11
52.236-2 (DEV) Differing Site Conditions (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-5 (DEV) Material and Workmanship (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-6 (DEV) Superintendence by the Contractor (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-7 (DEV) Permits and Responsibilities (Nov 1991) (DEVIATION AUG 2025)..... 11
52.236-8 (DEV) Other Contracts (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-9 (DEV) Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-10 (DEV) Operations and Storage Areas (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-11 (DEV) Use and Possession Prior to Completion (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-12 (DEV) Cleaning Up (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-13 (DEV) Accident Prevention (Nov 1991) (DEVIATION AUG 2025)..... 11
52.236-14 (DEV) Availability and Use of Utility Services (Apr 1984) (DEVIATION AUG 2025)..... 11
52.236-17 (DEV) Layout of Work (Apr 1984) (DEVIATION AUG 2025)..... 11
52.242-13 Bankruptcy (July 1995)..... 11
52.243-4 (DEV) Changes (June 2007) (DEVIATION JUL 2025)..... 11
52.244-6 (DEV) Subcontracts for Commercial Products and Commercial Services (Jan 2025) (DEVIATION APR 2026)..... 11
52.249-2 Termination for Convenience of the Government (Fixed-Price) (Apr 2012)..... 11
52.252-6 Authorized Deviations in Clauses (Nov 2020)..... 12
52.253-1 (DEV) Computer Generated Forms (Jan 1991) (DEVIATION NOV 2025)..... 12
DOJ-01 Whistleblower Information Distribution (Oct 2021)..... 12
DOJ-02 Contractor Privacy Requirements (JAN 2022)..... 12
DOJ-03 Personnel Security Requirements For Contractor Employees (Nov 2021)..... 12

DOJ-08 Continuing Contract Performance During a Pandemic Influenza or other National Emergency (OCT 2007)....12
DOJ-05 Security of Department Information and Systems (APR 2026)....12
FAO-0001 Bonds....19
FAO-0002 Magnitude....20
FAO-0003 Required Insurance....20
FAO-0004 Pre-Construction Conference....21
FAO-0005 Submittals....21
FAO-0006 Contractor Use of Premises....22
FAO-0007 Payment Services....23
FAO-0008 Request for Final Inspection....23
FAO-0009 Contract Security (Program Statement 3000.03 Human Resource Management Manual)....23
FAO-0010 Assignment of Contract Administration Office and Functions....23
FAO-0011 Schedule of Values....24
FAO-0012 Progress Meetings....24
FAO-0013 Contract Closeout Procedures (for construction contracts exceeding $150,000)....25
FAO-0014 Contract Closeout Procedures (for construction contracts $150,000 or less)....26
FAO-0015 Changes....26
FAO-0016 Equitable Adjustments: Waiver and Release of Claims....28
List of Attachments....29
Solicitation Provisions....30

Section 1 - Commodity or Services Schedule

SCHEDULE OF SUPPLIES/SERVICES

CONTINUATION SHEET

ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0001	The selected contractor shall provide all materials, labor, and equipment to complete the project "Building Elevator Renovation" at FCI Seagoville in accordance with the attached Statement of Work. PSC: Z2FF **Delivery Schedule:** **Delivery Description:** Delivery Number: 1 Delivery Estimated By: 07/27/2027 Quantity: 0.000000 Delivery Address: Federal Bureau of Prisons FCI Seagoville 2113 N HWY 175 SEAGOVILLE, TX 75159-2237	1	EA	$_____	$_____

The selected contractor shall provide all materials, labor, and equipment to complete the project "Building Elevator Renovation" at FCI Seagoville in accordance with the attached Statement of Work.

Section 2 - Contract Clauses

A.1 ADDENDUM TO FAR 52.212-4, Terms and Conditions-Commercial Products and Commercial Services (Nov 2023) (DEVIATION NOV 2025)

The terms and conditions for the following clauses are hereby incorporated into this solicitation and resulting contract as an addendum to FAR clause 52.212-4.

Clauses By Reference

52.252-2 CLAUSES INCORPORATED BY REFERENCE (FEB 1998)		
This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es): www.acquisition.gov		
Clause	Title	Fill-ins (if applicable)
52.202-1	Definitions (Jun 2020)	
52.203-3	Gratuities (Apr 1984)	
52.203-5	Covenant Against Contingent Fees (May 2014)	
52.203-6	Restrictions on Subcontractor Sales to the Government (Jun 2020)	
52.203-7	Anti-Kickback Procedures (Jun 2020)	
52.203-8	Cancellation, Rescission, and Recovery of Funds for Illegal or Improper Activity (May 2014)	
52.203-10	Price or Fee Adjustment for Illegal or Improper Activity (May 2014)	
52.203-12	Limitation On Payments to Influence Certain Federal Transactions (Jun 2020)	
52.203-17	Contractor Employee Whistleblower Rights (Nov 2023)	
52.204-9	Personal Identity Verification of Contractor Personnel (Jan 2011)	
52.204-13 (DEV)	System for Award Management-Maintenance (Oct 2018) (DEVIATION NOV 2025)	

Clause	Title	Fill-ins (if applicable)
52.204-14 (DEV)	Service Contract Reporting Requirements (Oct 2016) (DEVIATION NOV 2025)	
52.204-19	Incorporation by Reference of Representations and Certifications (Dec 2014)	
52.209-6 (DEV)	Protecting the Government's Interest When Subcontracting with Contractors Debarred, Suspended, Proposed for Debarment, or Voluntarily Excluded (Jan 2025) (DEVIATION NOV 2025)	
52.209-9 (DEV)	Updates of Publicly Available Information Regarding Responsibility Matters (Oct 2018) (DEVIATION NOV 2025)	
52.209-10 (DEV)	Prohibition on Contracting With Inverted Domestic Corporations (Nov 2015) (DEVIATION NOV 2025)	
52.211-12	Liquidated Damages-Construction (Sept 2000)	(a): " $ 1,873.88"
52.212-4 (DEV)	Terms and Conditions-Commercial Products and Commercial Services (Nov 2023) (DEVIATION NOV 2025)	
52.215-21 (DEV)	Requirements for Certified Cost or Pricing Data and Data Other Than Certified Cost or Pricing Data-Modifications (Nov 2021) (DEVIATION DEC 2025)	
52.215-21 Alt I (DEV)	Requirements for Certified Cost or Pricing Data and Data Other Than Certified Cost or Pricing Data-Modifications (Nov 2021) - Alternate I (DEVIATION DEC 2025)	
52.219-14 (DEV)	Limitations on Subcontracting (Oct 2022) (DEVIATION DEC 2025)	(f)(1) End of Base Term: "X"
52.222-1 (DEV)	Notice to the Government of Labor Disputes (Feb 1997) (DEVIATION DEC 2025)	
52.222-3 (DEV)	Convict Labor (June 2003) (DEVIATION DEC 2025)	
52.222-4 (DEV)	Contract Work Hours and Safety Standards--Overtime Compensation (May 2018) (DEVIATION DEC 2025)	

Clause	Title	Fill-ins (if applicable)
52.222-7 (DEV)	Withholding of Funds (May 2014) (DEVIATION DEC 2025)	
52.222-8 (DEV)	Payrolls and Basic Records (Jul 2021) (DEVIATION DEC 2025)	
52.222-9 (DEV)	Apprentices and Trainees (July 2005) (DEVIATION DEC 2025)	
52.222-10 (DEV)	Compliance with Copeland Act Requirements (Feb 1988) (DEVIATION DEC 2025)	
52.222-11 (DEV)	Subcontracts (Labor Standards) (May 2014) (DEVIATION DEC 2025)	
52.222-12	Contract Termination - Debarment (May 2014)	
52.222-14 (DEV)	Disputes Concerning Labor Standards (Feb 1988) (DEVIATION DEC 2025)	
52.222-15	Certification of Eligibility (May 2014)	
52.222-35 (DEV)	Equal Opportunity for Veterans (Jun 2020) (DEVIATION DEC 2025)	
52.222-37 (DEV)	Employment Reports on Veterans (Jun 2020) (DEVIATION DEC 2025)	
52.222-40 (DEV)	Notification of Employee Rights Under the National Labor Relations Act (Dec 2010) (DEVIATION DEC 2025)	
52.222-50 Alt I (DEV)	Combating Trafficking in Persons (Oct 2025) - Alternate I (Mar 2015) (DEVIATION DEC 2025)	
52.222-54 (DEV)	Employment Eligibility Verification (Jan 2025) (DEVIATION DEC 2025)	
52.222-55 (DEV)	Minimum Wages for Contractor Workers Under Executive Order 14026 (Jan 2022) (DEVIATION DEC 2025)	
52.222-62 (DEV)	Paid Sick Leave Under Executive Order 13706 (Jan 2022) (DEVIATION DEC 2025)	

Clause	Title	Fill-ins (if applicable)
52.222-90	Addressing DEI Discrimination by Federal Contractors (APR 2026)	
52.223-5	Pollution Prevention and Right-to-Know Information (May 2024)	
52.223-23 (DEV)	Sustainable Products (May 2024) (DEVIATION DEC 2025)	
52.226-7	Drug-Free Workplace (May 2024)	
52.226-8	Encouraging Contractor Policies To Ban Text Messaging While Driving (May 2024)	
52.227-1	Authorization and Consent (Jun 2020)	
52.227-2	Notice and Assistance Regarding Patent and Copyright Infringement (Jun 2020)	
52.228-2	Additional Bond Security (Oct 1997)	
52.228-5	Insurance-Work on a Government Installation (Jan 1997)	
52.228-11	Individual Surety-Pledge of Assets (Feb 2021)	
52.228-12	Prospective Subcontractor Requests for Bonds (Dec 2022)	
52.228-14	Irrevocable Letter of Credit (Nov 2014)	
52.229-3 (DEV)	Federal, State, And Local Taxes (Feb 2013) (DEVIATION AUG 2025)	
52.229-12 (DEV)	Tax on Certain Foreign Procurements (Feb 2021) (DEVIATION AUG 2025)	
52.232-17	Interest (May 2014)	
52.232-23	Assignment of Claims (May 2014)	
52.232-33	Payment by Electronic Funds Transfer-System for Award Management (Oct 2018)	
52.232-39	Unenforceability of Unauthorized Obligations (Jun 2013)	
52.232-40	Providing Accelerated Payments to Small Business Subcontractors (Mar 2023)	

Clause	Title	Fill-ins (if applicable)
52.233-1 Alt I (DEV)	Disputes (May 2014) - Alternate I (Dec 1991) (DEVIATION NOV 2025)	
52.233-3 (DEV)	Protest after Award (Aug 1996) (DEVIATION NOV 2025)	
52.233-4 (DEV)	Applicable Law for Breach of Contract Claim (Oct 2004) (DEVIATION NOV 2025)	
52.236-2 (DEV)	Differing Site Conditions (Apr 1984) (DEVIATION AUG 2025)	
52.236-5 (DEV)	Material and Workmanship (Apr 1984) (DEVIATION AUG 2025)	
52.236-6 (DEV)	Superintendence by the Contractor (Apr 1984) (DEVIATION AUG 2025)	
52.236-7 (DEV)	Permits and Responsibilities (Nov 1991) (DEVIATION AUG 2025)	
52.236-8 (DEV)	Other Contracts (Apr 1984) (DEVIATION AUG 2025)	
52.236-9 (DEV)	Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements (Apr 1984) (DEVIATION AUG 2025)	
52.236-10 (DEV)	Operations and Storage Areas (Apr 1984) (DEVIATION AUG 2025)	
52.236-11 (DEV)	Use and Possession Prior to Completion (Apr 1984) (DEVIATION AUG 2025)	
52.236-12 (DEV)	Cleaning Up (Apr 1984) (DEVIATION AUG 2025)	
52.236-13 (DEV)	Accident Prevention (Nov 1991) (DEVIATION AUG 2025)	
52.236-14 (DEV)	Availability and Use of Utility Services (Apr 1984) (DEVIATION AUG 2025)	
52.236-17 (DEV)	Layout of Work (Apr 1984) (DEVIATION AUG 2025)	
52.242-13	Bankruptcy (July 1995)	
52.243-4 (DEV)	Changes (June 2007) (DEVIATION JUL 2025)	
52.244-6 (DEV)	Subcontracts for Commercial Products and Commercial Services (Jan 2025) (DEVIATION APR 2026)	

Clause	Title	Fill-ins (if applicable)
52.249-2	Termination for Convenience of the Government (Fixed-Price) (Apr 2012)	
52.252-6	Authorized Deviations in Clauses (Nov 2020)	
52.253-1 (DEV)	Computer Generated Forms (Jan 1991) (DEVIATION NOV 2025)	
DOJ-01	Whistleblower Information Distribution (Oct 2021)	
DOJ-02	Contractor Privacy Requirements (JAN 2022)	
DOJ-03	Personnel Security Requirements For Contractor Employees (Nov 2021)	
DOJ-08	Continuing Contract Performance During a Pandemic Influenza or other National Emergency (OCT 2007)	

Clauses By Full Text

52.252-2 Clauses Incorporated by Reference (Feb 1998)

This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):

https://www.acquisition.gov/
https://www.acquisition.gov/sites/default/files/page_file_uploads/far-companion.pdf

_____
[Insert one or more Internet addresses]

(End of clause)

DOJ-05 Security of Department Information and Systems (APR 2026)

I. Applicability to Contractors and Subcontractors
Section 2839.102 of the Justice Acquisition Regulation (JAR), (48 C.F.R. § 2839.102), applies to this contract. Accordingly, all contractors are obligated to comply with all applicable DOJ security policies, directives, or guidance documents, including the security requirements in the provisions in this contract clause. This contract clause applies to all contractors and subcontractors, including cloud service providers (“CSPs”), and personnel of the contractors and subcontractors (hereinafter collectively, “Contractor”) that may access, collect, store, process, maintain, use, share, retrieve, disseminate, transmit, or dispose of DOJ Information. The security requirements set forth herein are in addition to those required by the Federal Acquisition Regulation (“FAR”), and any other applicable laws, mandates, contract clauses, DOJ policies, directives or guidance documents and Executive Orders pertaining to the development and operation of Information Systems and/or the protection of Government Information. This clause does not alter or diminish any existing rights, obligations, or liability under any other civil and/or criminal law, rule, regulation, or mandate.

II. General Definitions
The following general definitions apply to this clause. Specific definitions also apply as set forth in other paragraphs.

A. **Authorization to Operate** (“ATO”), as defined in National Institute of Standards and Technology (“NIST”) Special Publication (“SP”) 800-37 Revision 2, is the official management decision given by a senior Federal official or officials to authorize operation of an information system and to explicitly accept the risk to agency operations (including mission, functions, image, or reputation), agency assets, individuals, other organizations, and the Nation based on the implementation of an agreed-upon set of security and privacy controls.

B. **Cloud Computing**, as defined in DOJ Order 0904 Cybersecurity Program, is a model for enabling ubiquitous, convenient, on-demand network access to a shared pool of configurable computing resources (e.g., networks, servers, storage, applications, and services) that can be rapidly provisioned and released with minimal management effort or service provider interaction. This cloud model is composed of five essential characteristics, three service models, and four deployment models in accordance with NIST SP 800-145.

C. **Covered Contract** is any contract, order or other agreement under which the contractor, or a subcontractor at any tier, including a cloud service provider, may access, collect, store, process, maintain, use, share, retrieve, disseminate, transmit, or dispose of DOJ Information (as defined below) in the course of providing a product or service to the Department, with the exception of acquisitions under the micro-purchase threshold.

D. **Covered Information System** means any information system used for, involved with, or allowing, the processing, storing, or transmitting of DOJ Information under a Covered Contract.

E. **Data** means recorded information, regardless of form or the media on which it may be recorded. The term includes technical data, computer software, and personally identifiable information (PII) (defined below). The term does not include information incidental to contract administration, such as financial, administrative, cost or pricing, or management information.

F. **DOJ Information**, as defined in DOJ Order 0904, means any Information that is owned, produced, controlled, protected by, or otherwise within the custody or responsibility of the DOJ, including, without limitation, information related to DOJ programs or personnel. It includes, without limitation, Information (1) provided by or generated for the DOJ, (2) managed or acquired by the Contractor for the DOJ in connection with the performance of the contract, and/or (3) acquired to perform the contract.

G. **Information**, as defined in DOJ Order 0904, is any communication or representation of knowledge such as facts, data, or opinions, in any form or medium, including textual, numerical, graphic, cartographic, narrative, or audiovisual. This includes any communication or representation of knowledge in an electronic format that allows it to be stored, retrieved, or transmitted.

H. **Information System**, means a discrete set of information resources organized for the collection, processing, maintenance, use, sharing, dissemination, or disposition of information (44 U.S.C. 3502(8)).

I. **Personally Identifiable Information** (“PII”), as defined in the FAR 24.101, means information that can be used to distinguish or trace an individual's identity, either alone or when combined with other information that is linked or linkable to a specific individual. It includes but is not limited to common data elements such as names, addresses, dates of birth, and places of employment, to identity documents, Social Security numbers or other government-issued identifiers, precise location information, medical history, and biometric records. This definition covers all PII that is created by or becomes available to the contractor, including its employees, subcontractors, or affiliates, as a result of performing under this contract. PII, as supplementally defined in DOJ Order 0904, also includes information about an individual maintained by an agency, including, but not limited to, information related to education, financial transactions, medical history, and criminal or employment history and information, which can be used to distinguish or trace an individual’s identity.

J. **Private Cloud**, as defined in NIST SP 800-145, is the deployment model for cloud infrastructure provisioned for exclusive use by a single organization comprising multiple consumers (e.g., business units). It may be owned, managed, and operated by the organization, a third party, or some combination of them, and it may exist on or off premises.

K. **Security Breach** means any security incident (as defined below) that directly relates to the loss of control, compromise, exfiltration, manipulation, unauthorized disclosure, unauthorized acquisition, unauthorized exposure or unauthorized access or any similar occurrence of any Covered Information System or any DOJ Information or any PII accessed by, retrievable from, processed by, stored on, or transmitted within, to or from any such system. This includes incidents where (1) a person other than an authorized user accesses or potentially accesses PII or DOJ Information or (2) an authorized user accesses or potentially accesses PII or DOJ Information for an unauthorized purpose.

a. **Potential Security Breach** (hereinafter, “Potential Breach”) means any suspected, but unconfirmed security breach (as defined above).
b. **Confirmed Security Breach** (hereinafter, “Confirmed Breach”) means any confirmed security breach (as defined above).

L. **Security Incident** means any occurrence that (1) may actually or imminently jeopardize, without lawful authority, the availability, integrity, authentication, confidentiality, or nonrepudiation of DOJ Information or a Covered Information System; or (2) may constitute a violation or imminent threat of violation of law, security policies, security procedures, or acceptable use policies.

a. **Potential Security Incident** means any suspected, but unconfirmed security incident (as defined above).
b. **Confirmed Security Incident** means any confirmed security incident (as defined above).

M. **Vulnerability**, as defined in DOJ Vulnerability Management Plan, and the OCIO Information Security Management Procedure, means a weakness or flaw discovered in the design of a system that, when exploited, may result in a loss of confidentially, integrity, or availability of DOJ Information or an Information System.

III. Confidentiality and Non-Disclosure of DOJ Information

A. Preliminary and final contract deliverables and all associated working papers and material generated by the Contractor developed using DOJ Information, product, source code, and/or methods of operations, are the property of the U.S. Government and must be submitted to the Contracting Officer (“CO”) or the CO’s Representative (“COR”) at the conclusion of the contract. The U.S. Government has unlimited data rights to all such deliverables and associated working papers and materials in accordance with FAR 52.227-14 (Rights in Data-General). The Contractor will define a method of monitoring the development activity to include any activity associated with DOJ Information, product, source code, and methods of operations. The data rights and development details shall be defined within the Contract.

If the Contractor intends to utilize its existing data, for which it has a patent or copyright, to develop a contract deliverable, it is incumbent upon the Contractor to negotiate with the CO the proper FAR Part 27 clauses in the contract to protect its existing data.

B. Pursuant to FAR 52.227-14(d)(2), all documents and data produced in the performance of this contract containing DOJ Information, product code, source code, and/or methods of operations are the property of the U.S. Government and, without the prior written permission of the CO, the Contractor shall neither reproduce nor release such information to any third-party at any time, including during performance or following expiration and/or termination of the contract.

C. Any DOJ Information made available to the Contractor under this contract shall be used only for the purpose of performance of this contract and shall not be divulged or made known in any manner to any persons except as may be necessary in the performance of this contract. In performance of this contract, the Contractor assumes responsibility for the protection of the confidentiality of all DOJ Information processed, stored, or transmitted by the Contractor. The Contractor shall comply with information security responsibilities and duties throughout the contract and after expiration/ termination as appropriate per contract close-out activities. When requested by the CO (typically no more than annually), the Contractor shall provide a report to the CO identifying, to the best of the Contractor’s knowledge and belief, the type, amount, and level of sensitivity of the DOJ Information processed, stored, or transmitted under the Contract, including an estimate of the number of individuals for whom PII has been processed, stored or transmitted under the Contract and whether such information includes social security numbers (in whole or in part).

IV. Compliance with Information Technology Security Policies, Procedures and Requirements

A. For all Covered Information Systems, in addition to any other applicable requirements, as set forth in Part I, the Contractor shall comply with the security requirements of the Federal Information Security Modernization Act of 2014 (“FISMA”), Privacy Act of 1974, E-Government Act of 2002, National Institute of Standards and Technology (“NIST”) Special Publications (“SP”), including NIST SP 800-37, 800-53, and 800-60 Volumes I and II, Federal Information Processing Standards (“FIPS”) Publications 140-2, 199, and 200, Federal Risk and Authorization Management Program (“FedRAMP”), DOJ IT Security Standards as amended, and OMB Memoranda relating to the security of information and/ or Federal Information Systems.

B. In addition, for all Covered Information Systems, the Contractor shall comply with the following requirements, which are listed here only to highlight certain specific applicable requirements from one of the sources identified in the first paragraph of this Section. This is not an exhaustive list of all such requirements with which the Contractor is obligated to comply, and the omission of a requirement from this list should not be construed as negating the materiality of that requirement. These requirements and those in the authorities in the prior paragraph should be read together.

1. Limiting access to DOJ Information and Covered Information Systems to authorized users and to transactions and functions that authorized users are permitted to exercise.
2. Providing security awareness training at least annually to all Contractor employees and contractors involved with the Covered Contract. Such training shall include, but not be limited to, recognizing and reporting potential indicators of insider threats to users and managers of DOJ Information and Covered Information Systems.
3. Creating, protecting, and retaining, in accordance with applicable requirements but in any event at least until the expiration of the contract, Covered Information System audit records, reports, and supporting documentation to enable reviewing, monitoring, analysis, investigation, reconstruction, and reporting of unlawful, unauthorized, or inappropriate activity related to such Covered Information Systems and/or DOJ Information.
4. Maintaining authorizations to operate any Covered Information System.
5. Performing continuous monitoring on all Covered Information Systems, to include but not be limited to, collecting, reviewing, and analyzing appropriate logs and timely investigating security alerts and potential security incidents.
6. Establishing and maintaining baseline configurations and current inventories of Covered Information Systems, including hardware, software, firmware, and documentation, throughout the Information System Development Lifecycle, and establishing and enforcing security configuration settings for IT products employed in Covered Information Systems.
7. Ensuring appropriate contingency planning has been performed, including DOJ Information and Covered Information System backups.
8. Identifying Covered Information System users, processes acting on behalf of users, or devices, and authenticating and verifying the identities of such users, processes, or devices, using multifactor authentication or HSPD-12 compliant authentication methods as defined by NIST 800-63-3, Digital Identity Guidelines or current revision.
9. Establishing and maintaining an operational incident handling capability for Covered Information Systems that includes adequate and timely development, logging, detection, analysis, containment, recovery, and user response activities, and tracking, documenting, and timely reporting incidents to appropriate officials and authorities within the Contractor's organization and the DOJ.
10. Performing periodic and timely maintenance on Covered Information Systems, and providing effective controls on tools, techniques, mechanisms, and personnel used to conduct such maintenance.
11. Protecting Covered Information System media containing DOJ Information, including paper, digital and electronic media, and DOJ assets under Contractor control; protecting them from environmental impacts, access, and equipment positioning requirements defined; limiting access to DOJ Information to authorized users; and sanitizing or destroying Covered Information System media containing DOJ Information before disposal, release or reuse of such media.
12. Limiting physical access to Covered Information Systems, equipment, and physical facilities housing such Covered Information Systems to authorized personnel according to DOJ 03.
13. Screening individuals prior to authorizing access to Covered Information Systems to ensure compliance with DOJ Security standards including personnel background checks.
14. Continuously assessing the risk to DOJ Information in Covered Information Systems, including scanning and remediating vulnerabilities, or implementing appropriate mitigation in accordance with DOJ policy, and ensuring the timely removal of assets no longer supported by the Contractor.
15. Continuously monitoring the application of security controls of Covered Information Systems, assessing the efficacy of such controls, and developing and implementing plans of action designed to correct deficiencies and eliminate or reduce vulnerabilities in such Covered Information Systems.
16. Monitoring, controlling, and protecting information transmitted or received by Covered Information Systems at the external boundaries and key internal boundaries of such Covered Information Systems, and employing architectural designs, software development techniques, and systems engineering principles that promote effective security.
17. Identifying, reporting, and correcting Covered Information System security flaws in a timely manner, providing protection from malicious code at appropriate locations, monitoring security alerts and advisories and taking appropriate and timely action in response.
18. Ensuring return of Government Furnished Equipment ("GFE") and/or PIV card assets within 10 business days of notification for end of use (contract end, staff change, etc.).
19. Complying with rights in data (FAR 52.227-14) as to the development, management, and protection of DOJ Information.
20. Reporting on risks or known issues impacting DOJ Services (staffing, hardware, process, changes, etc.) through the Contractor's CO or COR, DOJ Service Owner ("SO"), and Government Technical Manager ("GTM") including risk mitigation activities.
21. Reporting through the Contractor's CO or COR on any projected or planned changes in corporate ownership, covered information system design, and/or any technical changes that could impact the confidentiality, integrity

or availability of DOJ Information, data, or systems. Changes to system design must be updated through the authorization process per NIST SP 800-37 Revision 2, Step 6 (“Continuous Monitoring”) or current NIST revision.

22. When, as part of operating within the DOJ environment, the Contractor’s covered information system is subject to review, audit, or assessment by third parties, facilitating DOJ access to information system resources, facilities, personnel, and documentation in a timely manner as required by the auditors. Should a third-party organization conduct a review of any Covered Information System, the Contractor must provide a copy of the report to DOJ, through the CO and COR.
23. To enhance software supply chain and transparency, upon request, the Contractor shall provide a current Software Bill of Materials (SBOM) for all software, software updates, modules, libraries, and container images delivered or operated in the performance of this contract, consistent with applicable federal policy such as the National Telecommunications and Information (NTIA)-established minimum elements for SBOM to the CO who will refer to the DOJ Cyber-Security Risk Management team (C-SCRM) [Authority: OMB M-26-05; EO 14028/ NTIA minimum requirements].
24. Reporting on outages impacting DOJ Services through the Contractor’s CO, COR, and DOJ Service Owner (SO) to include event and mitigation details.

C. The Contractor shall not process, store, or transmit DOJ Information using a Covered Information System without first obtaining an ATO for each Covered Information System. The ATO shall be signed by the Authorizing Official for the DOJ component responsible for maintaining the security, confidentiality, integrity, and availability of the DOJ Information under this contract. (For Cloud Computing Systems, see Section V, below.)

D. The Contractor shall ensure compliance with DOJ-03 (Personnel Security Requirements for Contractor Employees) as to all Covered Information Systems.

E. When requested by the DOJ CO or COR as described below, the Contractor shall provide DOJ, including the Office of Inspector General (“OIG”) and Federal law enforcement components, (1) access to any and all information and records, including electronic information, regarding a Covered Information System, and (2) physical access to the Contractor’s facilities, installations, systems, operations, documents, records, and databases. Such access may include independent validation testing of controls, system penetration testing, and FISMA data reviews by DOJ or agents acting on behalf of DOJ, and such access shall be provided within 72 hours of the request. Additionally, the Contractor shall cooperate with DOJ’s efforts to ensure, maintain, and safeguard the security, confidentiality, integrity, and availability of DOJ Information.

F. The use of Contractor-owned laptops or other portable digital or electronic media to process or store DOJ Information covered by this clause or access a Covered Information System is prohibited unless the CO approves it in writing after the Contractor has provided a letter certifying compliance with the following requirements. For any requirements which include the use or storage of PII, the Senior Component Official for Privacy must also approve. Any additional requirements set forth for the use or storage of PII under DOJ-02, Contractor Privacy Requirements, are in addition to, not superseded by, the requirements set forth here.

1. Media must be encrypted using a NIST FIPS 140-2 approved product.
2. The Contractor must develop and implement a process to ensure that security and other applications software is kept up to date.
3. Where applicable, media must utilize antivirus software and a host-based firewall mechanism.
4. The Contractor must log all computer-readable data extracts from databases holding DOJ Information and verify that each extract including such data has been erased within 90 days of extraction or that its use is still required. All DOJ Information should be treated by the Contractor as sensitive information unless specifically designated as non-sensitive by the DOJ.
5. A Rules of Behavior (ROB) form must be signed and acknowledged annually by users. These rules must address, at a minimum, authorized, and official use, prohibition against unauthorized users and use, and the protection of DOJ Information. The form also must notify the users that they have no reasonable expectation of privacy regarding any communications transmitted through or data stored on Contractor-owned laptops or other portable digital or electronic media.
6. Cybersecurity Awareness Training (CSAT) shall be provided annually by Contractor for all users of Covered Information System. This training must be submitted to, and approved by, the CO or COR in advance of being provided to users. Users must complete and acknowledge having received CSAT each year. At a minimum, CSAT provided by contractors must include:
    a. Insider Threat Detection and Reporting – Importance of detecting, methodologies, indicators, and reporting

b. Privacy Awareness – Privacy Act and PII
c. General Cybersecurity – Information security, trends in advance persistent threats, social engineering/phishing, appropriate use, mobile devices, remote access, basic security best practices

G. Contractors shall not store DOJ information on Contractor-owned removable IT (e.g., media such as a thumb drive or external hard drive) unless expressly authorized in writing by the DOJ CO or COR in the performance of their contract.

H. When no longer needed, all media must be processed (sanitized, degaussed, or destroyed) in accordance with NIST SP 800-88, Guidelines for Media Sanitization.

I. The Contractor must keep an accurate inventory of digital or electronic media used in the performance of DOJ contracts.

J. The Contractor must remove all DOJ Information from Contractor media and return all such information to the DOJ within 10 days of the expiration or termination of the contract, unless otherwise extended by the CO, or waived (in part or whole) by the CO, and all such information shall be returned in a format and form acceptable to DOJ. The Contractor shall provide a written certification certifying the removal and return of all such information to the CO within 10 business days of the removal and return of all DOJ Information.

K. DOJ, at its discretion, may suspend the Contractor's access to any DOJ Information, or terminate the contract, when DOJ suspects that the Contractor has failed to comply with any security requirement, or in the event of an Information System Security Incident or Security Breach (see definitions above), where the Department determines that either event gives cause for such action. The suspension of access to DOJ Information may last until such time as DOJ, in its sole discretion, determines that the situation giving rise to such action has been corrected or no longer exists. Any termination action taken because of the Contractor's suspected failure to comply with any security requirement will be conducted in accordance with the applicable termination clause governing the awarded contract. The Contractor understands that any suspension or termination in accordance with this provision shall be at no cost to DOJ, and that upon request by the CO, the Contractor must immediately return all DOJ Information to DOJ, as well as any media upon which DOJ Information resides, at the Contractor's expense. The Contractor must comply with FAR 52.227-14 (Rights in Data), FAR 52.245-1 (Government Property), DOJ 2400.3A Chapter 1 (component property procedures), and FAR 4.804-5(a)(6) (Procedures for closing out contract files).

V. Cloud Computing

A. The Contractor may not utilize the Cloud system of any Cloud Service Provider ("CSP") unless:

1. 1. All of the following has occurred: (a) the Cloud system and CSP have been evaluated by a Third Party Assessing Organization ("3PAO") certified under FedRAMP; (b) the Cloud system received FedRAMP authorization; (c) the Contractor has provided the most current System Security Plan ("SSP") and Security Assessment Report ("SAR") to the DOJ CO for consideration, and provides any subsequent SSPs and SARs within 30 days of issuance; and, (d) the Authorizing Official for the DOJ component responsible for maintaining the security confidentiality, integrity, and availability of the DOJ Information under the Covered Contract has issued an ATO; or,
   2. In cases where the CSP or its offering is not FedRAMP authorized, the COR approves utilization of the Cloud System after the CSP has worked with the authorizing official, the DOJ OCIO, and the FedRAMP Program Management Office to determine that the CSP is likely to seek and receive Agency/FedRAMP authorization within 1 year, or DOJ has authorized use as a Private Cloud or Contractor Owned, Contractor Operated system.

B. The Contractor must ensure that the CSP allows DOJ to access and retrieve any DOJ Information processed, stored, or transmitted in a Cloud system under this Contract within a reasonable time of any such request, but in no event less than 48 hours from the request. To ensure that the DOJ can fully and appropriately search and retrieve DOJ Information from the Cloud system, access shall include any schemas, meta-data, and other associated data artifacts.

C. The Contractor must ensure that the CSP provides access and information to support and enable DOJ's cloud security posture management, to include the current inventory of security management configuration data for services and information to confirm the Contractor has been monitoring accounts for compliance with security requirements. The DOJ Justice Security Operations Center (JSOC) must be able to access logs and events to investigate potential security breaches and perform security posture assessments associated with the Security Audit Identity Credential Access Management (ICAM) policies.

D. The Contractor must ensure that the CSP provides evidence of annual recertification of privileged user access management.

E. A C-SCRM review is mandatory for specified acquisitions in accordance with established process in EO 14028 and NIST SP 800-161, Cybersecurity Supply Chain Risk Management Practices for Systems and Organizations, or superseding document. All vendor products and solutions to be used on DOJ national security systems, enterprise-wide systems, or new FIPS-199 High and Moderate systems for the purpose of accessing, collecting, storing, processing, maintaining, using, sharing, retrieving, disseminating, transmitting, or disposing of DOJ Information must be submitted to DOJ OCIO for a C-SCRM review prior to contract award or ATO signature. Changes in corporate ownership or structure shall be reported to the CO for referral to C-SCRM. The Contractor shall notify the CO of any confirmed Supply Chain compromise affecting the Contractor's products or services within 1 hour of discovery.

__ The following C-SCRM requirements for acquisition of systems, hardware, or software which will be used in systems that are mission critical or process sensitive data apply to this award. **(CO check as appropriate in coordination with the Program Manager and/or System Owner)**

1. The Contractor shall develop and deliver a C-SCRM Plan. The C-SCRM Plan shall meet the format described in NIST SP 800-161, Appendix E. The C-SCRM plan shall address the following security controls from NIST SP 800-53 Rev 5: SR-2, SR-3, SR-4, SR-5, SR-6, SR-7, SR-8, SR-9, SR-10, and SR-11. Equivalent ISO 27000 series controls may be used if they are mapped to the NIST control(s).
2. The Contractor shall implement the required security controls as documented in the C-SCRM Plan. The requirements of the C-SCRM plan shall flow down to all subcontractors. Evidence of the certification and compliance is required.
3. For cloud platforms or managed services, upon request, the Contractor shall provide a current SBOM of the runtime production environment reflecting the software components and dependencies materially present in the service.
4. The Contractor shall provide evidence of compliance with the documented C-SCRM Plan. (CO select which applies)

__ Self-assessment by a contractor security team
__ External assessment by an independent auditor

VI. Information System Security Incident

A. Confirmed Security Incident. The Contractor shall immediately (and in no event later than 1 hour of discovery) report any Confirmed Security Incident to the DOJ CO and COR. If the Confirmed Security Incident occurs outside of regular business hours and/or neither the DOJ CO nor the COR can be reached, the Contractor must call JSOC at 1-202-357-7000 immediately (and in no event later than within 1 hour of discovery of the Confirmed Security Incident) and shall notify the CO and COR as soon as practicable.

B. Potential Security Incident.

1. If the Contractor suspects that DOJ information has been potentially disclosed or impacted, the Contractor shall promptly investigate to determine if a Security Incident has occurred. If the Contractor has not determined within 24 hours (i.e., 24 hours from detection of potential security incident and/or security breach) whether the Potential Security Incident was in fact a Security Incident, then it must immediately report the Potential Security Incident to the DOJ CO and the COR. If the time by which to report the Potential Security Incident occurs outside of regular business hours and/or neither the DOJ CO nor the COR can be reached, the Contractor must call or e-mail the JSOC Team at 1-202-357-7000 or JSOC@USDOJ.GOV and contact the DOJ CO and COR as soon as practicable. If the contract involves PII, the Contractor must comply with the notification requirements of DOJ-02 and Executive Order M-17-12 (Memorandum on Preparing for and Responding to a Breach of Personally Identifiable Information), Contractor Privacy Requirements, Section B.5, for an actual or suspected Security Incident.
2. The Contractor must limit sharing of Security Incident details to only those individuals involved in responding to the potential Security Incident. Any provisions of the Covered Contract regarding the citizenship or location of individuals working on the Covered Contract apply equally to individuals involved in responding to any potential Security Incidents. The Contractor may request assistance from the JSOC for advice, incident response, or FBI coordination. The Contractor must provide weekly updates to CO, COR and JSOC during the course of a Security Incident investigation.

C. Any report submitted in accordance with paragraphs (B) and (C), above, shall identify:

1. Both the Covered Information Systems and DOJ Information involved or at risk, including the type, amount, and level of sensitivity of the DOJ Information and, if the DOJ Information contains PII, the estimated number of unique instances of PII.
2. All steps and processes being undertaken by the Contractor to minimize, remedy, and/or investigate the Security Incident.
3. Any and all other information as required by the CISA Federal Incident Notification Guidelines, including the functional impact, information impact, impact to recoverability, threat vector, mitigation details, and all available incident details; and

The Contractor may request assistance from the JSOC Team for advice, incident response, or FBI coordination, and must provide weekly updates to CO, COR, and JSOC during the course of an Incident investigation.

D. Except as otherwise required by Federal, State and local laws, executive orders, rules and regulations, all determinations regarding whether and when to notify other individuals and/or federal agencies potentially affected by a Security Incident will be made by DOJ senior officials, the DOJ Core Management Team, or the COR at DOJ's discretion.

E. The Contractor must provide to DOJ full access to any facility and/or Covered Information System affected or potentially affected by any potential or confirmed Security Incident, including access by the DOJ OIG and federal law enforcement organizations, and undertake any and all response actions DOJ determines are required to ensure the protection of DOJ Information, including providing all requested images, log files, and event information to facilitate rapid resolution of any Security Incident.

F. DOJ, at its sole discretion, may obtain, and the Contractor will permit, the assistance of other federal agencies and/or third-party contractors or firms to aid in response activities related to any potential or confirmed Security Incident. Additionally, DOJ, at its sole discretion, may require the Contractor to retain, at the Contractor's expense, a 3PAO acceptable to DOJ, with expertise in incident response, compromise assessment, and federal security control requirements, to conduct a thorough vulnerability and security assessment of all affected Covered Information Systems.

G. Response activities related to any Security Incident undertaken by DOJ, including activities undertaken by the Contractor, other federal agencies, and any third-party contractors or firms at the request or direction of DOJ, may include inspections, investigations, forensic reviews, data analyses and processing, and final determinations of responsibility for the Security Incident and/or liability for any additional response activities. The Contractor shall be responsible for all costs and related resource allocations required for all such response activities related to any Security Incident, including the cost of any penetration testing.

VII. Pass-Through of Security Requirements to Subcontractors and CSPs

A. The requirements set forth in the preceding paragraphs of this clause apply to all subcontractors and CSPs who perform work in connection with the contract, including any CSP providing services for any other CSP under the contract, and the Contractor shall flow down this clause to all subcontractors and CSPs performing under this contract. Any breach by any subcontractor or CSP of any of the provisions set forth in this clause will be attributed to the Contractor.

(End of Clause)

FAO-0001 Bonds

(a) Bid Guarantee. Each bidder shall submit with his bid a Bid Bond (Standard Form 24) with good and sufficient surety or sureties acceptable to the Government, or other security as provided in provision 52.228-1, in the form of twenty percent (20) of the bid price or not to exceed $3,000,000. The bid bond penalty may be expressed in terms of a percentage of the bid price or may be expressed in dollars and cents. A bid bond is not required for bids of $150,000 or less. (FAR 28.102-1)

(b) Performance and Payment Bonds. Within 10 days after award the contractor shall execute and submit to the Contracting Officer two bonds, each with good and sufficient surety or sureties acceptable to the Government, as follows; a Performance Bond (Standard Form 25) and a Payment Bond (Standard Form 25A). The penal sums of such bonds will be as follows: (Not required for contracts of $150,000 or less)

(1) Performance Bond: The penal sum of performance bonds at the time of contract award shall be 100 percent of the original contract price.

(2) Payment Bond: The penal amount of payment bonds at the

time of contract award shall be 100 percent of the original contract price.

(c) For construction contracts greater than $35,000 but not greater than $150,000, the Contracting Officer shall select two or more of the following payment protections, giving particular consideration to inclusion of an irrevocable letter of credit as one of the selected alternatives (FAR 28.102-1(b)(1)):

(1) A Payment Bond;
(2) An irrevocable letter of credit (ILC);
(3) A tripartite escrow agreement;
(4) A Certificate of Deposit; or
(5) A deposit of the types of security listed in 28.204-1 and 28.204-2.

(d) Individual Sureties.

(1) Bidders may elect to furnish individual surety bonds. If individual surety bonds are furnished for bid guarantees, payment or performance bonds, the individual sureties must submit their bonds proof of ownership and value of the assets which they claim in their net worth at time of bid opening. The Government's preferred method of proof is to have a statement of net worth prepared by a Certified Public Accountant (CPA) in accordance with Generally Accepted Accounting Principles (GAAP). Statements from a CPA that contain disclaimers are not acceptable. The statement of net worth on the Standard Form 28, Affidavit of Individual Surety, is insufficient and will not be accepted without additional proof of value and ownership.

(2) Bidders are cautioned that individual sureties must provide complete and detailed information in Block 9 of Standard Form 28 concerning other contracts on which they have provided bonds. This information shall include contract number, contract location, amount, and type of bond and telephone number of the involved contracting office. Failure to provide the proof and information required may result in rejection of the bid or termination of the contract for failure to provide adequate bonds.

FAO-0002 Magnitude

The magnitude of this project is between $100000.00 and $170000.00.

FAO-0003 Required Insurance

See FAR 52.228-5, Insurance - Work on a Government Installation.

The Contractor shall, at its own expense, provide and maintain during the entire performance

period of this contract, at least the kinds and minimum amounts of insurance required in the

Schedule or elsewhere in the contract.

TYPE	AMOUNT
(1) WORKERS COMPENSATION & EMPLOYER'S LIABILITY	$100,000

The required Workmen's Compensation Insurance shall extend to cover employee's liability for accidental bodily injury or death and for occupational disease with a minimum liability of $100,000.

(2) COMPREHENSIVE GENERAL LIABILITY with a minimum limit of:

PER ACCIDENT OR	
OCCURRENCE FOR BODILY INJURY	$500,000

This insurance shall include contractor's protective and contractual liability.

(3) COMPREHENSIVE AUTOMOBILE LIABILITY with the following minimum limits:

PER PERSON	$200,000
PER OCCURRENCE FOR BODILY INJURY	$500,000
PER OCCURRENCE FOR PROPERTY DAMAGE	$ 20,000

FAO-0004 Pre-Construction Conference

(a) Prior to the start of construction, Contracting Officers shall call a conference with the contractor, subcontractor(s), Warden, Controller/Business Administrator, Safety Manager, Facilities Administrator, Project Representative, A&E firm, Captain and other interested personnel to discuss the statutory labor standards, prevailing wage requirements, submission of the contractor's payrolls, subcontractor's responsibilities, institution work schedules, local policies, contraband, parking, storage of vehicles and equipment, etc.

Minutes of the conference shall be recorded, listing the names and titles of all attendees, and the subject matter of all items covered. The minutes shall be signed by the contractor and the Contracting Officer, and a signed copy placed in the contract file.

(b) The Contractor shall familiarize himself/herself with all procedures involved in normal institution routines. Any requirements which may constitute a problem or result in conflict, will be brought to the attention of the Contracting Officer or his representative for determination.

FAO-0005 Submittals

Within 10 calendar days after commencement of work or as otherwise established by the Contracting Officer, all materials and articles requiring approval, as contemplated by the Materials and Workmanship clause, shall be submitted by the contractor.

The submittal process is in place to allow the Government the opportunity to determine whether materials or procedures used by the contractor are in accordance with contract requirements. It is ultimately the Contractor's responsibility via the quality control process to ensure submittal items installed under the contract and work performed on site are in accordance with industry standards and general practices.

(a) The types of submittal requirements specified in this contract may include, but is not limited to; shop drawings, product data, samples, certificates of conformance or compliance, certified test or inspection reports, equipment, materials, and miscellaneous work related submittals for construction. Individual submittal requirements are generally specified in applicable sections for each unit of work in the specifications and/or as a whole in one section in the statement of work.

(b) The Bureau of Prisons (BOP) Contracting Officer's Representative (COR) shall act for the Contracting Officer in the review and acceptance of all submittals. The Contractor shall submit submittals as required by the contract/specifications to the COR for transmittal to the Contracting Officer. Fabrication of any work or purchase or use of any submittals (such as materials for which samples are required or equipment, etc.) shall not take place until written acceptance is given by the COR, except at the Contractor's own risk.

(c) The Contractor shall submit all shop drawings and submittals sufficiently in advance (unless otherwise specified in the specifications) of the construction requirements to allow ample time for checking, re-submitting, and re-checking.

(d) Failure of any materials to pass their specified tests shall be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make of that material. The Government reserves the right to disapprove any material or equipment which has previously proven unsatisfactory in service.

(e) The Contracting Officer's or designee's approval or acceptance of submittals is not to be construed as a complete check. Approval or acceptance will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor is responsible for the satisfactory construction of all work. The Contractor is responsible for delivering a final product/system that is operational as intended by the contract requirements, regardless of any Government approvals or acceptance of submittals. The Government assumes no liability during the submittal approval/acceptance process. It is the sole responsibility of the Contractor to deliver a properly functioning product or system.

FAO-0006 Contractor Use of Premises

Work Hours

The project schedule is based on a normal forty (40) hour work week, eight (8) hours per day, Monday through Friday, excluding Federal holidays. The Contracting Officer's Representative (COR) shall establish the work hour time frames for the duration of the project, subject to the approval of the Contracting Officer. Work hours and work days may be altered only with a 48 hour advance approval of the Contracting Officer.

NOTE: Access to the site will be available during normal working hours except during emergencies. It shall be the responsibility of the Contractor to familiarize himself, his employees, and his subcontractors of the working hours and conditions in the correctional facility, as working hours may not constitute a full eight hour day. The Government assumes no responsibility to the Contractor, nor to any of his subcontractors, for shorter hours due to institutional emergencies or entry and/or exit of workers necessitated by normal institution routines. The procedures and institutional entrance/exit routines applicable to this project will be explained at both the pre-bid conference/site visit and the pre-construction meeting.

Contraband

The Contractor shall inform his employees that intoxicating beverages, drugs, weapons, etc., will not be allowed on the site. Introduction of contraband shall be subject to the penalties prescribed by Title 18 USC-1791.

Explosives

The use of explosives is absolutely forbidden without written authorization from the Contracting Officer.

Parking and Temporary Office

Parking will be available at the site to the extent it does not interfere with construction activities. Otherwise, parking shall be provided for by the Contractor, at his expense, off the site for workmen employed on the project. Any temporary field office used by the Contractor shall be located in an area approved by the COR.

Safety and Accident Prevention

In performing work under this contract the contractor shall:

(a) Conform to the specific safety requirements established by this contract;

(b) Comply with the safety rules of the Government institution that concern related activities not directly addressed in this contract;

(c) Take all reasonable steps and precautions to prevent accidents and preserve the life and health of contractor and Government personnel performing or in any way coming in contact with the performance of this contract; and

(d) Take such additional immediate precautions as the Contracting Officer and/or COR may reasonably require for safety and accident prevention purposes.

FAO-0007 Payment Services

(a) Original application for payment shall be prepared on AIA (American Institute of Architects) Form G-702 "Application and Certificate for Payment" and submitted to the Contracting Officer. The contractor may use another form; however, it shall contain similar information as the AIA Form G-702. The Contracting Officer's Representative (COR) will approve the amount of payment by signing. The approved application for payment shall be forwarded as follows: Original to Accounting; Copy for Contract Award File.

(b) All small business contractors are required to self-certify on all invoices their small business status.

(c) The following information is required with each application for payment:

- Name and address of contractor
- Contract number
- Contractor invoice/application for payment number
- Description, price, and quantity of construction completed/rendered
- Payment terms (reference the contract payment clause)
- Other substantiating documentation or information required by the contract
- Name, title, and phone number of official to be notified in the event of a defective invoice
- Contractor TIN (Tax ID Number)

FAO-0008 Request for Final Inspection

The Contractor shall give the Contracting Officer's Representative (COR) a minimum of ten (10) working days advanced written notice of the date on which the work will be fully completed and ready for the Government's final inspection.

FAO-0009 Contract Security (Program Statement 3000.03 Human Resource Management Manual)

In addition to the information contained in clause "DOJ-03 Personnel Security Requirements For Contractor Employees (Nov 2021); (Alt. I) -- Classified Information – Cleared
Contractors", the following additional security is required to be completed and submitted for all contract employees who will be working under the terms of the contract:
Criminal History Check – BP-A0660
CJIS Name Check Request Form
BOP Contractor Pre-employment Questionnaire
BOP Authority for Release of Information

FAO-0010 Assignment of Contract Administration Office and Functions

Pursuant to FAR 42.201 and 42.202, the assigned Contract Administration Office is listed in Block 26 of the Standard Form 1442 Back. This assignment carries with it the authority to perform all of the contract administration functions listed in FAR 42.302(a) and 42.302(b) to the extent that those functions apply to the contract.

The Contract Administration Office is required, however, to obtain written authorization from the Procuring Contracting Officer (PCO) to perform any function listed under 42.302(b). *Specifically*, the Administrative Contracting Officer (ACO) is required to obtain written authorization to perform the below referenced functions **FOR CONSTRUCTION CONTRACT AWARDS**:

(1) Negotiate or negotiate and execute supplemental agreements incorporating contractor proposals resulting from change orders issued under the Changes clause. Before completing negotiations, coordinate any delivery schedule change with the contracting office.

(2) Negotiate prices and execute priced exhibits for unpriced orders issued by the contracting officer under basic ordering agreements.

(3) Negotiate or negotiate and execute supplemental agreements changing contract delivery schedules.

(4) *Complete* Contractor Performance Assessment Report System (CPARS) evaluations of contractor performance in accordance with FAR Subpart 42.15.

Should any other function under FAR Subpart 42.15 not listed above be required, the ACO is required to contact the PCO for authority.

FAO-0011 Schedule of Values

The Contractor shall prepare a Schedule of Values (SOV) for the project and submit to the Contracting Officer for approval prior to submitting the first application for payment. The SOV shall be correlated with the construction schedule. The SOV shall be formatted per the Construction Specification Institute Master Format structure. The Contractor may propose an alternate organizational format to the Contracting Officer for approval.

(a) The SOV shall include:

(1) Project name, location, and contract number;
(2) Contractor's name and address;
(3) Date of submittal.

(b) The SOV shall be arranged in a tabular form with separate columns to indicate the following for each item listed:

(1) Description of Work or Material;
(2) Related specification section, if applicable;
(3) Name of subcontractor, if applicable;
(4) Name of manufacturer or fabricator, if applicable;
(5) Name of supplier, if applicable;
(6) Change orders (modifications) that have affected value, if applicable;
(7) Dollar value;
(8) Percentage of Contract sum rounded to the nearest percent, adjusted to total 100 percent.

(c) The SOV shall breakdown the contract sum in sufficient detail to facilitate continued evaluation of applications for payment and progress reports. The contractor should separate principal subcontract amounts down into several line items.

(d) SOV amounts shall be rounded to the nearest whole dollar. The total of all SOV amounts shall equal the total contract amount.

(e) The contractor shall progress the percentage of completion, with the concurrence of the Contracting Officer's Representative, for each value in conjunction with the preparation of each monthly application for payment. The progressed value percentages shall directly correlate to the calculated total amount due for each monthly progress payment.

(f) The SOV shall remain fixed for the duration of contract performance. Any revisions to the SOV must be requested in writing, with justification, for approval by the Contracting Officer.

FAO-0012 Progress Meetings

The Administrative Contracting Officer (ACO) shall conduct progress meetings at the project site on a monthly basis, or at intervals as determined by the ACO.

(a) At a minimum, the attendees shall include but is not limited to:

(1) FBOP: Administrative Contracting Officer, Contracting Officer's Representative (COR), Facility Administrator/Manager, Architect/Engineer (if applicable), Other Personnel (Executive Staff, Captain, Safety Manager, etc.).

(2) Contractor: Project Manager, Superintendent, and technical support disciplines as appropriate (Subcontractors, Manufacturers, Suppliers, etc.).

(b) The meeting should include, but is not limited to issues such as:

Administrative Contracting Officer:

(1) Old business from previous progress meeting(s);

(2) Status of modifications, certified payrolls, submittals, requests for information (RFI);

(3) Review of payments made to date and review/approve current payment request;

(4) Status of modification proposal requests;

(5) Discuss new business.

COR:

(1) Status of escort coverage;

(2) Review gate or sallyport entrance/exit issues;

(3) Discuss other delays contractor may be experiencing;

(4) Discuss performance/quality issues.

Contractor:

(1) Review/discuss updated progress schedule;

(2) Provide 30 day outlook;

(3) Discuss other issues affecting performance.

FAO-0013 Contract Closeout Procedures (for construction contracts exceeding $150,000)

Contract Closeout must be completed within six (6) months of physical completion of the work.

Prior to payment of final invoice:

The contractor shall submit the following documents:

(1) Contractor's Affidavit of Release of Liens (AIA Document G706A);

(2) Contractor's Affidavit of Payment of Debts and Claims (AIA Document G706);

(3) All as-built drawings/shop drawings, if applicable;

(4) Contractor's final invoice;

(5) Release of Claims (GSA Form 1142);

(6) Consent of Surety to Final Payment (AIA Document G707);

(7) Letter establishing warranty dates;

(8) Complete list of subcontractors with telephone numbers and points of contact;

(9) Guarantees and warranties;

(10) All balance and test reports;

(11) All operation/maintenance manuals;

(12) All permits and certifications.

AIA forms can be obtained from The American Institute of Architects at www.aiabookstore.com.

GSA forms can be obtained from the General Services Administration at www.gsa.gov (click on the “Forms Library” link).

FAO-0014 Contract Closeout Procedures (for construction contracts $150,000 or less)

Contract Closeout must be completed upon receipt of property and final payment.

Prior to payment of final invoice:

The Contractor shall submit the following documentation:

(1) Guarantees and warranties;

(2) All operation/maintenance manuals;

(3) Consent of Surety to Final Payment (AIA Document G707), if the contractor furnished a bond;

(4) Release of Claims (GSA Form 1142);

(5) Evidence of no pending labor disputes;

(6) As-built drawings/shop drawings, (if applicable);

(7) Contractor’s final invoice.

AIA forms can be obtained from The American Institute of Architects at www.aiabookstore.com.

GSA forms can be obtained from the General Services Administration at www.gsa.gov (click on the “Forms Library” link).

FAO-0015 Changes

(a) Changes will be in accordance with the Changes clause 52.243-4 or Changes and Changed Conditions clause 52.243-5 whichever applies to this contract.

(b) When changes are made in the work that requires an equitable adjustment to the contract, the Contractor shall submit to the Contracting Officer, through the Contracting Officer’s Representative (COR), a written proposal for adjustment of the amount of increase or decrease. With the proposal, the Contractor shall submit an itemized breakdown in at least the following detail:

(1) Material quantities and unit cost

(2) Labor costs by material item
(3) Construction equipment cost
(4) Workmen's compensation and public liability insurance
(5) Overhead
(6) Profit or commission
(7) Employment taxes (FICA and FUTA)

(c) The maximum allowable overhead, profit and commission percentages are contained below. The percentages for overhead, profit and commission shall be negotiated and may vary according to the nature, extent and complexity of the work involved, but in no case shall exceed the following:

(1) To the Contractor, on work performed by other than his own forces. The commission is 10% in the first $20,000, 7 1/2% on the next $30,000, 5% on the balance over $50,000.

(2) To the Contractor, and/or the Subcontractors for that portion of the work performed with their respective forces. The commission is 10% overhead and 10% profit on the first $20,000, 7 1/2% overhead and 7 1/2% profit on the next $30,000, and 5% overhead and 5% profit on the balance over $50,000.

Not more than three (3) percentages, not to exceed the maximum percentage amounts shown above, will be allowed regardless of the number of Subcontractors (i.e., the mark up on work subcontracted by the Subcontractor will be limited to the overhead percentage and one profit percentage in addition to the prime Contractor's commission percentage). On proposals covering both increases and decreases in the amount of the contract, overhead, profit and commission will be allowed on the net increase only.

(d) When certified cost or pricing data are required under FAR 15.403-4 for proposals over $2,000,000, the cost or pricing data shall be submitted in accordance with FAR 15.408, Table 15-2. No itemized breakdown will be required for proposals amounting to less than $1,000.

(e) When the necessity to proceed with a change does not allow sufficient time to negotiate a modification or because of failure to reach an agreement, the Contracting Officer may issue a change order instructing the contractor to proceed on the basis of a tentative price based on the best estimate available at the time, with the firm price to be determined later. Furthermore, when the change order is issued, the contractor shall submit a proposal for cost of changes in work within 30 calendar days.

(f) The Contracting Officer will consider issuing a settlement by determination to the contract, if the contractor's proposal required by paragraphs (a) and (b) of this clause is not received within 30 calendar days, or if agreement has not been reached.

(g) Where a change involves credit items only, a proper measure of the amount of downward adjustment in the contract price is the reasonable cost to the contractor if he/she had performed the deleted work. A reasonable allowance for overhead and profit are properly includable as part of the downward adjustment for a deductive change. The amount of such allowance is subject to negotiation.

(h) Overhead and contractor's fee percentages shall be considered to include insurance other than mentioned herein, field and office supervisors and assistants, security police, use of small tools, incidental job burdens, and general home office expenses and no separate allowance will be made therefor. Assistants to office supervisors include all clerical, stenographic and general office help. Incidental job burdens include, but are not necessarily limited to, office equipment and supplies, temporary toilets, telephone and conformance to OSHA requirements. Items such as, but not necessarily limited to, review and coordination, estimating and expediting relative to contract changes are associated with field and office supervision and are considered to be included in the contractor's overhead and/or fee percentage.

(i) The Contractor shall submit with his proposal a request for time extension, if applicable.

(j) The COR shall review the proposal and check estimates in detail, utilizing unit prices where specified or agreed upon. If they are in agreement, the COR shall forward the proposal to the Contracting Officer. The Contracting Officer will forward copies to the Architect-Engineer (if applicable) and the Regional Project Manager for their review and recommendations. After their review, the Architect-Engineer and Project Manager will forward their comments to the Contracting Officer.

(k) If the Contracting Officer determines that an equitable adjustment is to be made, the contract shall be modified in writing utilizing the prescribed Standard Form 30 (Amendment of Solicitation/Modification of Contract)(SF-30). After the SF-30 has been signed by the Contractor and executed by the Contracting Officer, distribution shall be made as follows:

(1) Original: Contract file
(2) Copy to: Contractor
Regional Project Manager
Contracting Officer's Representative (COR)
Architect-Engineer Firm (if applicable)
Accounting Supervisor
Contracting Officer

FAO-0016 Equitable Adjustments: Waiver and Release of Claims

(a) When the Contractor, after receipt of notification of a change made pursuant to the clause of this contract entitled "Changes" or after affirmation of constructive change thereunder, submits any claim for equitable adjustment under this clause, such claim shall include all types of adjustments in the total amounts to which that clause entitles the Contractor, including but not limited to adjustments arising out of delays or disruptions or both caused by such change. Except as the parties may otherwise expressly agree, the Contractor shall be deemed to have waived (i) any adjustments to which it otherwise might be entitled under the aforesaid clause where such claim fails to request such adjustment, and (ii) any increase in the amount of equitable adjustments additional to those requested in its claim.

(b) Further, the Contractor agrees that, if required by the Contracting Officer, it will execute a release, in form and substance satisfactory to the Contracting Officer, as part of the supplemental agreement setting forth the aforesaid adjustment, and that such release shall discharge the Government, its officers, agents, and employees, from any further claims, including but not limited, to further claims arising out of delays or disruptions or both caused by the aforesaid change.

[END OF ADDENDUM TO FAR 52.212-4]

Section 3 - List of Attachments

Identifier	Title	Number of Pages
1	SEA 26Z5AP9 SOW Building Elevator Renovation.pdf	11
2	SEA 26Z5AP9 Reference Documents	6

Section 4 - Solicitation Provisions

Provisions By Full Text

52.252-1 Solicitation Provisions Incorporated by Reference (Feb 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es):

www.acquisition.gov
https://www.acquisition.gov/far-overhaul

_____
[Insert one or more Internet addresses]

(End of provision)

U.S. Department of Justice
Federal Bureau of Prisons

Facilities Management

Washington, DC 20534
February 5, 2026

MEMORANDUM FOR **SEAN O'BRIEN, CONSTRUCTION REPRESENTATIVE**
RESOURCE MANAGEMENT SECTION

THRU: Kimberly Hudson, Chief
Construction and Environmental Review Section

FROM: Julius Buyag, Engineering Technician
Construction and Environmental Review Section

SUBJECT: Statement of Work Approval for Project 26Z5AP9
Building Elevator Renovation

The Construction and Environmental Review Section, Facilities Management, has reviewed and approved the Statement of Work (SOW) and As-Built Drawings (with Pictures) to be used for solicitation services at FCI Seagoville for Project 26Z5AP9, Building Elevator Renovation. There are no additional square footage or modifications to the primary structure, nor changes to the utilities to this project.

This SOW specifically addresses the Building Elevator Renovation under Project 26Z5AP9 as defined herein and should not be interpreted as an open-ended approval for future, unrelated work.

If you have any additional questions or concerns, please email Julius Buyag, Engineering Technician, at jbuyag@bop.gov.

Cc: Regional Facilities Administrator

FEDERAL BUREAU OF PRISONS
FCI SEAGOVILLE
PROJECT # 26Z5AP9 Building Elevator Renovation

APPROVED
By FMB-CERS at 2:55 pm, Feb 05, 2026

STATEMENT OF WORK

I. SPECIFICATIONS

A. INTRODUCTION

1. The Federal Bureau of Prisons (FBOP), Federal Correctional Institution (FCI) Seagoville, located at 2113 N. HWY 175, Seagoville, Texas 75159, requires a firm-fixed-price contract for the comprehensive modernization of one (1) existing passenger elevator located in Building 9. The successful Contractor shall provide all necessary engineering, specialized labor, certified materials, and equipment required to deliver a fully operational system. The modernized elevator must adhere to all ASME A17.1/CSA B44 Safety Codes, ADA Standards, and Manufacturer's Recommended Installation Practices.

2. **EQUIPMENT IDENTIFICATION:** The existing system to be modernized is a **Traction Passenger Elevator** currently utilizing the following components:
    - **Manufacturer:** Motion Control Engineering (MCE)
    - **Controller Model:** M4000-AC-1
    - **Serial Number:** 3252232
    - **Location:** Building 9, FCI Seagoville

3. **GENERAL PERFORMANCE REQUIREMENTS:** The Contractor is responsible for the removal and disposal of all obsolete components and the installation of a modern, **non-proprietary** microprocessor-based control system. The upgrade is intended to maximize operational reliability, improve energy efficiency through modern drive technology, and ensure the safety of staff and inmates within the correctional environment. All work shall be performed in accordance with the detailed Technical Specifications outlined in this solicitation, including the General Notes as provided on the drawings (Sheets 2 and 3).

B. SCOPE OF WORK

1. **GENERAL SUMMARY:**

    a. The Contractor shall provide a comprehensive modernization that replaces the existing MCE M4000-AC-1 controller with a modern, non-proprietary microprocessor control and Variable Frequency Drive (VFD) system. The completed system shall be optimized for high-reliability performance and peak energy efficiency, meeting or exceeding all original manufacturer specifications.
    b. Contractor shall field-verify and perform assessment of hoistway/cab/door dimensions, machine type (geared/gearless), roping/belting arrangement, counterweight location, governor and tension sheave arrangement, and existing power/disconnects. Provide a written survey report and updated shop drawings prior to ordering materials.

2. **CONTROL AND DIAGNOSTIC SYSTEMS**

   a. Microprocessor Control: Contractor shall replace existing obsolete controllers with a new non-proprietary microprocessor traction controller (e.g., MCE Motion 4000).
   b. Variable Frequency Drive: Contractor shall install a VVVF (Variable Voltage Variable Frequency) AC Drive for high-efficiency power management.
   c. Non-Proprietary Mandate: All diagnostic tools, software, and passwords required for full maintenance and troubleshooting must be provided to the FBOP. No "proprietary lockout" tools are permitted.
   d. Positioning System: Contractor shall provide a new digital absolute encoder hoistway leveling system to ensure accuracy within +/- 1/4 inch.

3. MECHANICAL AND DRIVE EQUIPMENT

   a. AC Hoist Motor: Contractor shall furnish and install a new High-Efficiency AC Induction Hoist Motor compatible with the new VFD drive. Installation must include new heavy-duty isolation pads to prevent noise and vibration transmission to the building structure.
   b. Braking & Safety: Contractor shall install a certified "Rope Gripper" or secondary emergency braking system to provide protection against Unintended Car Movement (UCM) and Ascending Car Overspeed (ACO) in strict accordance with ASME A17.1.
   c. Suspension & Governor: Contractor shall replace all existing hoist cables with new domestic steel ropes sized for the rated load. Additionally, the contractor shall replace the overspeed Governor and the Governor Tail-Sheave in the pit to ensure the safety system is as modern as the controller.

4. DOOR EQUIPMENT AND ENTRANCES

   a. Door Operator: Contractor shall install a new high-speed Heavy-Duty Linear Door Operator (e.g., MOVFR or equivalent) utilizing closed-loop technology for consistent speed regardless of wind or debris.
   b. Hardware: Contractor shall provide all new tracks, hangers, high-speed rollers, and interlocks. Include a new door-restrictive clutch to prevent passengers from prying doors open between floors.
   c. Panels: Contractor shall furnish and install new 16-gauge Stainless Steel (#4 Finish) car doors and all hoistway door panels at every landing. Doors must be reinforced for correctional use.
   d. Passenger Protection: Contractor shall install a full-height 3D Infrared Light Curtain. The 3D feature must detect approaching passengers before they enter the door path to prevent any physical contact.

5. ELECTRICAL AND COMMUNICATION

   a. Traveling Cables: Contractor shall furnish and install new fire-resistant, multi-conductor traveling cables between the car junction box and the controller. Cables must include

sufficient conductors for all specified features plus a minimum of eight (8) spare conductors or 10%, whichever is greater.

b. Data & Video Cabling: Traveling cables shall contain a minimum of two (2) shielded pairs for telephone/intercom use and two (2) CAT6 cables. One (1) CAT6 cable shall be dedicated to the cab security camera, and one (1) shall support the code-mandated emergency communication system.

Contractor shall coordinate with FBOP to relocate the existing camera to the new cab. If required, FBOP shall furnish and install a new IP-based security camera compatible with Institution's existing surveillance head-end.

c. Emergency Communication: Contractor shall furnish and install a code-compliant ADA Emergency Phone. Per ASME A17.1, this system must provide two-way visual/video capability for the hearing impaired.

d. Hoistway Wiring: Contractor shall provide all new machine room and hoistway wiring, including conduit as specified in Section 6.e, fittings, and junction boxes compliant with NFPA 70 (NEC).

6. SECURITY INTEGRATION AND HARDENING

a. Access Control Interface: Contractor shall provide a dedicated terminal interface within the controller for card reader integration. The controller logic must be programmed to allow for Hall Station and COP lockout via a dry contact interface.

b. Field Wiring for Readers: Contractor shall provide one (1) shielded 6-conductor cable from the controller to each Hall Station and the COP to support modern multi-technology card readers.

c. On-Site Reader Placement: The final mounting location of the card readers (e.g., flush-mounted within the fixtures, surface-mounted on the wall, or integrated into the door frame) will be determined on-site by **FCI Seagoville IT personnel**.

d. Installation Support: The Contractor shall provide a minimum 6-foot wiring "tail" at each station to allow for flexible positioning. Contractor shall assist the **FCI Seagoville IT Department** in the physical installation, termination, and functional testing of the readers and building security interface.

e. Hardened Conduit Protection: To prevent tampering in the correctional environment, all new hoistway and machine room wiring shall be installed in Rigid Metal Conduit (RMC) up to a height of 8 feet above the floor in the hoistway and throughout the machine room. This prevents a "gap" where a wire could be pulled out of a wall.

f. Tamper-Proof Fasteners: All exposed junction boxes, call stations, and fixtures shall be secured with tamper-proof, Torx-head security screws.

g. Cabling Armor: All cabling between the car junction box and the door operator or security camera must be encased in liquid-tight flexible metal conduit to prevent manual cutting or manipulation.

h. Signal Isolation: Security and data wiring (readers/cameras) must be physically separated from high-voltage power lines within the hoistway to prevent electrical interference and signal disruption.

7. FIXTURES AND FIRE SERVICE

a. Car Operating Panel (COP): Contractor shall furnish and install a new, vandal-resistant #4 brushed stainless steel COP. Panel shall include an integrated LED Position Indicator with an audible floor arrival chime, FEO K1 Fire Service cabinet, and EPCO1/EPCO2 barrel-type keyed switches.
b. Hall Stations: Contractor shall provide new stainless steel hall stations at all floors with keyed operation only to prevent unauthorized use. All buttons must be flush-mounted and impact-resistant.
c. Fire Service Compliance: COP must include a built-in two-way visual communication system (screen and camera) to allow for text-based messaging between trapped passengers and emergency personnel per ASME A17.1-2019/B44-19 Section 2.27.1.1.3.
d. Fire Alarm Interconnect: Contractor shall provide the fire alarm interconnect for "Fireman's Return" (Phase I) and the "Fireman's Hat" (Visual Signal) service. The connection point will be provided in the elevator machine room by others (building fire alarm vendor); the elevator contractor is responsible for final termination to the controller and system testing.

8. PIT EQUIPMENT, DRAINAGE & ACCESS

a. Hoistway Access: Contractor shall furnish and install new keyed Hoistway Access Switches at the top and bottom terminal landings to allow for safe car-top and pit entry by authorized personnel.
b. Submersible Sump Pump: Contractor shall furnish and install a new heavy-duty submersible pump capable of 3,000 GPH. Contractor shall reconnect to the existing discharge piping and ensure all check valves are replaced with new, heavy-duty hardware.
c. Oil-Sensing Shutoff: In accordance with environmental regulations, the pump system must include an oil-sensing control (e.g., Oil-Smart switch) to prevent the discharge of elevator lubricants into the sanitary sewer.
d. Safety Upgrades: Contractor shall install new NEMA 4X (water-resistant) pit emergency stop switches, high-output LED pit lighting, and GFCI protected outlets.
e. Pit Ladder & Restoration: Contractor shall modify or replace the pit ladder to ensure stringers extend 48 inches above the sill per ASME A17.1. All non-moving pit equipment, including buffers and channels, shall be wire-brushed and painted with gray industrial enamel.

9. PROJECT CLOSEOUT

a. Field Survey & As-Builts: Contractor shall provide a comprehensive survey and shop drawings for approval before fabrication. Upon completion, provide three (3) sets of laminated, site-specific wiring diagrams.
b. Data Plates & Labels: Affix permanent, etched-metal data plates indicating the Code Year of Record and testing dates.

c. Testing & Certification: Contractor is responsible for performing the Full-Load Safety Test and coordinating the final inspection with the FBOP-designated inspector or third-party Authority Having Jurisdiction (AHJ).
d. FBOP Training: Contractor shall provide at least two (2) hours of on-site training for **FCI Seagoville staff** on the operations and service procedures.

C. QUALITY ASSURANCE & TESTING

1. Certified Technicians: All installers/technicians shall be qualified and certified by the manufacturer to install, test, and certify new modernized elevator system. Such certification must be verified in writing by the manufacturer and submitted to the COR seven (7) days before the project starts.
2. Pre-Installation Audit: The contractor shall perform a comprehensive survey of the existing hoistway signals, limits, and wiring to ensure compatibility with the new microprocessor. Any degradation in existing wiring must be reported and replaced to prevent "ghost" faults in the new system.
3. Ride Quality Analysis: Upon completion, the contractor shall provide a ride quality report (using an industry-standard accelerometer) demonstrating that horizontal and vertical vibrations have been reduced compared to the legacy MCE M4000 system.
4. Thermal Management: The control room environment must be evaluated for the heat dissipation requirements of the new VFD. The contractor is responsible for ensuring the controller cabinet includes active ventilation (filtered fans) to maintain internal temperatures within the manufacturer's specified range.
5. Compliance & Documentation: This ensures the system is legally compliant and maintainable by any qualified third party.
    a. Code Compliance: System must meet or exceed ASME A17.1 / CSA B44 (Safety Code for Elevators) and all local jurisdictional amendments.
    b. Documentation: Contractor shall provide three (3) sets of complete, "as-built" wiring diagrams. These shall be laminated and stored in the controller or a designated wall-mounted rack.
    c. Energy Audit: Contractor shall provide documentation verifying that the VFD system is configured for Peak Efficiency Mode, utilizing sleep functions for fans and lights when the elevator is idle.
    d. Software Rights: All software required for the operation and maintenance of the elevator shall be licensed to FBOP in perpetuity.
6. All seismic zone requirements, environmental compliance, Life Safety, NFPA, ADA-ABA, and Federal, State and Local codes and regulations will be considered during all phases of this project.
7. Services and materials provided by the contractor will adhere to and shall be consistent with the most current industry standards, the Underwriters Laboratories (UL) and the General and the National Electric Code (NEC).
8. It is the contractor’s responsibility to obtain permitting, should it be required. Copies of all permits must be submitted to the COR upon receipt from local agency.

9. These parts shall be currently manufactured and available through authorized dealers. Such certification must be verified in writing through submittals by the manufacturer and submitted to the COR on a timely basis.

D. UTILITIES

1. Electricity Access: Contractors will have access to designated electrical outlets at the site (120v). Usage is limited to project-related equipment and activities. Any additional requirements must be coordinated with the COR.
2. Non-Potable Water Access: Contractors may use non-potable water sources for purposes such as cleaning or construction tasks. These sources will be clearly marked and communicated.
    - Contractors must adhere to site rules and guidelines for the safe use of electricity and non-potable water to prevent disruptions or hazards. FBOP will address specific needs or any additional requirements beyond the standard access provided.
3. Restrooms: Contractors will be granted access to designated on-site restroom facilities, which will be clearly marked and communicated to all personnel. If such facilities are unavailable, the contractor will coordinate with the COR to arrange for portable restrooms. These portable restrooms must be placed in a location approved by the COR prior to the commencement of the project. The contractor is responsible for ensuring regular maintenance of these facilities to uphold cleanliness and sanitation standards.
4. Parking: A designated area within the project site will be allocated for contractor parking. This area will be clearly marked and communicated to all contractors. Contractors should coordinate with the project site management for any specific parking needs or arrangements beyond the allocated area.

E. HOUSEKEEPING AND MATERIAL DISPOSAL:

1. All removed equipment and debris shall be disposed of off-site by the contractor in accordance with local regulations, unless otherwise directed by FCI Seagoville staff.
2. The contractor must maintain a clean worksite, free of waste and debris at all times. This includes daily removal of rubbish, scrap, and excess materials, as well as prompt removal of surplus equipment upon project completion.
3. Upon project completion, the contractor must remove and dispose of all debris and waste from the site. For long-term projects requiring dumpsters, these must be properly covered and secured to prevent salvaging. Debris must be disposed of at agreed intervals in compliance with federal, state, and local regulations.

II. CONTRACTOR SECURITY/WORKING REGULATIONS

A. WORKING HOURS AND CONDITIONS

1. Work Hours: Work Hours for on-site contract services are **7:00 AM to 3:00 PM**, Monday through Friday, except Federal Holidays. Any work to be completed at any other time requires written approval, a minimum of five (5) working days prior to the start of the work.

2. Access to the site will be available during normal working hours except during emergencies. It is the responsibility of the Contractor to familiarize himself, his employees, and his subcontractors with the working hours and conditions in the correctional facility, as working hours may not constitute a full eight-hour workday.
3. To avoid processing out of and back into the institution at midday, lunches are to be consumed at the work site. Workers shall ensure they have everything they need for their lunch when they check in first thing in the morning. A contractor supplied tool list should accompany the contractors for entry into the secure areas of the institution.
4. Contractors should plan for a certain amount of time for security considerations, i.e., check-in screening, delay due to inmate movements, institution lock-down, institution emergencies, or any other weather-related events, etc. In the event of an institutional emergency, the Contractor will be instructed to secure all work, to secure and stow all tools, equipment, and materials, and will be escorted out of the institution. Work will resume once the institution emergency passes.
5. Contractors will NOT be allowed to bring cell phones, or cameras into the institution. The Facilities Department maintains a digital camera that will be utilized by FBOP staff to document the project work. The Contractor may request copies of these photos for record keeping.
6. Contractor personnel shall wear clothing suitable for the work they are to perform. The following clothing is not permitted on institution grounds:
    a. Green or khaki-color clothing (inmates wear these colors);
    b. Camouflage shirt/pants/outer wear.
    c. Shorts
    d. Sleeveless shirts/tank top

B. DELIVERY OF MATERIALS

1. All project materials and heavy equipment must be processed by the contractor and coordinated with the COR for use in the assigned temporary laydown yard and storage area.
2. Deliveries shipped directly to the contractor can only be received between **7:00 a.m. and 2:00 p.m.,** Monday through Friday, excluding Federal Holidays. FBOP is not responsible for receiving or signing deliveries. The contractor must provide their own resources for loading and unloading materials or equipment.
3. The contractor is prohibited from using the institution's entry or driveway for loading, unloading, or storage. Driveways must remain unblocked during and after work hours.
4. The contractor is responsible for maintaining proper housekeeping in the assigned laydown yard, ensuring materials are covered to protect against the elements. If the laydown yard is temporarily used as a disposal area during the project, this must be managed accordingly.

C. TOOLS, EQUIPMENT & STORAGE

1. FBOP shall provide a secure staging area for materials; however, Contractor remains liable for all tools and equipment until final acceptance.

2. All project tools and small equipment, such as power tools and materials, must be stored in an area designated by the COR. If required, the contractor shall provide a secure storage container, such as a Job or Gang Box, to remain in the agreed-upon storage area for the project duration.
3. The storage container must be secured with a padlock system using two locks: one provided by the contractor and the other by the institution. If needed, a contractor-supplied heavy-duty chain may be used to facilitate security. All items within the container must be stored safely and kept in an orderly condition.
4. Assigned escorts shall conduct daily tool inventories upon entry and exit to ensure accurate accountability of all tools brought into and removed from the institution.
5. All contractor-owned extension cords and ladders used during the project must be in good condition and approved for use within the institution. Ladders must be stored in a designated area and secured to a stationary fixture with a heavy-duty chain and lock to prevent unauthorized removal.

D. SECURITY REQUIREMENTS AND ESCORTING

1. Contractor personnel may be required to meet certain security requirements prior to entering the secured side of the institution. Contractor personnel shall go thru a security vetting process to acquire the necessary security clearance as required. The assigned program manager at the Institution is responsible for conducting the appropriate law enforcement check on all Contractor staff that may need access inside the prison facility.
2. As soon as the award has been accepted and signed both by the Contractor and the FBOP's Contracting Officer, the Contractor shall submit to the institution the list of all the names who are expected to work for this project, including Subcontractors. All these personnel are required to fill, sign, and submit the required security clearance form (NCIC).
3. Security clearance documents shall only be accepted from the prime Contractor. It is the prime Contractor's responsibility to review security clearance submissions to ensure they are accurate and complete and submitted on a timely manner.
4. In the event a Contractor or Subcontractor employee cannot pass the security clearance process, it shall be the Contractor's responsibility to provide a replacement. By law the FBOP cannot, and shall not, release any information to the Contractor concerning the nature of why Contractors or Subcontractor personnel were not able to pass the FBOP's security clearance process.
5. The Contractor shall provide a daily list of names of all approved personnel who shall be working on site each day to the COR or assigned escort.
6. The daily operation of this facility follows strict security checks and may require additional time to process into and out of the institution. Entry into the secure area of the facility and shall require passage of security screening to include a metal detector and other requirements. Once passed through security, FBOP staff shall be assigned as Escort/s to the Contractor, as required.
7. FBOP shall ensure a minimum of one representative (escort) is always present to allow access to all areas requested by the Contractor as needed.

E. SAFETY

1. Contractors and personnel must wear industry-standard personal protective equipment (PPE) at all times while on the job site. Contractors are responsible for providing PPE.
2. All ladders must be securely stored in a predetermined area using a chain and lock to prevent removal. If ladders are required, the contractor must consult with the COR to notify appropriate institution staff promptly.
3. Extension cords must be in good condition, with no damaged insulation, and stored in a locked gang box. For systems requiring Lock-out/Tag-out, both contractors and the institution locks must secure the isolation point to prevent electrical shock. All Lock-out/Tag-out procedures must comply with the institution's Lock-out program.

F. ADDITIONAL CONSIDERATIONS

1. Contractors, their employees, and agents are strictly prohibited from introducing or possessing any form of contraband within the secure perimeter of the institution. Contraband is defined as any item not authorized for retention or possession by federal, state, or local law, or by the facility's rules, regulations, and post orders, including but not limited to electronic devices, weapons, drugs, alcohol, and currency.
2. All contractor personnel shall adhere to the Federal Bureau of Prisons' comprehensive ban on smoking and tobacco products. The possession or use of any tobacco product (including but not limited to cigarettes, cigars, pipes, and e-cigarettes) and smoking apparatus is prohibited for all individuals, except for staff and official visitors in a Warden-designated outdoor smoking area (which must be outside the secure perimeter and out of view of inmates)

END STATEMENT OF WORK

REFERENCE DOCUMENTS (SEPARATELY PROVIDED)

Attached reference drawings are provided for general information and the Contractor’s benefit only. Actual equipment installation and existing conditions may vary.

Sheet A1 – FCI Seagoville Site Plan

Sheet A2 – Building 9 Floor Plan & Area of Work

Sheet A3 – Existing Elevator Specifications


Sheet A4 – Existing Elevator Control Panel Photos

Sheet A5 - Existing Elevator Outer Door & Call Button Photos

Sheet A6 - Existing Elevator Pit Rails and Wiring Photos

FCI SEAGOVILLE
2113 N. HWY 175
SEAGOVILLE, TX. 75159

PROJECT: 26Z5AP9: 9 Building Elevator Renovation



SOUTH CENTRAL REGION
SCRO
344 Marine Forces Dr.
Grand Prairie, TX 75051

BUILDING INDEX


1	ADMINISTRATION OFFICES
2	FINANCIAL MANAGEMENT
3	AUDITORIUM, VISITING ROOM, & CHAPEL
4	COMMISSARY
5	INMATE HOUSING
6	INMATE HOUSING
7	INMATE HOUSING
8	EDUCATION/LIBRARIES/LAUNDRY/MAIL RM.
9	ADMINISTRATION/SHU
10	INMATE HOUSING
11	FOOD SERVICE
12	INMATE HOUSING
13	UNICOR TEXTILES, SAFETY OFFICE
14	UNICOR TEXTILES
15	FACILITIES FILE STORAGE
16/17	GARAGE, POWERHOUSE, WAREHOUSE
18	GATE HOUSE
19	RECREATION ADMINSTRATION
20	WATER STORAGE TANK
21	WATER TOWER
22	PUMP HOUSE
23	HOBBY SHOP/WEIGHT SHACK
24	A.W.'S RESIDENCE
25	WARDEN'S RESIDENCE
26	CONTROL CENTER
27	PUMPHOUSE STORAGE
28	VT AUTO/BLDG. TRADES
29	FACILITIES DEPT.
30	HAZARDOUS WASTE SITE
31	CAMP FACILITY
32	TRAINING CENTER
33	INSIDE GROUNDS
35	RADIO ROOM
36	MAINTENANCE-OUT STORAGE
37	LOWER COMPOUND GATEHOUSE
38	HORTICULTURE GREENHOUSE
39	VT SMALL APPLIANCE/HORTICULTURE
40	REC PAVILION/MUSIC ROOM/EQUIP. ISSU
41	SALLYPORT - REAR GATE
43	SHU GUARDHOUSE
47	VEHICLE WASH BUILDING
53	INMATE HOUSING
54	INMATE HOUSING
55	FOOD SERVICE WAREHOUSE
61	VACANT
70	FDC/JAIL/DETENTION UNIT
80	CREDIT UNION

PROJECT INFORMATION

CONSTRUCTION - CONTRACTED :	(YES)	NO	Comments
SPECIFICATIONS INCLUDED:	(YES)	NO	Comments
CHANGE OF USE CONDITION:	YES	(NO)	Comments
RATED CAPACITY AFFECTED:	YES	(NO)	Comments
LIFE SAFETY AFFECTED:	YES	(NO)	Comments
ACCESSIBILITY AFFECTED:	YES	(NO)	Comments
LEAD (LBP)/ASBESTOS (ACM) EXIST:	YES	(NO)	Comments

DRAWING INDEX

A-1 - FCI SEAGOVILLE SITE PLAN
A-2 - BUILDING 9: FIOOR PLAN & AREA OF WORK
A-3 - BUILDING 9: ELEVATOR SPECIFICATIONS
A-4- BUILDING 9: ELEVATOR CONTROL PANEL PHOTOS
A-5- BUILDING 9: ELEVATOR OUTER DOOR & CALL BUTTONS
A-6- BUILDING 9: ELEVATOR RAILS AND WIRING PHOTOS



PROJECT AREA

FOR PUBLIC RELEASE

APPROVED
By FMB-CERS at 2:35 pm, Feb 05, 2026

1
A-1
FCI SEAGOVILLE- SITE PLAN

Federal Correctional Institution RECORD DRAWINGS

United States Department of Justice
Federal Bureau of Prisons
Federal Correctional Institution - Seagoville
2113 N. Hwy 175
Seagoville, Tx 75159

PREPARED BY
A. HURD, Engineering Tech

DRAWING TITLE
9 BUILDING ELEVATOR RENOVATION


B&F PROJECT NUMBER:
26Z5AP9
M.W.O. NUMBER:
####
DRAWN BY:
A. HURD
CHECKED BY:
S. O'BRIEN
DATE DRAWN:
2/3/2026


REVISIONS

SHEET NUMBER:
1 OF: 6

ACAD NUMBER:
ELEVATOR.DWG

AREA OF WORK





BOP GENERAL NOTES

All work associated with this project shall comply with all applicable Federal, State, and Local Codes, ABA, Life Safety, NFPA, environmental regulations, seismic zone requirements and security regulations. This project shall also provide for rental/purchase cost of specialty tooling/equipment and photographic and/or office supplies to ensure proper completion and documentation of all construction/renovation/installation tasks.

CONSTRUCTION NOTES

Work includes the existing elevator hoistway, car, pit, and machine room/machinery space necessary to complete the traction elevator modernization. All dimensions are for reference only; contractor shall field-verify all conditions. Structural modifications, hazardous material abatement, and architectural finish upgrades beyond minor patching are excluded unless specifically noted.

1
A-2

BUILDING 9: FLOOR PLAN & AREA OF WORK

SCALE: 1/8" = 1'-0"

FOR PUBLIC RELEASE

APPROVED
By FMB-CERS at 2:39 pm, Feb 05, 2026

Federal Correctional Institution RECORD DRAWINGS

United States Department of Justice
Federal Bureau of Prisons
Federal Correctional Institution - Seagoville
2114 N. HWY 175
Seagoville, TX 75159

PREPARED BY
A. HURD, Engineering Tech


DRAWING TITLE
9 BUILDING ELEVATOR RENOVATION


B&F PROJECT NUMBER:
26Z5AP9
M.W.O. NUMBER:
#####
DRAWN BY:
A. HURD
CHECKED BY:
S. O'BRIEN
DATE DRAWN:
2/3/2026


REVISIONS

SHEET NUMBER:
2 OF: 6

ACAD NUMBER:
ELEVATOR.DWG







SPECIFICATIONS AND DATA	
CLASSIFICATION:	PASSENGER
CAPACITY:	2100 LBS
SPEED: UP/DN:	150 RPM
OPERATION:	SELECTIVE AUTOMATIC
CONTROL:	330a
LANDINGS:	3 LANDING (3F/ 0R)
RISE:	23' - 10"

GENERAL NOTES

1. Area of work includes the existing elevator hoistway, elevator car, machine room or machinery space, pit, and elevator-related electrical spaces as required to complete the elevator modernization described in the Contract Documents. Existing Conditions: Elevator is an existing traction passenger elevator serving three (3) landings with center-opening doors. Contractor shall verify all existing conditions prior to commencement of work. Field Verification: All dimensions shown are for reference only. Contractor shall field-verify hoistway, cab, door, pit, overhead, and machinery space dimensions prior to fabrication or ordering of materials.

2. Hoistway: Work includes all equipment, devices, and wiring within the elevator hoistway required for modernization, including but not limited to guide rails, counterweight, safeties, limit switches, traveling cable, and door interlocks. Car Interior: Work includes elevator car operating equipment, door equipment, lighting, fan, car operating panel (COP), indicators, and related wiring. Machine Room / Machinery Space: Work includes traction machine interfaces, controller, drive/VFD, disconnects, and all elevator-related control and power wiring. Pit: Work includes pit safety devices, pit lighting, pit stop switch, ladder, GFCI receptacle, and related elevator equipment as required by code.

3.Building Modifications: Structural modifications to the hoistway, floors, roof, or building framing are excluded, except for minor patching and repair directly related to elevator equipment removal and installation. Architectural Finishes: Repair or replacement of architectural finishes beyond minor patching and painting at elevator fixture locations is excluded unless specifically noted. Fire Protection & Alarm: Fire alarm and sprinkler system modifications are excluded except for required testing and interface verification with elevator controls. Hazardous Materials: Abatement of asbestos, lead, or other hazardous materials is excluded.

4. Access & Shutdowns: Contractor shall coordinate elevator shutdowns, access routes, and work hours with the COR to minimize disruption to facility operations. Protection: Contractor shall protect adjacent occupied areas, finishes, and building systems from damage during construction. Temporary Services: Temporary lighting, barricades, signage, and safety controls shall be provided as required during construction.

5. Power: Existing electrical service capacity shall be verified by the Contractor. New or modified elevator disconnects and branch circuits shall be provided as required for the modernized system. Utilities: Contractor shall coordinate temporary or permanent utility interruptions with the COR prior to execution.

6. Codes: All work shall comply with ASME A17.1 / CSA B44, applicable local codes, and manufacturer requirements. Inspections: Contractor shall arrange for all required inspections and tests by the Authority Having Jurisdiction (AHJ).

7. Testing & Acceptance: Elevator shall not be placed into service until all required testing is complete and acceptance by the Government and AHJ is achieved. Restoration: Upon completion, all disturbed areas shall be cleaned, patched, and restored to match adjacent finishes.

Federal Correctional Institution RECORD DRAWINGS

United States Department of Justice
Federal Bureau of Prisons
Federal Correctional Institution - Seagoville
2114 N. HWY 175
Seagoville, TX 75159

PREPARED BY
A. HURD, Engineering Tech

DRAWING TITLE
9 BUILDING ELEVATOR RENOVATION

B&F PROJECT NUMBER: 26Z5AP9
M.W.O. NUMBER: #####
DRAWN BY: A. HURD
CHECKED BY: S. O'BRIEN
DATE DRAWN: 2/3/2026

REVISIONS

SHEET NUMBER: 3 OF: 6
ACAD NUMBER: ELEVATOR.DWG


1
A-3
BUILDING 9: ELEVATOR SPECIFICATIONS & BOX CAR DIMENSIONS
NOT TO SCALE

FOR PUBLIC RELEASE

APPROVED
By FMB-CERS at 2:40 pm, Feb 05, 2026



2 A-4 ATTIC CONTROL PANEL TO BE REPLACED



3 A-4 CURRENT CONTROL , MOTOR, AND BRAKE NAME PLATE



1 A-4 CONTROL PANEL AND MOTOR ASSEMBLY



4 A-4 MOTOR, PULLEY AND BRAKE ASSEMBLY

FOR PUBLIC RELEASE

APPROVED
By FMB-CERS at 2:40 pm, Feb 05, 2026

Federal Correctional Institution RECORD DRAWINGS

United States Department of Justice
Federal Bureau of Prisons
Federal Correctional Institution - Seagoville
2113 N. Hwy 175
Seagoville, Tx 75159

PREPARED BY
A. HURD, Engineering Tech


DRAWING TITLE
9 BUILDING ELEVATOR RENOVATION

B&P PROJECT NUMBER: 26Z5AP9
M.W.O. NUMBER: ####
DRAWN BY: A. HURD
CHECKED BY: S. O'BRIEN
DATE DRAWN: 2/3/2026


REVISIONS

SHEET NUMBER: 4 OF: 6


ACAD NUMBER: ELEVATOR.DWG



2 A-5 BUILDING 9: DAMAGED OUTER DOOR TO BE REPLACED



3 A-5 BUILDING 9: INSIDE CAB ELECTRICAL TO BE INSPECTED



1 A-5 BUILDING 9: DAMAGED FIRE KEY LOCK TO BE REPLACED



4 A-5 BUILDING 9: DAMAGED CALL BUTTON TO BE REPLACED

FOR PUBLIC RELEASE

APPROVED
By FMB-CERS at 2:40 pm, Feb 05, 2026

Federal Correctional Institution RECORD DRAWINGS

United States Department of Justice
Federal Bureau of Prisons
Federal Correctional Institution - Seagoville
2113 N. Hwy 175
Seagoville, Tx 75159

PREPARED BY
A. HURD, Engineering Tech


DRAWING TITLE
9 BUILDING ELEVATOR RENOVATION

B&F PROJECT NUMBER: 26Z5AP9
M.W.O. NUMBER: ####
DRAWN BY: A. HURD
CHECKED BY: S. O'BRIEN
DATE DRAWN: 2/3/2026

REVISIONS

SHEET NUMBER: 5 OF: 6


ACAD NUMBER: ELEVATOR.DWG




2 A-6 BUILDING 9: INSTALL SUMP PUMP AT BOTTOM OF PIT



3 A-6 BUILDING 9: REPLACE PULLEY'S AND CABLES



1 A-6 BUILDING 9: REPLACE COMMUNICATION LINES AND CONDUIT



FOR PUBLIC RELEASE

APPROVED
By FMB-CERS at 2:41 pm, Feb 05, 2026

4 A-6 BUILDING 9: REPLACE CONDUIT AND ALL ELECTRICAL

Federal Correctional Institution RECORD DRAWINGS

United States Department of Justice
Federal Bureau of Prisons
Federal Correctional Institution - Seagoville
2113 N. Hwy 175
Seagoville, Tx 75159

PREPARED BY
A. HURD, Engineering Tech

DRAWING TITLE
9 BUILDING
ELEVATOR
RENOVATION

B&F PROJECT NUMBER:
26Z5AP9
M.W.O. NUMBER:
####
DRAWN BY:
A. HURD
CHECKED BY:
S. O'BRIEN
DATE DRAWN:
2/3/2026

REVISIONS

SHEET NUMBER:
6 OF: 6

ACAD NUMBER:
ELEVATOR.DWG