PERFORMANCE WORK STATEMENT

Network Cable Installations and Maintenance Services for Tobyhanna Army Depot (TYAD) Local Area Network (LAN)

Status:	Draft
Author:	Tobyhanna Army Depot (TYAD)
Date:	June 16, 2026
Version:	5.0

Table of Contents

Table of Contents 1
1. Scope 3
2. Government Provided Material, Equipment and Accommodations 3
3. General Requirements 3
4. Performance Requirements 4
4.1 LAN/Ethernet 4
4.2 Fiber Cable 4
4.3 Remedial Maintenance (RM) 4
4.4 BBLAN Removal 4
5. AT OPSEC requirements 5
6. SERVICE or EQUIPMENT INSTALLATION CONTRACTOR SAFETY STANDARDS FOR TYAD 13
S1.0 THE CONTRACTOR IS SOLELY RESPONSIBLE AND LIABLE FOR JOB- SITE SAFETY 14
S2.0 CODE COMPLIANCE 15
S3.0 JOB HAZARD ANALYSIS (JHA) / ACTIVITY HAZARD ANALYSIS (AHA) 16
S4.0 SITE SPECIFIC SAFETY & ACCIDENT PREVENTION PLANS 16
S6.0 FALL PROTECTION 19
S7.0 ELECTRICAL SAFETY 19
S8.0 DEPOT REQUIRED PERMITS / APPROVALS 20
S9.0 CONFINED SPACES 21
S11.0 PROTECTION TO THE DRINKING WATER SYSTEM 22
S12.0 PROTECTION OF PERSONNEL 22

S13.0 FIRE AND EMERGENCY SERVICES 23
S14.0 IF AN INCIDENT HAPPENS 23
S15.0 CRANE LIFT OPERATIONS AT TOBYHANNA ARMY DEPOT 24
S16.0 APPLICATION OF ANY ODOR PRODUCING MATERIAL 25
S17.0 CONTROL OF RESPIRABLE CRYSTALLINE SILICA 25
6. Standard Specifications for Projects Under the National Environmental Policy Act (NEPA) in Accordance with 32 CFR 651 Proponent ELTY-ISP-N 26
7. Performance Standards 36
8. Unacceptable Performance 37

1. Scope

This Performance Work Statement (PWS) defines the requirements to install, extend, retract, move and perform all work necessary for the Local Area Network (LAN), located at Tobyhanna Army Depot (TYAD), Tobyhanna Pa. 18466, to support multimedia functions, (e.g., two-way data communications) so that the entire LAN may operate as one system while conforming to the specifications herein.

The LAN is comprised of, but not limited to, for the purposes of this contract, the following types of components: Ethernet and Fiber Optic Cables and their necessary connectors, to include those that pass-through walls and cubicles. All work performed by the contractor shall provide minimal disruption to Government owned systems and personnel.

2. Government Provided Material, Equipment and Accommodations

- **Government Furnished Material (GFM) and Government Furnished Equipment (GFE):** The Government shall provide GFM & GFE as all LAN Ethernet cable, fiber optic cable, connectors, installation hardware, ladders, lift equipment, and any other miscellaneous installation related items.
- **Contractor Provided:** Except for the GFM/GFE identified above, the Contractor shall provide all plant, labor, vehicles, tools, fiber splicing equipment, consumable materials not provided as GFM, supervision, and services necessary to perform all operations with regard to inspection, connections, removal, repair, maintenance (remedial and preventive), part replacements, and tests to ensure proper operation of the LAN located at TYAD as one system.
- **Site Provisions:** The Government shall provide to the Contractor as applicable to this contract: desk, chair and storage space for tools and test equipment.

3. General Requirements

- **Place of Performance:** All within the scope of this effort are located on the Tobyhanna Army Depot.
- **Period of Performance:** The base period is one (1) year from date of award with the option to extend for four (4) additional years.
- **Standards:** The contractor shall install LAN cabling, in accordance with (IAW) industry standards, i.e., ANSI/TIA-568.0-D, Generic Telecommunications Cabling for Customer Premises, 2015, ANSI/TIA-568.1-D, Commercial Building Telecommunications Infrastructure Standard, 2015, ANSI/TIA-568.2-D, Balanced Twisted-Pair Telecommunication Cabling and Components Standard, in buildings as required by the Government.
- **Contractor Personnel:** The contractor shall provide trained and experienced service technicians with recent and relevant experience in the installation, termination and testing of Category 6 and 6E Ethernet drops at TYAD.

4. Performance Requirements

4.1 LAN/Ethernet

The contractor shall provide a team of journeyman LAN cable installers to install and terminate category 6 and 6E LAN twisted pair cable drops as requested by the COR via Government conduit. Quantity not to exceed 400 drop installations per contact year.

4.2 Fiber Cable

The contractor shall provide a team of journeyman LAN cable installers to install, terminate, and splice fiber-optic cable as requested by the COR through Government-provided conduit. Pre-terminated fiber runs will consist of Government-provided fiber-optic cables with eye pulls and LC connectors on each end. The contractor shall install these runs to Government-designated locations through Government-provided conduit. The contractor shall terminate or splice fiber-optic cable as necessary using contractor-provided equipment operated by personnel trained in its use. The length of pre-terminated fiber cables will be between 200 and 1000 ft. The quantity of pre-terminated runs shall not exceed 10 fiber-cable installations per contract year. The quantity of fiber-splicing instances shall not exceed five per contract year. Regarding the size of cable to be spliced, cables will be between 12 and 72 strands. Fusion splicing will be required. OTDR certification will also be required to prove the splices don't have high loss.

4.3 Remedial Maintenance (RM)

The contractor shall provide remedial maintenance (RM) for the entire cable LAN at TYAD. In the event of a major failure, the contractor shall provide on-site RM within six (6) business hours after notification by the Government. The contractor shall restore LAN service to operational status within 18 business hours after notification by the Government. RM shall also include water removal from manholes, as necessary, to install or repair LAN cable. There are approximately 160 manholes on post; the contractor is not required to keep all manholes free of water at all times but shall remove water as necessary to support LAN installation or repair. Water removal shall not exceed 40 hours per contract year.

4.4 BBLAN Removal

The contractor shall uninstall the previously employed Broadband Local Area Network (BBLAN). The contractor shall remove all coaxial cable and components necessary for the operation of the end-of-life BBLAN. One-fifth (1/5) of the BBLAN cable (approximately 31/miles) and components (splitters, amplifiers, taps, power supplies, line extenders, couplers, node taps, equalizers, 2126 devices in all) shall be removed during the course of each annual period of performance. Priority shall be given to work orders issued for other performance requirements. Documentation necessary for determining the location of this equipment will be provided upon contract award. The contractor shall report to the COR regarding removal effort at each POP expiration until the BBLAN removal is complete.

5. AT OPSEC requirements

Force Protection Condition (FPCON) Should the Force Protection Condition (FPCON) at the installation change, the Government may require changes in contractor security matters and/or processes.

If based on the requirements of this contract, contractor employees may be designated as mission essential. Mission-essential contractor employees are required to report for duty and remain on duty during declared emergencies and/or elevated FPCON levels unless otherwise directed by the Contracting Officer (KO) via the appropriate Contracting Officer's Representative (COR).

Unscheduled gate closures by Law Enforcement may occur at any time causing all personnel entering or exiting a closed installation to experience a delay. This cannot be predicted or prevented. Contractors are not compensated for unexpected closures or delays.

Vehicles operated by contractor personnel are subject to search pursuant to applicable regulations. Any moving violation of any applicable motor vehicle regulation may result in the termination of the contractor employee’s installation driving privileges.

The contractor’s employees shall become familiar with and obey the regulations of the installation, including law enforcement, fire, traffic, safety and security (protecting National security) regulations while on the installation. Contractor employees should only enter restricted areas when required to do so and only upon prior approval. All contractor employees shall always carry proper identification with them. The contractor shall ensure compliance with all regulations and orders of the installation which may affect performance.

The contractor, if required, shall provide support during contingencies, exercises, heightened operations, and adverse weather or security closures in the accomplishment of performance requirements. From time to time, the Base Commander may decide to close all or part of a base in response to an unforeseen emergency or similar occurrence. Such emergencies include adverse weather such as snow, or ice, "an act of God,” such as tornado or earthquake, or a base disaster such as a gas leak or fire.

Emergency Communications and Services. If assigned to TYAD for (7) seven days or longer, contractors and subcontractor employees will enroll in the ALERT! Mass Warning Notification System (MWNS). Common Access Card (CAC) is required to register for ALERT!. If a CAC has not been deemed necessary for the contractor or subcontractor, the COR will provide the necessary information to TYADs

Antiterrorism Officer or TYADs Emergency Manager in the Security Operations Branch for manual input into the ALERT! System.

ALERT! MWNS is NOT optional - it is a Headquarters Department of the Army (HQDA) requirement to be a registered user.

Due to the life-safety implications of the information being relayed and the requirement to provide immediate alerts and warnings, personnel assigned to TYAD must ensure that their personal contact information, including after-duty hours contact information, as appropriate (e.g., personal cellular phone numbers or landline phone numbers), e-mail addresses, home address, etc., are entered into the system and regularly updated or verified every 90 days to remain current and accurate.

In the event of a life-threatening emergency or natural disaster, COR will account for assigned contractors. COR will send personnel accountability report to Emergency Operations Center (EOC).

Base closure announcements will be disseminated via ALERT! MWNS.

Antiterrorism (AT) Level I Training. In accordance with AR 525-13, all contractor and subcontractor employees requiring access to Army installations, facilities, or controlled access areas shall complete AT Level I awareness training annually. This training must be completed prior to being granted installation access and beginning work. The contractor is responsible for ensuring this requirement is met and for providing certificates of completion for each employee to the COR upon request. The web-based training is available at https://jko.jten.mil (Course: JS-US007).

AT Level I and iWATCH training is not required to be in person. While in-person training is an option, the most common and widely accepted method is web-based. Army regulations explicitly provide multiple ways to meet the training requirement to ensure flexibility for all personnel, regardless of their location or access to a classroom setting.

iWATCH Army Training. This training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within 30 calendar days of contract award and within 30 calendar days of new employees commencing performance with the results reported to the COR NLT 30 calendar days after contract award. Contractors and all associated sub-contractors will be briefed by the TYAD Antiterrorism/Force Protection officer. It is recommended this training be conducted as part of an initial entry briefing or unit/organization newcomer's briefings. Send training requests to TYADs Antiterrorism Officer. Contractor employee training will be documented on a local form.

Access and General Protection/Security Policy and Procedures. Contractor and all associated sub-contractor employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative). The contractor shall also provide all information required for background checks to meet installation access requirements to be accomplished by TYAD Law Enforcement. Contractor workforce must comply with all personal identity verification requirements as directed by DoD, HQDA, and/or local policy.

Contractor and all associated sub-contractor employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by the government representative), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

A background check and approval from TYAD Law Enforcement is required for all contractor and subcontractor personnel prior to on-site access at TYAD. All persons seeking entrance to TYAD shall submit to and comply with all security standards and requirements in force at the time such persons are seeking entry. All contractors, regardless of resident status or citizenship, will be subject to vehicle search and intense in-processing by TYAD security personnel prior to being granted access to TYAD. This requirement is inclusive of on-site supervisory or managerial personnel and sub-contractor personnel that the contractor anticipates will be performing work or visiting on-site. This security screening process may be time consuming, and access may be delayed or denied. COR will provide specifics to the contractor after award and at least ten days prior to the expected visit date for completion. This security screening does not relieve the contractor of any responsibilities to conduct thorough pre-employment background checks and drug screening. Contractor workers will **not** be granted access to the work site until security screening is completed and access is approved. Any contractor personnel on-site who fail screening will not be permitted further access to TYAD. Ensure undocumented workers are not included in contracted work related to Army missions.

The company will ensure that its employees entering Army-controlled installations or facilities have obtained access badges and passes in accordance with facility regulations and that these badges and passes are obtained in advance so as not to delay the accomplishment of contracted services.

Pre-Bid Site Visit Controls: Any pre-bid site visits held before the contract award will be conducted under strict security controls. These protocols—including mandatory pre-registration for baseline vetting and constant escorting—apply to all potential bidders, regardless of any previous work history with TYAD or current installation access. During this public solicitation phase, a contractor's prior access or familiarity with the installation does not grant them a "need-to-know" for a new requirement. All

bidders will be treated as external entities, and the site visit is strictly for a visual inspection of physical conditions only.

Post-Award Information Release: Conversely, all project specifics—including exact locations, detailed plans, and mission context—can and must be provided to the contractor only after the contract is awarded and their personnel have completed all mandatory security training (AT, OPSEC, CUI). At this stage, the contractor has an established "lawful government purpose," and the controlled release of detailed information is appropriate and necessary for the performance of the contract.

Common Access Card (CAC): For contractors that do not require CAC, but require access to a DoD facility or installation: Contractor and all associated subcontractor employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (Army Directive 2014-05/AR 190-13); applicable installation, facility and area commander installation and facility access and local security policies and procedures (provided by Government representative); or, at OCONUS locations, in accordance with status-of-forces agreements and other theater regulations.

Collection of Badges: The Contractor shall account for all forms of Government-provided identification (even visitor badges) issued to the Contractor employees in connection with performance under this contract. The Contractor shall return such identification to the issuing agency at the earliest of any of the following, unless otherwise determined by the Government:

1. When no longer needed for contract performance
2. Upon completion of the Contractor employee's employment
3. Upon contract completion or termination

The Contracting Officer may delay final payment under a contract if the Contractor fails to comply with these requirements. The Contractor shall insert the substance of this clause, including this paragraph, in all subcontracts when the subcontractor's employees are required to have routine physical access to a federally controlled facility and/or routine access to a federally controlled information system. It shall be the responsibility of the prime Contractor to return such identification to the issuing agency in accordance with the terms set forth in of this section, unless otherwise approved in writing by the Contracting Officer. The company will return all issued U.S. Government Common Access Cards, installation badges, and/or access passes to the COR when the contract is completed or when a contractor employee no longer requires access to the installation or facility. Contractor personnel will obtain a vehicle pass for access to the military installation and Common Access Cards for computer access, if applicable.

Insider Threat Program: The contractor will establish and maintain an insider threat program to gather, integrate, and report relevant and available information indicative of a potential or actual insider threat, consistent with E.O. 13587 and Presidential Memorandum "National Insider Threat Policy and Minimum Standards for Executive Branch Insider Threat Programs."

Operations Security (OPSEC). OPSEC is mandatory for all and is not a one-time checklist, it is a dynamic, ongoing process embedded in every phase of planning, execution, and daily operations. It requires continuous critical thinking and vigilance from everyone who interacts with government information or operates on a government installation. This includes military personnel, Department of Defense civilians, contractors, subcontractors, and family members. OPSEC is not just a policy, it's a mindset. Its success depends on consistent awareness and execution by every member of the TYAD community.

At TYAD, all observations, communications, and experiences must be protected and must not be shared with anyone lacking a lawful government purpose or a validated business need-to-know. This disciplined approach ensures that emerging threats, evolving vulnerabilities, and shifting mission parameters are constantly reassessed and addressed to safeguard critical information.

OPSEC applies across the full spectrum of DoD missions, functions, programs, and activities under this contract. Practicing OPSEC daily is a requirement that is essential to mission success and the protection of national security assets.

Failure to properly safeguard sensitive or classified information—whether through negligence, willful misconduct, or ignorance—may result in administrative, disciplinary, contractual, or criminal consequences.

Applicability and Management of the Contractor OPSEC Plan The requirement for an Operations Security (OPSEC) Plan or an OPSEC Standing Operating Procedure (SOP) is based on the contractor's access to and handling of Critical Information and/or Controlled Unclassified Information (CUI), regardless of where that information resides. It is essential to distinguish between Information Security (INFOSEC), which protects data "at rest" within a system, and OPSEC, which protects data "in use" by governing the procedures and actions of personnel.

When contractor personnel generate, access or handle CUI—such as building floor plans, maps, technical manuals, operational schedules, or documents that contain information that falls within a CUI category www.dodcui.mil—they are required to have an approved OPSEC Plan/SOP. Contact the COR for more information on an OPSEC Plan/SOP. This plan is a formal, documented agreement that outlines how the contractor will protect the government's sensitive information. Even when CUI is handled exclusively on Government Furnished Equipment (GFE), the contractor remains responsible for the "human factor." The OPSEC Plan transfers the responsibility for protecting this information from the Government to the contractor by legally obligating them to establish internal procedures for everything from secure physical storage and controlled discussions to the proper destruction of materials. Without this plan, the Government retains all risk for how a contractor safeguards its data.

The management and approval of the contractor's OPSEC Plan is a shared responsibility, with defined roles at each stage. Per government acquisition and security policy, it is the Contracting Officer's Representative (COR) who is ultimately responsible for the initial identification and final enforcement of this requirement. The process is as follows: **The COR (designated technical representative) identifies the need for an OPSEC Plan based on the work described and writes the requirement into the Statement of Work (SOW)/checks this off on the Security Review Cover Sheet. After contract award, the COR enforces this by ensuring the contractor submits the plan on time.** The Contracting Officer (KO) ensures the requirement is legally binding in the final contract and is the sole authority to take contractual action for non-compliance. Finally, the Government OPSEC Officer, as the technical expert, is responsible for reviewing the submitted plan against AR 530-1 and providing the formal approval or rejection back to the COR.

Mandatory Annual OPSEC Training Requirements. In accordance with AR 530-1 (4-2-a), all contractors and subcontractors shall complete OPSEC Level I certification training annually (Initial and Continual – detailed below).

The Contracting Officer's Representative (COR) serves as the oversight authority: the COR verifies contractual compliance by collecting and reviewing certificates, ensuring they're submitted within the required timeframe – first 30 days of assignment.

According to AR 530-1 (para 4-2) and DoDM 5205.02, there is no "grace period" or minimum number of days on-site before OPSEC Level I Initial and Continual training becomes mandatory—any contractor, subcontractor, or support-service provider who requires access to TYAD information, systems, or facilities must complete both parts of their OPSEC Level I training.

OPSEC Level I training is comprised of two parts (Initial and Continual):

1. OPSEC Level I **Initial** training (annual):
    - To be completed within first 30 days of assignment to TYAD and annually thereafter – preferably before the job starts
    - Provides specific information about TYADs OPSEC program
    - Contractors and subcontractors must set up an appointment with TYADs OPSEC Officer for Initial training. The COR will provide the necessary point of contact to schedule this training.
    - Conducted by TYAD's OPSEC officer or alternate – training can be in person or via MS Teams (30 minutes) and is tracked by a TYADs OPSEC Officer via a local training form
2. OPSEC Level I **Continual** training (annual):
    - Commonly referred to as annual OPSEC training
    - To be completed within 30 days of assignment to TYAD and annually thereafter – preferably before the job starts

- Provides general information about OPSEC and reemphasizes sound OPSEC practices throughout the contract period
- Title of the training is: “OPSEC Awareness for Military Members, DoD Employees and Contractors” and is available online - https://securityawareness.dcsa.mil/opsec/index.htm
- Certificates of completion must go to the COR

OPSEC Measures to Protect Critical Information. All personnel are required to protect critical information at all times and in all forms. This section is critical because it moves beyond a simple, vague requirement to “practice OPSEC” and provides the contractor with specific, actionable, and enforceable rules of behavior.

All contractors and subcontractors shall implement the following mandatory OPSEC measures during the entire period of performance to protect critical and sensitive unclassified information:

1. Training and Compliance: Complete all mandatory OPSEC training as specified in this contract and actively apply all TYAD OPSEC measures in daily, contract-related operations.
2. Secure Communications: Avoid discussing government operations in public spaces or over unprotected communications (e.g., personal cell phones). Transmit Controlled Unclassified Information (CUI) only through authorized, encrypted channels as directed in the SOW/PWS = DoD Safe Access File Exchange (SAFE) is the accredited method for sending files that contain CUI, Personally Identifiable Information (PII), or other sensitive data that should not be transmitted over unencrypted, commercial email channels. The files are encrypted during the transfer process.
3. Public Release and Social Media Prohibition: Do not disclose or post any images, data, or operational details (e.g., maps, pictures, schedules, equipment, tactics) to any unofficial media, including personal or corporate social media platforms. All information or materials intended for public release require a documented OPSEC review by a TYAD certified OPSEC Level II reviewer. Coordinate all press releases through the COR and TYADs Public Affairs Office.
4. Reporting Requirements: Immediately report any attempts by unauthorized third parties to solicit sensitive information to the TYAD Security Operations Branch, the contract POC, and the contractor's Facility Security Officer (FSO).
5. Credential Control: Conceal or remove all government-issued badges and identification when off the installation. Do not duplicate, loan, or leave credentials unattended (CACs, badges, and/or parking passes or placards). Report any lost or stolen passes/badges/credentials to TYAD Law Enforcement Branch. The COR will provide all POC contact information.
6. Protection of Sensitive Data: Mark and protect internal company data related to this contract (e.g., schedules, deliverables, vulnerability reports) as CUI. All government-provided information, such as drawings and technical data, must be protected in accordance with DoD, Army guidance and guidance within contract package documents.

7. Information Disposal: At contract completion or upon Government request, return all government information to the COR or destroy it in accordance with approved TYAD procedures for handling CUI.

Photography or Videography. Contractors and subcontractors who take photos or video at TYAD must notify their COR at least fourteen business (14) days in advance and complete OPSEC Level I Initial training. The COR will provide the contractor with the security branch's points of contact after the contract is awarded. All individuals must follow TYAD policy regarding photography/videography and the use of personal electronic devices.

All photos and videos must undergo an OPSEC Review—per AR 530-1 Chapter 4—to evaluate them against TYAD's Critical Information List and identify any vulnerabilities. That review must be fully documented and signed off by a TYAD employee who holds OPSEC Level II certification before disseminated.

Information Security (INFOSEC). The contractor shall comply with all applicable regulations for the protection of government information. Information handled under this contract is categorized as either Controlled Unclassified Information (CUI) or Classified National Security Information (CNSI).

Controlled Unclassified Information (CUI) The handling, marking, safeguarding, and destruction of all CUI shall be in strict accordance with DoD Instruction 5200.48, *Controlled Unclassified Information (CUI)*. Specific contractor responsibilities are detailed in the "Safeguarding CUI" section of this document.

CUI Training Requirement Any contractor or subcontractor personnel who will generate or have access to CUI under this contract must complete mandatory CUI training prior to accessing such information. The "DoD Mandatory Controlled Unclassified Information (CUI) Training" course available on the DCSA CDSE Security Awareness Hub (https://securityawareness.dcsa.mil/cui/) satisfies this requirement. Completion certificates shall be provided to the COR upon request.

Contractor Responsibilities for Handling CUI – even if it is their own information that must be controlled (example: Personal Identifiable Information, etc.). Contractors are responsible for handling CUI when it is created, collected, or maintained in performance of a government contract. The contractor shall comply with all CUI requirements outlined in Executive Order 13556 and 32 CFR Part 2002. www.dodcui.mil The contractor's responsibilities include, but are not limited to:

- Marking: Applying uniform CUI markings to all CUI data and deliverables.
- Access Controls: Restricting CUI access to personnel with a lawful government purpose and validated need-to-know.
- Flow Down: Ensuring all CUI protection requirements are passed down to subcontractors.
- Physical Safeguarding: Implementing appropriate physical controls (e.g., locked storage, controlled-access areas) for all CUI, whether in hard copy or on electronic media.

- Incident Reporting: Reporting any actual or suspected loss or compromise of CUI to the COR immediately.
- Disposition: Returning all CUI to TYAD control or destroying it in accordance with DoD and Army guidelines upon contract completion.

Physical Security.

Safeguarding of Government Property - The Contractor shall be responsible for safeguarding all government equipment, information, and property provided for Contractor use. At the close of each work period, government facilities, equipment, and materials shall be secured.

Key Control - The Contractor shall establish and implement methods of making sure all keys and key cards issued to the Contractor by the Government are not lost, misplaced, or used by unauthorized personnel.

- No keys issued by the Government shall be duplicated.
- The Contractor shall develop a key control procedure, to be included in their Quality Control Plan, which includes procedures for the turn-in of keys by personnel who no longer require access.
- The Contractor shall immediately report any lost or duplicated keys to the Contracting Officer (KO). In the event a key is lost or duplicated, the Government may, at its option, re-key or replace the affected locks, and the total cost shall be deducted from the monthly payment due to the Contractor.

Lock Combinations - The Contractor shall establish and implement methods to ensure that lock combinations are not revealed to unauthorized personnel when applicable. The Contractor shall ensure combinations are changed when personnel with knowledge of the combination no longer have a need-to-know.

6. SERVICE or EQUIPMENT INSTALLATION CONTRACTOR SAFETY STANDARDS FOR TYAD

Below are some “installation specific” safety standards which contractors are required to adhere to while performing any work on Tobyhanna Army Depot. It is the contractor’s responsibility to always incorporate these particular requirements into their daily operations while under contract and to institute these specifics into their overall site

safety controls. These do not substitute or deflect in any way the requirement to institute and adhere to all OSHA 29 CFR 1910 & 1926 and USACE EM385-1 safety standards, as well as all applicable contractual Federal Acquisition Regulations while performing the work under this contract on Tobyhanna Army Depot.

It is the responsibility of the contractor to enforce the below requirements as well as all current revisions of the above referenced standards. Failure to enforce safety requirements on the depot can result in immediate stop works, safety stand down orders and even complete termination of the contract.

Important Phone Numbers:

Fire or Emergency: 911
Fire Department – (Non-Emergency):
Security:
Safety Office:

The COR will provide a list of necessary on-post contact numbers to the contractor upon contract award.

S1.0 THE CONTRACTOR IS SOLELY RESPONSIBLE AND LIABLE FOR JOB- SITE SAFETY

1. Review of the project plans and other documents by any government appointed official does not constitute an acceptance of Federal responsibility or liability for the adequacy of the safety measures identified for the job or for the Contractor's compliance with all applicable safety rules and regulations.

2. The Contractor remains solely responsible and liable for job-site safety at all times during the term of the contract. No outside personnel (other than ET, COR, TYAD Safety, or other government appointed contract personnel) are allowed onto the job site at any time during contract without prior permissions and/or escort by the ET, COR or KO.

3. Tobyhanna Army depot has restrictions on the use of fossil fuels in all buildings. When it is determined that electric or other alternatively fueled vehicles are insufficient or unavailable for movement of material within the buildings on the installation, fossil-fueled vehicles can be used only when all alternatives of accepted electric material movement equipment have been considered, and the last option is use of a fossil fuel vehicle or project failure. This includes any situations where safety of employees and equipment may be jeopardized. Convenience will never be an acceptable justification to utilize fossil-fueled vehicles. The Government Designated Representative (GDR) will notify the appropriate supervisor(s) or leader(s) in the area where the need to utilize a fossil fuel vehicle is required. The supervisor / leader will take the necessary steps to notify the employees in the work

area of the option to leave the area during the material movement process. The GDR and Contractor will also document all actions the Contractor took to utilize electric or other alternatively fueled vehicles. The documentation will specifically state why electric or alternatively fueled vehicles are insufficient and all mitigation efforts used to minimize the effects of fossil-fueled vehicles to include information as to any appropriate scrubbers that can be utilized along with any ventilation or exhaust systems that can be used to externally vented to the outside of the facility. The documentation must be submitted to the TYAD Safety office for approval prior to any equipment being used. A final copy of the Approved documentation will be provided to the TYAD Safety Division.

4. All direct construction supervision, including subcontractors, must as a minimum, complete an OSHA 30-hour safety course for construction. These certificates must be submitted as part of the site safety plan BEFORE construction activities start.

5. **RED CARD PROGRAM** - Tobyhanna Army Depot utilizes a program to allow employees to stop an action which is considered unsafe. Employees carry small red cards that can be thrown down when employee sees any action they consider unsafe. Work ceases until TYAD management can decide if it is safe or not. Contractors are required to comply with this program. If a TYAD employee presents the red card to the contractor, the contractor must stop working until the COR and Safety Office can determine if there is a safety hazard or not.

6. All contractor personnel, to include subcontractors, vendors, suppliers, or visitors, when performing any type of work activity, or gaining access through an occupied area or shop - must have all applicable PPE that is required for the area to include, but not limited to, hardhats, safety glasses, hearing protection, and respirator protection. Notify both COR & Area Supervision, for access approval and prior to any work activities being performed.

S2.0 CODE COMPLIANCE

As noted in Tobyhanna Army Depot Safety Regulation 385-1 - TYAD follows all requirements and is certified as an ISO 45001 facility. Accordingly, the contractor shall comply with and maintain these high safety standards and provide full compliance with all applicable safety regulations and standards. The Contractor shall maintain, monitor, and enforce employee compliance with all applicable rules, regulations, and codes.

Tobyhanna Army Depot requires full contractor compliance with all safety regulations and standards. The Contractor is responsible for maintaining, monitoring, and enforcing all rules, regulations, and codes, by ALL personnel working for the contractor including all subcontractors. These codes include:

Title 29 Code of Federal Regulations-1910 (OSHA General Industry Standards)

Title 29 Code of Federal Regulations-1926 (Construction Industry Standards)

National Fire Protection Association Codes

Uniform Facilities Code

Unified Facilities Guide Specifications (UFGS)

USACE EM385-1-1 (Safety and Occupational Health Requirements)

All other codes as required to maintain safety standards.

S3.0 JOB HAZARD ANALYSIS (JHA) / ACTIVITY HAZARD ANALYSIS (AHA)

Prior to the start of work, the contractor shall prepare a JHA / AHA for each phase of work that will be done under the contract. This will be completed in accordance with all applicable OSHA safety requirements. A phase is any operations involving a certain type of work. Examples include demolition, excavation, masonry work, concrete pouring, roofing, and electrical wiring. Work done by each subcontractor is also a phase. The JHA / AHA will:

1. List the activity being performed and identify the sequence of work steps.

2. List the hazards associated with each step, and the procedures and training required to eliminate or reduce the risk to an acceptable level.

S4.0 SITE SPECIFIC SAFETY & ACCIDENT PREVENTION PLANS

Contractors will submit a written Site-Specific Safety / Contractor Accident Prevention Plan prior to beginning activities. The plan must follow the guidelines in OSHA 29 CFR 1926 or 1910 as applicable.

1. Who will implement the plan, including who is responsible for safety and accident prevention?

2. A means for coordinating and controlling subcontractors and suppliers.

3. Safety training.

4. Who will investigate accidents?

5. Emergency response.

6. Job site cleanup and safe access.

7. Public safety requirements such as signs and barricades.

S5.0 MACHINERY SAFETY, RISK ASSESSMENT, AND VALIDATION REQUIREMENTS

The below defines the mandatory machine safety, risk assessment, and validation criteria for all machinery, integrated subsystems, and equipment delivered, installed, or modified by the Contractor at Tobyhanna Army Depot (TYAD). These requirements are established to maintain TYAD's accredited ISO 45001 Occupational Health and Safety Management System and AS9100/9110 Quality Standards.

COMPLIANCE STANDARDS & GUIDELINES

The Contractor shall ensure that all equipment, machinery, and integrated subsystems delivered under this contract are designed, manufactured, and validated to achieve an acceptable level of risk.

System Safety Engineering: Shall comply with MIL-STD-882E (Department of Defense Standard Practice for System Safety) and ANSI B11.0 (Safety of Machinery - General Requirements and Risk Assessment).

Electrical & Control Subsystems: Must comply with NFPA 79 (Electrical Standard for Industrial Machinery) and relevant OSHA 29 CFR 1910 standards.

TYAD Safety & Health Requirements: Any onsite contractor activities (such as installation, validation, or testing) shall comply with the US Army Corps of Engineers Safety and Health Requirements Manual (EM 385-1-1).

MANDATORY TASK-BASED RISK ASSESSMENT

The Contractor shall conduct a comprehensive, task-based Machine Risk Assessment (MRA) for all phases of the equipment lifecycle. This assessment must explicitly evaluate hazards associated with the following profiles: Standard industrial operations. Maintenance and system troubleshooting. Equipment setup, tooling changes, and calibration. Clearing line jams and mechanical debris. Cleaning and equipment sanitation protocols. Lockout/Tagout (LOTO) procedures, designed in strict accordance with OSHA 29 CFR 1910.147 (Control of Hazardous Energy) and fully aligned with local

Tobyhanna Army Depot (TYAD) safety regulations, permitting workflows, and local LOTO template requirements.

HAZARD MITIGATION HIERARCHY

The Contractor shall apply the hazard mitigation hierarchy to resolve identified operational risks. Hazards must be addressed in the following strict order of precedence:

- Elimination or Substitution: Eliminate the hazard entirely through inherent design choices (e.g., eliminating pinch points) or substitute hazardous materials/processes with non-hazardous alternatives

- Engineering Controls: Implement physical guards, barriers, enclosures, or safety-rated devices (e.g., light curtains, safety mats, interlocks) to isolate personnel from the hazard.

- Awareness Devices: Install visual and audible warning systems, such as strobe lights, backup alarms, and safety signage, to alert personnel to residual hazards.

- Administrative Controls: Develop safe work procedures, standard operating instructions, and mandatory training programs to limit exposure time or dangerous behaviors.

- Personal Protective Equipment (PPE): Mandate the use of appropriate safety gear (e.g., safety glasses, steel-toed boots, arc flash protection) as the final line of defense.

VERIFICATION AND VALIDATION (V&V) REQUIREMENTS

The Contractor shall provide documented evidence that all safety systems function exactly as designed and reduce risks to acceptable levels. All V&V activities must strictly adhere to the following regulatory benchmarks:

Safety Function and Hardware Verification: The Contractor must execute functional testing on all safety-related control circuits, including emergency stops (E-stops), interlocked guards, and presence-sensing devices. Testing methods must comply with ANSI B11.26 (Functional Safety - Control Systems) and NFPA 79 (Electrical Standard for Industrial Machinery).

Fault Injection and Failure Mode Validation: Testing must simulate component failures (e.g., short circuits, broken wires, sensor misalignments) to verify that the system fails only into a predictable, safe state. This validation process must align with MIL-STD-882E Section 4 (System Safety Program Requirements) and the risk reduction metrics of ANSI B11.19 (Performance Requirements for Risk Reduction Measures).

OSHA Compliance Verification: The final physical configuration of all physical guarding, perimeter barriers, and points of operation must be validated against OSHA 29 CFR 1910 Subpart O (Machinery and Machine Guarding).Military Installation Inspection:

Prior to equipment integration at TYAD, all electrical and safety components must pass a field validation audit compliant with US Army Corps of Engineers Manual EM 385-1-1 Section 11 (Electrical) and Section 16 (Machinery and Mechanized Equipment).Validation Report: A final, signed Safety Validation Report must be submitted to the TYAD Contracting Officer Representative (COR) prior to final equipment acceptance.

S6.0 FALL PROTECTION

1. Personnel performing works at a height of six feet or more from any lower level shall comply with OSHA 29 CFR 1926.500 through 1926.503 safety standards for any type of new installations. OSHA 29 CFR 1910-28 shall apply to any type of servicing on previously installed equipment.

2. There are currently no certified anchorage points or permanent guardrail systems on any TYAD roof. Most roofs of the depot are more than 20 feet high.

3. Contractors and their employees must be protected from falling off the edge of the roof, regardless of how briefly the employees are at the edge of the roof.

S7.0 ELECTRICAL SAFETY

Follow the current Tobyhanna Army Depot standard. This standard is based on NFPA 70E.

Copies of the TYAD Electrical standard may be obtained by request from the ET, COR or KO on the project or service contract.

All equipment shall be certified by a Nationaly Recognized Testing Laboratory (NRTL) in accordance with 29 Code of Federal Regulations (CFR) 1910.303.

29 CFR 1910.303(a): *Approval*. The conductors and equipment required or permitted by this subpart shall be acceptable only if approved, as defined in § 1910.399.

29 CFR 1910.399: *Acceptable*. An installation or equipment is acceptable to the Assistant Secretary of Labor, and approved within the meaning of this subpart S:

(1) If it is accepted, or certified, or listed, or labeled, or otherwise determined to be safe by a nationally recognized testing laboratory recognized pursuant to § 1910.7;

Army Regulation 385-10, Army Safety Program, Paragraph 23-5.d: *Tools and equipment.* Electrical equipment that contains or produces energy greater than 50V

alternating current (AC) or 100V direct current (DC) must meet one of the following conditions to be safe for use:

(1) Listed by an NRTL and used as intended (for example, as described in the manufacturer's instructions or technical manual). All purchased electrical equipment must be NRTL-listed if available, even if a less expensive unlisted product is available. NRTL approved equipment is stamped with a listing symbol. NRTL listing symbols can be found at https://www.osha.gov/dts/otpca/nrtl/nrtllist.html.

S8.0 DEPOT REQUIRED PERMITS / APPROVALS

Permits are required for:

1. **Excavation**: Contractors must utilize the PA 1 Call system and also coordinate with contracting officer representative (COR) for a TYAD dig permit for any excavations prior to any groundbreaking including digging, drilling and stake driving.

2. **Trenching**: Contractors will adhere to OSHA requirements and receive approval from TYAD Safety office before any trenching deeper than 5 feet is performed. Notifications of such activities will be provided to the COR along with required plans, requests and permits prior to any trenching works being performed. Contractor is responsible for field verifying all utilities and underground entities. Excavation or trench greater than 18 inches in depth that remains open greater than (1) day OR left unattended for any period of time shall have a safety orange construction fence installed around the perimeter of the opening. Caution tape or cones for this purpose is unacceptable.

3. **Confined Space**: All confined space works on TYAD are to be considered as permit required entries, (unless reclassified by the TYAD Safety office,) and Contractor must first request and be provided with an approved "signed" permit from TYAD Safety Office prior to any confined space entry. Contractor will refer to all OSHA requirements and must have a confined space plan and all appropriate safety equipment. Contractor is to request approval from TYAD Safety office through COR prior to entry.

4. **Burning / fire***:* Hot work permits must be obtained daily from the Fire Department.

5. **Cranes:** For use of cranes and all WHE and LHE at TYAD see S.10.13

6. **Army Radiation Permits:** Non-Army agencies (including other military Services, vendors, and civilian contractors) require an Army Radiation Permit (ARP) to use, store, or possess ionizing radiation sources on TYAD (see 32 CFR 655). Non-Army applicants will apply by letter with supporting documentation to the Depot Commander. The letter should be submitted so that the Depot Commander receives the application at least 30 days before the requested start date of the permit. The

ARP application will specify start and stop dates for the ARP and describe the intended use of the radioactive material.

For sealed sources of radiation, i.e. Moisture Soil Density Gauges, the application must include a valid Nuclear Regulatory Commission (NRC) Radioactive Materials License that allows the applicant to use the source as specified in the ARP application, current leak test certificates, operator training records and calibration certificates for any equipment that may be utilized at TYAD.

For machine produced ionizing radiation sources, i.e. X-ray Equipment, the application must include the appropriate state authorization that allows the applicant to use the source as specified in the ARP application along with operator training records and calibration certificates for any equipment that may be utilized at TYAD.

ARPs will not be issued for more than 12 months at a time.

S9.0 CONFINED SPACES

1. All Confined Spaces at TYAD are considered as Permit-Required Confined Spaces unless reclassified by TYAD Safety office after a thorough review of the area and the work being planned.

2. Contractors must first notify the COR and receive TYAD Safety office approvals prior to gaining access or opening any confined space area.

3. Contractors must fully comply with all OSHA regulations for Confined Space Operations, including on-site use and availability of a Confined Space Entry Permit / Checklists, along with prior approvals of their Accident Prevention Plan and associated Activity Hazard Analysis (AHAs) for the work to be performed.

4. The contractor and/or the COR will then notify the TYAD Safety office and TYAD Fire and Emergency Services of the Confined Space Entry timelines and schedules.

5. Upon completion, the contractor will notify the TYAD Safety Office and discuss whether any new hazards were added to the Confined Space and will submit the completed Confined Space Entry Permit / Checklist for record.

S10.0 LOCKOUT/TAGOUT PROCEDURE

1. The Contractor shall perform this work in accordance with 29 CFR § 910.147-The Control of Hazardous Energy requirements.

2. The Contractor shall notify the COR that a lockout/tag out system is going to be used.

3. The contractor is to request the COR to notify them if TYAD is using any lockouts / tag outs in the construction area.

4. The Contractor shall locate and identify all isolating devices.

5. The Contractor shall shut down the equipment normally.

6. The Contractor shall isolate all energy using appropriate methodology.

7. After all work is complete, the Contractor shall remove the energy isolating device and restore the equipment to service.

8. The Contractor shall notify the COR that energy is again restored.

S11.0 PROTECTION TO THE DRINKING WATER SYSTEM

1. The contractor will not perform any work on the depot potable water system until prior approval is obtained from the Environmental Branch and the certified operator through the Directorate of Installation Services COR.

S12.0 PROTECTION OF PERSONNEL

At no time is any depot employee to be put at risk to illness or injury. No construction actions are exempt from this requirement.

1. Where pedestrian and driver safety is endangered, use appropriate traffic barricades. Use anchor barricades to prevent displacement by wind. Institute PA DOT regulations and OSHA requirements. Notify the COR prior to beginning such work.

2. Where demolition is required, a Demolition Plan describing the steps and individual Definable Features of Works (DFOWs) as well as safety protocols, controls and oversight is required to be submitted to the COR for review prior to works being performed. Continuously evaluate the condition of the structure being demolished and take action to protect personnel working around the project site. No structural element will be left standing without sufficient support to prevent collapse.

3. Contractor shall provide personal protective equipment (PPE) and provide training for use, for all visitors requiring entry into the regulated area.

4. Subcontractors, vendors, and delivery personnel are the responsibility of the prime contract and must follow the same regulations the prime contractor does.

S13.0 FIRE AND EMERGENCY SERVICES

Hot Work Permits will be issued by Fire Department upon request. All requests must be made at least thirty (30) minutes prior to the expected start time by contracting the fire department.

1. Contractors are required to have fully charged and operable contractor provided fire extinguisher, in quantities and properly spaced per OSHA requirements that are appropriate for the type of possible fire. Fire extinguisher shall be immediately available for inspection by the fire department upon an inspection of the worksite and shall remain at the work site at all times. At a minimum, 10 pound class 4A, 60B or C multi-purpose dry chemical fire extinguisher or equivalent shall be provided.

2. A fire watch must be in place during the hot work and for 30 minutes after the HWP operation. Upon completion of the thirty (30) minute, post hot work fire watch, the contractor shall contact the fire department to report the work is complete.

3. Use of a plasma torch will require special approval by the fire department.

4. Any fire, even one that is extinguished, must be reported to the fire department.

5. Ambulance services are provided at a cost to contractors. The contracted ambulance service provider will transport to the nearest hospital. Advanced Life Support, helicopter transport, etc. is all at the contractor's expense.

6. The fire department will respond to all fire, ambulance, hazmat and confined space incidents.

S14.0 IF AN INCIDENT HAPPENS

1. **Any serious injury or medical emergency**:
   - Immediately call emergency responders
   - Dial 911 and give accurate location and nature of emergency. Make sure to tell the operator that you are calling from Tobyhanna Army Depot.
   - Send someone to the nearest exit to assist responders.
   - Treat victims to the best of your ability.
   - Notify COR / call work order desk at *TBD* if there is any blood or body fluids that must be cleaned up.

2. **In the event of the smell of natural gas:**
   - Call dial 911and give accurate location and nature of emergency. Make sure to tell the operator that you are calling from Tobyhanna Army Depot.
   - Have all personnel evacuate the area if the smell is significant.

- Upon arrival of fire personnel, provide information as to specific equipment and exact location of potential leak.

3. **In the case of a fire**:
   - If the fire is small, use a fire extinguisher and call 911.
   - Otherwise, dial 911 and pull the fire alarm.
   - Evacuate the building.

4. **Accident/Injury Reports and OSHA 301 Reports**:

The contractor shall report to the COR and KO, - Immediately but no later than eight (8) hours, any Fatality, In-patient hospitalization, Amputation, Eye loss or Property damage over $600,000. Similarly, contractor shall report to the COR and KO, – Immediately, but no later than twenty-four (24) hours, all other accidents or near misses.

Notifications shall be followed up within five (5) working days of all incidents (reportable or not) with an OSHA 301 report including all available facts relating to each instance of personal injuries and of loss / damage to Government property.

For any accident that results in illness or injury that requires more than first aid treatment, TYAD Safety & Health Office has the option to have the contractor immediately secure the accident area until released by the accident investigation authority as designated by the Commander. If the Government elects to conduct an investigation of the accident, the contractor shall cooperate fully and assist authorities until the investigation is complete. If requested after the investigation is completed, the contractor shall provide a Corrective Action Plan related to the incident to the COR & KO.

COR to provide copies of all OSHA 301 incident reports and any Correction Action Plans to the TYAD Safety office when available.

S15.0 CRANE LIFT OPERATIONS AT TOBYHANNA ARMY DEPOT

A Lift Plan for Crane Operations will be submitted to the ET/COR for approval by the TYAD Safety Office *at least 14 days* prior to a lift operation. It will conform to all applicable OSHA regulations and requirements and shall include:

1. A description of the operation to be performed, specific personnel assignments (Lift Director, Safety Coordinator, Operator, rigger, etc.) and signaling and any other details pertaining to activities during the lift.

2. A drawn Site Plan with specifications including work zone, support equipment locations, evacuation area, traffic control, electrical power line clearances (if applicable), lift path, surface conditions at crane location, etc.

3. Training/Certifications (scans) for crane operator and other lift-team members included in the lift operation.

4. Equipment nomenclature and a certificate of comprehensive annual inspection records, including any deficiencies and corrective action.

5. Load chart for crane, with target capacities specific to the crane/boom configuration and lift details clearly marked.

6. Lift calculations, including rigging components and configuration.

7. Weather conditions are always part of the ongoing safety assessment and may result in rescheduling of the lift.

8. Only approved operators are allowed to operate or move the crane for any reason.

A Production Lift Plan pertains to repetitive lifts within a work project and may be outlined with one lift plan depicting the nomenclature and general capacities of the equipment to be utilized. Besides the eight items above, the plan will also include how often the crane will be used and how traffic and personnel safety will be handled. A separate traffic plan will be required for vetting and approval prior to any lifts taking place.

S16.0 APPLICATION OF ANY ODOR PRODUCING MATERIAL

1. Any application of any paint, epoxy, adhesive or anything else that produces an offensive odor must be coordinated with the COR or POC before starting. This is particularly true of the construction work in a building occupied by Tobyhanna employees.

2. It is highly recommended that this type of work be planned for off hours, weekends, or holidays to avoid shutdowns of operations due to these offensive odors. Odors during curing times for products shall also be considered.

S17.0 CONTROL OF RESPIRABLE CRYSTALLINE SILICA

1. Contractors are required to follow the OSHA standard 29 CFR 1926.1153 which requires employers to limit worker exposures to respirable crystalline silica and to take steps to protect their workers and TYAD personnel.

2. Contractors shall establish and implement a written exposure control plan that identifies tasks that involve exposure and methods used to protect workers, including procedures to restrict access to work areas where high exposures may occur.

3. Restrict housekeeping practices that expose workers to silica by utilizing engineering controls such as local exhaust ventilation, using “wet spray” methods when cutting or drilling and providing proper respiratory protection and other PPE as applicable.

S18.0 OPERATION & MAINTENANCE MANUALS

1. The Contractor shall provide to the COR a copy of all Operation and Maintenance (O&M) Manuals and Parts Manuals for any equipment provided.

2. The O&M Manuals shall contain a complete set of mechanical drawings and diagrams; a complete set of electrical drawings and diagrams including electrical schematics; logic circuitry descriptions; spare parts list; operator and maintenance instructions for operating, testing, and maintaining all system components.

3. The O&M Manuals shall contain complete detailed instructions and schedules for system PM.

4. The O&M Manuals shall contain a detailed description of the lock-out/tag-out procedures needed to bring the system and individual components to a zero-energy state for maintenance and servicing.

5. The O&M data must be consistent with the manufacturer's standard brochures, schematics, printed instructions, general operating procedures, and safety precautions.

IN ANY CONFLICT BETWEEN STANDARDS, THE STRICTER OF THE TWO SHALL APPLY. IF UNSURE CONTACT THE COR / ET VIA PROPER RFI PROTOCOLS FOR VERIFICATION THROUGH THE TYAD SAFETY OFFICE.

7. Standard Specifications for Projects Under the National Environmental Policy Act (NEPA) in Accordance with 32 CFR 651 Proponent ELTY-ISP-N

Spill Response Procedures 1-2-3

1. Stop work
2. Call 911
3. Evacuate Area

*********Damaged Asbestos?*********

Environmental Questions?

Call Environmental Branch

1. Air Pollution Control

The contractor must control fugitive emissions, including dust, during the course of their contract. The contractor must obtain approval from the Environmental Branch (EB) prior to exhausting equipment to the outside. The contractor must not allow any pollutant or particulate matter to be released to the atmosphere at levels that are visible from outside of Tobyhanna Army Depot (TYAD). The contractor must not perform work that will release pollutants or particulate matter to the atmosphere when the wind speed exceeds ten miles per hour and will result in adverse effects to the surrounding areas. TYAD will monitor the wind speed; it is the contractor's responsibility to obtain wind speed information through the Contracting Officer Representative (COR).

2. Asbestos

The contractor must ensure that all materials used in the performance of this contract are asbestos-free.

Unless specified in the contract, the contractor must not disturb any existing Asbestos-Containing Material (ACM) in the performance of this contract. If ACM, or suspect ACM might be disturbed in performance of this contract, the contractor must avoid encountering the material and immediately notify the COR and the Contract Administrator in writing. The COR must coordinate with EB to have the material tested to determine if there is ACM. If the material is determined to be ACM and the contractor cannot avoid disturbing the material, the COR will notify the Contracting Officer. The Contracting Officer will direct a change pursuant to the contract clauses entitled "Changes" and "Differing Site Conditions." If ACM, or suspect ACM has been disturbed, the contractor must immediately notify the COR and call the EB. The contractor will shut down and not move any equipment or supplies near the damaged ACM. The

contractor will evacuate all non-contaminated contractor personnel from the immediate vicinity. Any contractor personnel thought to be contaminated with asbestos must remain in the area until the EB responds. If the damaged material is determined to be ACM and there is potential for further damage, the Contracting Officer will direct a change pursuant to the clauses of the contract clauses entitled “Changes” and “Differing Site Conditions.”

Asbestos abatement required under the contract as originally awarded must be in accordance with United Facilities Guide Specification 02 83 14 00 10 and as otherwise required in the contract. Asbestos abatement not required under the contract as originally awarded, can be incorporated into the existing contract via contract modification, or by the Government taking responsibility for the asbestos abatement. The method of acquiring the abatement is at the discretion of the Government. The contractor must have an asbestos abatement work plan that has been approved by EB prior to beginning any asbestos abatement work.

3. Backflow

The contractor shall have a backflow prevention device installed on all contractor equipment that is connected to TYAD’s water distribution system. The contractor shall have a water meter installed to monitor water consumption during all phases of the contract. Water use will be reported monthly to the COR.

4. Burning

The contractor must not burn refuse and debris anywhere on TYAD.

5. Buy Recycled-Content Materials

The Contractor must comply with Resource Conservation and Recovery Act (RCRA) Section 6002 (42 U.S.C. 6962, Federal Procurement) in the acquisition of materials with recycled content. Specific designated items in this contract for which recycled content standards have been established have been set forth in the specification (e.g., insulation, roofing materials, carpet, carpet pad, paint, floor tiles, shower and restroom dividers). Recovered Material Certification: As required by the RCRA, the contractor must certify that the percentage of recovered materials to be used in the performance of the contract will be at least the amount required by the applicable contract specifications (see Federal Acquisition Regulation (FAR) Provision 52.223-4, Recovered Material Certification). Prior to application for final payment, the contractor must provide a report in accordance with FAR Clause 52.223-9, Estimate of Percentage of Recovered

Material Content for Environmental Protection Agency (EPA) Designated Items, to the Contracting Office. Compliance with this program does not relieve the contractor from meeting all other specification requirements.

6. Cultural Resources

The contractor must not adversely affect any property listed on the National Register of Historic Places (NRHP) or properties eligible for inclusion on the NRHP without consultation and approval from the EB through the COR. If there is a discovery of any historic properties, including archeological sites and graveyards, work will cease immediately until requirements of National Historic Preservation Act, as amended, have been met. All archaeological artifacts found at TYAD or TYAD-controlled properties are U.S. Government property until a determination is made otherwise.

7. Demolition Notification

If a project involves the demolition of any load-bearing structural members, whether or not asbestos is present, 25 days prior to the demolition, the Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification Form 2700-FM-BAQ0021 must be submitted to EB as specified in the Unified Facilities Guide Specification 02 82 13.00 10.

8. Drinking Water

The contractor must not perform any work on the TYAD potable water system prior to obtaining approval from the EB and the Installation Planning and Maintenance Division certified operator through the COR. If a permit is required due to construction or proposed chemical feed changes, it will be the responsibility of the contractor to obtain all permits associated with the project. Permit applications will first be reviewed and approved by the Environmental Branch before being submitted to regulatory authorities. Any piping or additions added to the TYAD water system must be disinfected following "American Water Works Association circular C651-14 "Disinfecting Water Mains." Construction will be kept outside of drinking water wellhead protection zones when feasible. All new buildings and remodeled buildings will be equipped with a water meter that can easily be read from the exterior of the building.

9. Endangered Species

The contractor is responsible for meeting requirements of the Endangered Species Act of 1973. The contractor must not disturb any endangered species, their habitat or offspring during the implementation of this contract.

10. Emergency/Spills

All emergencies and spills must be reported to the TYAD Fire Department by calling 911 from a TYAD phone or *TBD*. If a 911 call is placed on a cell phone, the call will go to the Monroe County Emergency Office. Notify the Monroe County Emergency Office that you are at TYAD, and the call will be forwarded to TYADs Fire Department. The contractor must ensure all personnel working on site are trained in the proper procedure according to 29 CFR 1910.120 (if applicable) to initiate a spill response to handle the hazardous substances they are working with. The contractor will take the necessary actions to prevent and contain spills of hazardous materials.

11. Energy Resilience and Mission Readiness

The Energy Policy Act of 2005 section 109 and the Energy Independence and Security Act of 2007 require all new construction at federal facilities to be 30% better than ASHRAE 90.1. Energy Policy Act of 2005 section 104 and the Energy Independence and Security Act of 2007 require all new equipment to be Energy Star qualified when available. This is applicable to heating, ventilation and air conditioning (HVAC) equipment, plumbing, building materials, lighting, commercial food service equipment and appliances.

12. Environmental Automation and Control Systems

The contractor will not alter, modify, remove or tamper with any environmental automation or control system unless previous arrangement has been made with EB. This includes sensors, programmable logic controllers, equipment housing, power supplies, meters or other hardware/sensor technology.

13. Erosion and Sedimentation Control

The contractor shall protect streams, lakes and wetlands from sediment discharges caused by the contractor's activities. The contractor shall also provide (where applicable) an erosion and sedimentation control plan in compliance with state and local laws and regulations, to the COR for approval prior to executing any soil-disturbing activities. The contractor must submit a National Pollutant Discharge Elimination System Permit (NPDES) to the Pennsylvania Department of Environmental Protection (PADEP) prior to any construction activity that encompasses more than one acre. All permits must be reviewed and approved by the EB prior to being sent to any regulatory authority. The contractor shall not disturb any wetlands. The contractor is to place silt sock around dirt, rock, or construction debris to ensure runoff does not occur. The contractor will place silt sock, or drain covers around/in storm drains surrounding the construction and downstream of the site. Contractor will remove all silt fencing and other temporary control measures once the site is stabilized. Contractor will remove all spoils from TYAD unless a previously approved disposal site has been established.

The contract COR will be responsible for management and control of the spoil's disposal site.

14. Fluorescent and Mercury-Bearing Lamps

The contractor is to collect, containerize, manage and recycle fluorescent and mercury-bearing lamps in accordance with 40 CFR 273, Standards for Universal Waste Management. A copy of the manifest/Bill of Lading must be given to the EB through the COR five days in advance of shipment by the contractor so that it can be reviewed for accuracy and completeness. The contractor must install low mercury bulbs when available.

15. Hazardous Materials Stored and Labeled

The contractor must ensure all hazardous materials (HM) at the work site are properly stored and labeled. The contractor must not leave any HM behind at the completion of the job for any reason. HM must not be stored outside without adequate secondary containment and shelter.

16. Hazardous Waste

The contractor must ensure that all hazardous wastes (HW) at the work site are properly stored and labeled in a pre-approved location designated by the EB. The contractor must provide copies of any shipping documents for HW/Universal Waste/Toxic Substances Control Act waste. If the TYAD EPA number is being used for shipping purposes, only EB is authorized to sign a manifest, and the manifest (or copy) must be supplied prior to the day of shipment for review. The EB will keep original copies. If HW or waste requiring special handling (e.g., asbestos) is being turned over to the government for disposal, the contactor must notify the EB through the COR when the waste is ready to be moved.

17. ISO 14001

TYAD is an ISO 14001 certified facility. All contractor and subcontractor employees on site must comply with TYAD Regulation 200-5, "Environmental Management System (EMS)." The contractor may obtain these regulations through the project COR.

18. Limit of Disturbance

The contractor must confine the limit of disturbance of the project to the smallest area possible.

19. Mercury-Bearing Equipment

The contractor must not install any equipment, switches, or devices (including thermostats) that contain mercury or lead.

20. Safety Data Sheets (SDSs)

The contractor must submit SDSs for all hazardous materials proposed for use, including paints, solvents, adhesives, etc., to the EB through the COR five working days prior to material being brought on post. As of June 1, 2015, all Material Safety Data Sheets (MSDS) must be replaced with new Safety Data Sheets (SDS). EB will no longer be accepting older legacy MSDS sheets, and the contractor must submit the current SDS for the hazardous material. The contractor must keep a copy of all SDSs required for the project at the jobsite.

21. Migratory Bird Protection

The contractor is responsible for meeting requirements of the Migratory Bird Treaty Act of 1918 (as amended). The contractor must not disturb any migratory bird, their nesting area or offspring during the implementation of this contract.

22. National Pollutant Discharge Elimination System (NPDES) Permits

The contractor must not perform any work on existing NPDES structures or treatment units unless previously approved in writing by the Installation Planning and Maintenance Division certified operators and the Environmental Branch. This includes work within the sewage treatment plant, sewage lift stations, sewage conveyance pipes, Industrial Operations Facility pretreatment plant, and storm water sewer systems. If a permit is required, it will be the responsibility of the contractor to obtain all permits prior to work being performed. All permit application packages must first be reviewed by the Environmental Branch prior to being sent to any regulatory authority. All liquids (chemical, cleaner, and lubricants) in containers, drums, and IBC totes are to be stored on secondary containment at all times. The container shall be labeled with the contents inside and an SDS sheet must be provided to EB.

23. Net Zero Water

The contractor will minimize the use of potable water during the construction project. Water used during the construction project will be monitored and measured using

portable water meters if possible. Installed restroom equipment will consist of high-efficiency fixtures that use reduced volumes of water. Use of flow regulation devices must be approved by EB prior to installation. Employ strategies that in aggregate use 20% less water than the water use baseline calculated for the building after meeting the Energy Policy Act of 1992 fixture performance requirements. Automatic hands-free flushometers will not be used. Water-free urinals will not be used. Flushometers will be the piston variety that fail in the closed position. New building construction and renovations will include installation of a water meter that is capable of being read from the outside of the building.

24. Noise

The contractor must not allow the noise level to exceed 65 decibels at any point outside TYAD property. If noise levels exceed 65 decibels, a plan must be prepared by the contractor to mitigate the noise levels and submit to the EB for approval through the COR. The contractor will monitor the fence line to confirm this limit.

25. Ozone Depleting Substances (ODS)

The contractor must be responsible for ensuring that all personnel who perform maintenance and repair activities on refrigeration equipment have been trained and certified by an EPA-approved Section 608 program. The contractor must not use Class I or Class II ODS or install equipment that contains Class I or II ODS. Beginning 1 Jan 26, the contractor must adhere to all AIM Act regulations regarding Hydrofluorocarbon refrigerants, Title 40, Chapter I, Subchapter C, Part 84.

25. Paints

The contractor must not use paints containing zinc chromate or strontium chromate pigments and paints must not contain a concentration of lead greater than 0.009 percent. Coatings used within permitted paint spray booths must not have a Volatile Organic Compound (VOC) content greater than 3.50 pounds per gallon.

26. Pest Management

At no time during the execution of this contract must the contractor provide a food source or harborage for any pests. The contractor must coordinate through the COR to the EB prior to the application of any pesticide (PA state license is required for pesticide applications). All pesticides are required to be approved by the EB. The contractor must report all usage of pesticides the day they are applied through the COR to the

EB. After completion of the contract, the contractor must ensure there is no passage for pests to enter facilities or structures related to work performed by the contractor.

27. Polychlorinated Biphenyls (PCBs)

The contractor must not bring items containing PCBs onto TYAD. Light ballasts that are clearly marked "Contains no PCBs," or that are marked with a manufacture date after 1978 must be disposed of by the contractor as construction demolition debris. Any light ballast that is not marked as containing no PCBs that has a manufacture date prior to 1978, or that cannot be determined whether it contains PCBs, must be disposed of by the contractor at an approved and licensed facility for PCBs. The contractor must submit a shipping manifest and certificate of disposal of the PCB-containing items to the EB through the COR.

28. Recycling

The contractor must comply with TYADs general recycling plan for recyclable materials such as aluminum, steel, cardboard, paper, plastic and wood. The contractor should contact the EB for additional information on the recycling of materials through the COR. The COR will coordinate with EB to have the contractor recycle metals, cardboard, etc., through TYADs recycling program. All Construction and Demolition (C&D) material transferred from a construction project into the TYAD recycling program must be segregated and material type and weights submitted to the project COR for consolidation. Any material entering the TYAD recycling program that is not documented and properly reported will be absorbed into the TYAD recycling program and not count towards the C&D requirement of the project. Clean wood shall be recycled by the contractor off TYAD property. Regarding disposal of the BBLAN, all reclaimed equipment must be turned into building 96 for disposal. Each component shall be turned in with an accompanying DD1348 form filled out in its entirety.

29. Refuse and Construction Demolition Debris Removal and Disposal

During the performance of all construction, renovation and demolition projects, a minimum of 60 percent of all non-hazardous construction demolition debris shall be diverted from the landfill for reuse or recycling. The contractor shall provide written certification to the COR of the type and tonnage of debris reused or recycled from the contract. All refuse and the construction demolition debris not recovered for

reuse or recycling shall be disposed of at a PADEP permitted and Monroe County Municipal Waste Management Authority authorized facility. The contractor shall comply with the Monroe County Solid Waste Management Plan, PA Act 90, and all applicable licensing requirements. All waste must be transported to designated Monroe County landfills; see http://www.thewasteauthority.com for details. For questions, contact the Monroe County Municipal Waste Management Authority at *TBD*. The contractor shall provide a disposal certificate or landfill weight slip to the COR for all solid waste disposed of during the performance of this contract. The COR will then provide copies of the disposal certificate or landfill weight slips with the quarterly consolidated C&D report from The Installation Planning and Maintenance Division to EB.

30. Removal Materials

The contractor must remove from the site prior to the acceptance of work by the Government, all materials not identified to remain in place, including excess paints, building materials and equipment purchased by the contractor for the execution of this project.

31. Site Preservation and Restoration

The contractor must ensure that the land resources associated under this contract be preserved in their present condition or be restored to a like condition after completion of construction. This post construction appearance will appear to be natural and not detract from the appearance of the project.

32. Trees and Shrubs Protection

The contractor must be responsible for the protection of all trees and shrubs on site. The contractor must not allow any heavy equipment, vehicular traffic or stockpiling of materials within ten feet from the drip line of any tree. The contractor must not allow any toxic materials to be stored within 100 feet (35.5 meters) of the drip line of any tree. The contractor must not nail protective devices, signs, utility boxes or other objects to trees to be retained on the site.

33. Unexploded Ordnance (UXO)

All work that is done in the UXO area must include the support and clearance by a UXO technician. In addition, all personnel entering the UXO area must have UXO recognition

training. The COR will escort the contractor to the EB for UXO recognition training. The COR will provide a map of the UXO area to the contractor.

34. Water Quality

The contractor shall not pollute streams, lakes or reservoirs. All work under this contract shall be performed in such a manner that pollution will not be created in streams, surface waters or underground water located within, or adjacent to the project area. The contractor shall not spill, emit, dump or otherwise discharge any hazardous, toxic, harmful or unauthorized pollutant, substance or material, including petroleum products, cleaning agents or paints, onto the ground, into the air or into any waters or nearby storm drain. The contractor shall execute any preventative measures required to prevent any hazardous, toxic or harmful material stored or used on the project site from entering any stormwater drain. Nothing shall be allowed to spill, emit, dump or otherwise discharge any hazardous, toxic or harmful material or pollutant into any sink, toilet, drain, utility or receptacle without written permission from the EB through the COR. The contractor shall protect streams, lakes and wetlands from sediment discharges caused by his activities. The contractor shall contract the EB immediately in the event of a spill.

8. Performance Standards

The performance standard evaluation ratings are as follows: PASS or FAIL.

PWS Section	Performance Task & Objective	Acceptable Quality Level (AQL)	Method of Surveillance
4.1	**LAN/Ethernet:** Install and terminate category 6 and 6E LAN twisted pair cable drops as requested.	90% of installations completed successfully without defects or rework.	Review of contractor installations via internal service desk tracking system; Periodic Inspection.
4.2	**Fiber Cable:** Install, terminate and splice fiber optic cable as requested by the COR	90% of runs/ repairs completed without physical damage to fiber	Review of contractor installations via internal service desk tracking system.

PWS Section	Performance Task & Objective	Acceptable Quality Level (AQL)	Method of Surveillance
		and passing signal tests.	
4.3	**Remedial Maintenance (RM):** Provide on-site RM within 6 business hours of notification for major failures. Correct major failures within 18 business hours.	90% adherence to response (6 hours) and restoration (18 hours) timelines.	Verification that LAN service is restored; 100% inspection of major outage tickets.
4.4	**BBLAN removal:** Deinstallation of the previously employed Broadband Local Area Network (BBLAN).	100% of BBLAN components and cables removed by end of contract.	Physical validation.

9. Unacceptable Performance

There is a 90% acceptance that repairs on equipment are completed within established timeframes and function to OEM specifications. Less than 90% is considered unacceptable. Remedies for unacceptability are: at the Contracting Officer's discretion the contractor shall arrange for repair by another qualified source at the contractor's expense.