US Department of Agriculture (USDA)



Statement of Work

Contents

Project 3
General Information 3
1.0 Scope of Work 3
2.0 Background 3
Contractor Requirements 3
3.0 Technical Requirements / Tasks 3
4.0 Government Furnished 3
5.0 Deliverables / Schedule 4
6.0 Travel 4
7.0 Contractor's Key Personnel 4
8.0 Security Requirements 4
9.0 Data Rights 4
10.0 Section 508 – Electronic and Information Technology Standards 4
Attachment 4

Project

Fernan Sewage Lift Station Electrical Repair

General Information

1.0 Scope of Work

The electrical infrastructure powering the two Unimount electric motors (see Pump Label 1 photo for specifications) that drive the lift station pumps presents several dangerous safety hazards to the service technicians who perform routine maintenance and monitoring. The hazards identified are as follows:

Corroded Disconnect and Breaker Components: The damp environment within the vault has corroded the connections and wires in the breaker box and disconnect switch. This presents several unsafe conditions and adds unnecessary wearing to the electrical motors that operate the pumps.

Exposed Power Cables on Floor: The unsecured power cables that come into the vault from the floor present a tripping hazard and are exposed to damage from foot traffic. To protect the cables and technicians, the point of penetration must be secured and the cables protected in a conduit rated for a damp environment.

Damaged light Fixture: The existing light fixture uses an A19 lightbulb that, due to the cramped conditions of the vault, presents a risk of being struck by a technician's head while performing service on the lift station system. As a light source is necessary in the space to insure the safety of technicians, a low-profile light fixture is needed

To compound these hazards, the underground vault that they are contained in is cramped with machinery, minimal access to natural light, and often has standing water on the floor, increasing the chances of accidental electrocution. To mitigate these hazards, the exposed cable will need to be replaced and contained within waterproof conduit, the damaged light fixture will need to be replaced with a low-profile light fixture, and the corroded disconnect and circuit breaker box will need to be replaced with new equipment appropriate for the damp environment.

2.0 Background

The Fernan Ranger Station Serves as the Coeur d'Alene River Ranger Districts main office as well as houses a majority of the district's specialist resource shops. During the busy summer season, the district supports approximately 90 employees and frequently has outside visiting crews utilizing the facilities.

Contractor Requirements

3.0 Technical Requirements / Tasks

-Replace Disconnect Switch and Breakers:

-Replace current control box housing with new moisture proof housing.

-Remove all components displaying signs of corrosion, including, but not limited, to the disconnect switch, circuit breaker, and distribution block.

-Install corrosion resistant replacements.

-Protect Exposed Cables:

-Replace any worn or damaged cables.

-Install a protective, waterproof covering at the point of penetration.

-Place all exposed cable into waterproof conduit.

-Replace Light Fixture:

-Remove current light fixture.

-Install low-profile, hard wired LED fixture.

-Install a switch in an easily accessible location from the entry point of the vault.

4.0 Government Furnished

NA

5.0 Deliverables / Schedule

Key Deliverables

Item No.	Deliverable	Objective	Due
1	Replace Disconnect Switch, Control Box Housing, and Breakers	Replace corroded disconnect switch, control box housing, and corroded, compromised components of the breaker box and install new water resist replacements.	No later than thirty (30) business days after notice to proceed
2	Protect Exposed Cables	Replace compromised cable, install junction box and metal conduit to protect cables.	No later than thirty (30) business days after notice to proceed
3	Replace Light Fixture	Replace existing light fixture with a low profile, LED fixture.	No later than thirty (30) business days after notice to proceed

6.0 Travel

Any travel expenses should be included in the quote.

7.0 Contractor's Key Personnel

All personnel working on this project must hold the required licensing for the tasks they are performing.

8.0 Security Requirements

NA

9.0 Data Rights

NA

10.0 Section 508 – Electronic and Information Technology Standards

NA

Attachment