CONSTRUCTION STATEMENT OF WORK

U.S. GENERAL SERVICES ADMINISTRATION, ROCKY MOUNTAIN REGION 8

Date: *4/30/2026*
Revision:

Section 1: Project Title

Turner Roof & Building Envelope Project

Section 2: Project Location, Building Name, & Building Number

Turner LPOE
41725 Turner Rd
Turner, MT 59542

Building Number: *MT0055AW*

Section 3: Contact List

Contracting Officer (CO) Name:
John Morelion
Email: john.morelion@gsa.gov
Address:
Phone (O): 817-805-6017
Phone (C):

Contract Specialist (CS)
Name: TBD
Email:
Address:
Phone (O):
Phone (C):

Development Project Manager
Name: Mark Lovie
Email: mark.lovie@gsa.gov
Address: 333 W. Broadway S#1001
San Diego, CA 92101
Phone (C): 415-961-0222

Property Manager
Name: Travis Mart - PMBE
Email: travis.mart@gsa.gov
Address: 901 FRONT ST
HELENA, MT 59601-9708
Phone (O): (701) 566-6126

Section 4: Project Background & Project Description

Due to the nature of the leaks at the Main Building at the Turner LPOE, GSA engaged in a roof investigation with Jackola Engineering in 2021 and a report was generated detailing many issues with warranty and owner (GSA) responsibility items. This report was used as a basis of a design that was initiated with Jackola Engineering in 2022.This design for the construction package was completed in 2024 and is shown as an attachment.

Initially, the roof was the main focus, however it was evident that the stucco exterior was showing signs of deterioration and could be a contributor to the water intrusion and it would only worsen over time. So this project

will entail not only roof replacement, but building envelope of the main building. Additionally, the stucco exterior is on the water treatment building and is included in the base bid of these design documents too.

Section 5: Project Objectives & Technical Requirements

Construction services required to accomplish the Base Bid include, but not limited to:

1. The project shall comply with the most current version of 2025 PBS Core Building Standards, Design Package dated 10/23/23, this Scope of Work with attachments, and all codes/standards referenced therein. Please refer to all documents and references to assure compliance with our requirements.
2. Phasing:
    a. Please include in your method of procedure (MOP) an outline for order of operations between the building envelope and roof. Please provide the best logical order to obtain optimal results of sealing up building envelopes and not damaging newly installed material.
    b. Please include in your MOP ways to secure the site by the end of the day for security and weather conditions.
3. The existing roofing manufacturer (IB Roofing) will be a part of this project and coordinated with on the following items:
    a. Due to the nature of continuous open seams, IB Roofing will be supplying a portion of the material for the roof replacement per the warranty. IB will furnish all roofing system components as defined and covered under the existing IB Roofing Warranty to include but not limited to the membrane, membrane flashings, insulation, cover board, fasteners, adhesives, flashing accessories, clad metal, and any other roof components previously furnished by IB Roofing. This material will be coordinated with a certified installer that the Contractor will be choosing.
        i. Are we getting the material list prior to bidding?
    b. IB Roofing will not furnish non-IB Roofing materials such as but not limited to the metal coping, plywood, or other materials that were not previously supplied by IB Roofing. This will be the responsibility of the Contractor.
    c. The existing IB Roofing Warranty is provided as an attachment.
    d. After the contract is awarded, IB Roofing will furnish the said materials above to the certified installer.
    e. An IB Roofing Representative will be available for a pre-construction meeting, kick off meeting and final inspection.
    f. After passing a final inspection, IB Roofing will issue a new 20 Year NDL to the owner (GSA) in lieu of continuing the existing warranty.
    g. The Contractor must coordinate the roof materials receipt, installation, and inspection with the certified manufacturer, to ensure the warranty remains in effect.
    h. Please coordinate with the Contracting Officer and Project Manager for executing this coordination among parties.
4. Canadian Requirements (CBSA)
    a. Work Permits
        i. Contractors who are working on the Canadian side will be required to get a work permit. They can obtain one when they arrive on site. It is recommended that they show up a day early to start the process.
        ii. The Contractor will not have to pay for an LMIA fee - there is an exempt number to be used and please coordinate with the Project Manager or Contracting Officer for more information.
        iii. The individuals will need to provide in person:
            1. A passport - or - Driver's license & certified birth certificate.

2. $155 CAN - they accept multiple forms of payment.

iv. The Contractor can call the Climax LPOE at 306.293.2262 for more information.

b. Since we are using the same materials on both sides of the border, the contractor will have to follow CBSA's process for importing materials.
   i. For more information on the process - please visit their website at: CBSA-ASFC.GC.CA
   ii. GSA highly recommends using a broker to execute the necessary forms for importing materials if the Contractor is not familiar with the process. Please coordinate with the Project Manager or Contracting Officer for more information on brokers.
   iii. Some attributes/requirements about the process:
      1. Canadian Customs Coding Form - B3-3 (04)
         a. Paperwork needs to be filled out for each vendor.
      2. It amounts to 5% of the Canadian value of the goods.
      3. Requires obtaining a business number.

c. Dumpster Refuse Requirements:
   i. Any dumpster for hauling off recyclable materials or refuse will be on the US side of the border. CBSA will allow such materials to cross over the border and disposed of properly.

d. Antennas & Cables
   i. Coordination on moving/removing antennas and cables will need to be coordinated with CBSA.
   ii. The antenna on the second floor roof will be replaced with a non-penetrating stand. A non-penetrating stand on the upper level will be supplied and installed by CBSA IT personnel once the new roof is installed.
   iii. Please refer to Sheet A3.00 for more information.
   iv. Please coordinate with the Project Manager and Contracting Officer to aid in this process.

e. Building Signs Coordination:
   i. Coordination on removing, storage and reinstallation of the building signs will need to be coordinated with CBSA.
   ii. Please coordinate with the Project Manager and Contracting Officer to aid in this process.

5. US Requirements (CBP)
   a. Antennas & Cables:
      i. Existing antenna cables and antennas will be coordinated with OIT (CBP IT personnel) prior to moving/removing from the original location.
      ii. The east side, wall mounted antenna will be on a new stand on the roof, not reinstalled on the wall. This new non-penetrating stand will be provided and installed by OIT personnel once the new roof is installed.
      iii. Please refer to Sheet A3.00 for more information.
      iv. Please coordinate with the Project Manager and Contracting Officer to aid in this process

   b. Cameras & Cables:
      i. Existing camera cables and cameras will be coordinated with OIT (CBP IT personnel) prior to moving/removing from original location.
      ii. See the attached phasing diagram provided for their camera system. Not all cameras can be taken down or offline at the same time.
      iii. Please refer to Sheet A3.00 for more information.
      iv. Please coordinate with the Project Manager and Contracting Officer to aid in this process.

   c. Building Signs Coordination:
      i. Coordination on removing, storage and reinstallation of the building signs will need to be coordinated with CBP. Please coordinate with the Project Manager and Contracting Officer to aid in this process.

   d. Security Requirements:
      i. Additional CBP security requirements will be adhered to on this project. Please refer to

the attachments for more information.

ii. Please contact the Project Manager or Contracting Officer for additional support.

6. Other key items to keep in mind:
    a. Conduit will be housed behind the new facade to allow re-routing of cables and wires for a cleaner look. There will not be any surface mounted conduit on the new building facade.
    b. Additional requirements are listed in Division 1 of the specifications.
    c. GSA will provide additional contracts for Building Commissioning Agent and Construction Administration throughout the project. They will be coordinating at specific milestones to ensure quality control is being adhered to.
        i. The Contractor is required to provide mock-ups during this project. Please refer to the specifications and PBS Core Building Standards for more guidance and will be a submittal provided for approvals.

Section 6: Facilities Standards and Code Compliance

All work shall comply with the most current version of 2025 PBS Core Building Standards, and all codes/standards referenced therein.

Section 7: Proposal Pricing & Site Walk

Pre-proposal Site Visit Meeting

The site visit shall consist of a meeting to review the design requirements and the solicitation package followed by a walk-thru of the project site. Attendees shall include the A/E and GSA project personnel, and appropriate sub-contractors. No virtual site walk will be provided, only in person. Please coordinate with the COR & CO to coordinate a day and time.

The Contractor shall perform any site reviews necessary to ensure the design documents correctly reflect the existing conditions of the project area to include any field verification.

Cost Proposal Requirements

- Construction Pricing- When submitting a proposal, pricing shall be broken down by Construction Specification Institute (CSI) divisions. Provide a cost breakdown for each task into the following categories: Materials, equipment, labor hours, subcontractor's quotes, overhead, profit, and bond. Proposal shall include a breakdown of building shell, tenant improvements by tenant, building specific amortized capital (BSAC), and environmental costs, as applicable. Consult GSA project manager for further guidance.

- Proposal Structure

    - Base Bid - Turner Main Building Roof & Building Envelope (US)
    - Base Bid - Turner Main Building Roof & Building Envelope (CAN)
    - Base Bid - Turner Water Treatment Building Envelope (US)

Section 8: Period of Performance

Once notice to proceed has been issued, the contractor has 150 calendar days to complete construction. The contractor must promptly begin the badging process at the time of award. Please allow a minimum of 30 days to

complete the badging process. Contractor to provide overall project design and construction schedule that does not exceed the period of performance of 150 days.

A construction schedule, developed with consideration for the local climate, shall be provided by the contractor. This schedule must reflect the most current understanding of local weather patterns, material requirements, and availability, detailing projected weather delays and identifying the optimal construction window to prevent them

Section 9: Use of Premise & Badging

Contractor Use of the Premise

Construction- During the period of construction, the contractor will have access to the site only during business hours of 9:00 am to 5:00 pm. No on-site work shall be performed outside these hours or on holidays unless otherwise directed by the Contracting Officer or Project Manager. The contractor will need to coordinate with the Contracting Officer to arrange access to the parking lot. The contractor shall make every effort to cause a minimum of damage to parking lots, any other paved areas, any items that need to be moved during the course of the project, and any areas not included in this scope of work. Any damage caused will be repaired at the contractor's expense.

Disruptive Work

All painting, staining, or other activity which may cause noxious or undesirable fumes and/ or any noisy work that may be disruptive to the tenants/ public must be performed after normal working hours. The use of paint or stain that does not generate odors is preferred and may be required if the space will be occupied the following day with prior written approval from GSA.

Badging & Security

Contractor is responsible to follow GSA's security and badging requirements as detailed in the attached Badging & Security Requirements (Vendor Fitness Determination Training Manual).

US Access shared enrollment centers can be found at fedidcard.gov. Travel distances to the nearest center should be accounted for during the badging process.

Please refer to any additional security requirements as listed above and attached within this SOW.

Progress Meetings

The contractor shall schedule bi-weekly meetings with the GSA, subcontractors, and stakeholders during both design and construction phases. **The Contractor shall keep meeting minutes** and distribute copies at the following meetings. The meeting agenda will include the following as a minimum: Approval of previous meeting, review of work progress, field observations, problems and decisions, identification of problems which impede planned progress, review of submittals schedule and status of submittals, maintenance of progress schedules, planned progress during the succeeding work period.

Section 10: Project Management Information System

GSA requires the use of the PMIS (GSA's project management information system) throughout the project life cycle as a project management tool, and as a repository for timely and accurate project information. The current PMIS in use by GSA is Google Drive.

The contractor shall utilize the PMIS for the following:

1. Collaboration Tool - Collaborate with GSA and the broader Project Delivery Team across all project tasks.
2. Storage Repository - Store all project information and documentation, including controlled unclassified information (CUI) and communications.
3. The following applications shall be utilized by the Contractor:
    - Expenses - Manage contract financial information including contract awards, tracking potential change requests, breakdown of schedule of values, and pay request review
    - Document Management
    - Communications - Document and upload formal project communications
    - Daily Reports - Document and upload daily reports
    - Design Review - Initiate, manage and participate in project design reviews
    - Field Observations - Record field observations, test results and upload related documentation
    - File Manager - Manage project/contract files and initiate design reviews
    - Meetings - Document project meetings and track progress on key action items
    - Packaged Submittals - Manage project submittal review process and upload related documentation
    - Punchlists - Manage project punch-list process and upload related documentation
    - RFI’s - Manage project RFI process and upload related documentation
    - Risk Register - Identify and contribute to managing key project risks
    - Safety - Manage project related safety issues including Accident Reports, Fire Alarm/Sprinkler Outage Requests, Fire Incident Reports, Hot Work Requests, Injury Reports and Safety Notices
    - Schedule Management
4. Other
    - Sustainability - Review/contribute to project sustainability reporting, uploading related documentation
5. Access and Equipment - PMIS is web-accessible and can therefore be accessed via any compatible computer with an Internet connection. For requesting access, a GACA account will need to be created and shared with COR & CO for allowing access to the Google Drive. GSA will not furnish any equipment related to accessing PMIS.

6. Personnel Requirements - An HSPD-12 (Homeland Security Presidential Directive 12) security clearance is not required to access the GSA PMIS. Further information on HSPD-12 may be found at the following website: www.gsa.gov/hspd12. The time to process and obtain clearances may vary in length.

Section 11: Universal Scope Requirements

Contractor shall comply with attached Universal Scope Requirements (USR) as applicable.

Section 12: Submittals & Deliverables

Submittal Register/ Log

Include all products specified to establish a standard of quality. If product samples are required, please submit to the project manager in duplicate.

Refer to the specifications for more information on required submittals.

Method Of Procedures (MOP)

Contractor shall submit a MOP to the GSA Delivery Project Manager (PM) for approval prior to commencement of work that is disruptive or will impair any building systems (fire/life safety, mechanical, electrical, plumbing, etc.). At a minimum, the MOP shall include:

- Brief narrative describing method of project accomplishment, construction techniques, phasing, etc.
- Updated project schedule (to include phasing, critical path, major milestones, long lead time items, inspection dates, substantial completion, and project closeout)
- Service/Utility Outages (if necessary), also outage request form to be submitted.
- Any building infrastructure/ BAS equipment that may be impacted

Pre-Alteration Assessment Report

Contractor to perform a pre-alt asbestos and lead environmental survey prior to commencement of any work.

NCMMS (Maximo) Equipment Uploader

All new equipment and anything requiring a preventative maintenance plan shall be inputted into NCMMS upload template *(NCMMS template attached).*

Section 13: Fire, Life, & Safety

Fire Watch

Contractor shall be responsible for providing fire watch if required per attached GSA fire watch guidelines.

Fire Alarm Impairment and Hot Work

When a fire suppression or alarm system impairment is required, the Contractor shall provide a written outage request to GSA for approval in advance of impairing any systems. Contractor shall be responsible for having a GSA approved NICET certified fire alarm contractor perform all system impairments. During fire alarm/suppression impairments or hot work procedures, the Contractor shall provide a fire watch per the GSA Regional Fire Watch Guidelines.

Section 14: On-Site Logistics

Equipment and Material Storage

The contractor shall provide and store all equipment, the materials specified above, and any other materials required completing the project. The materials are required to be kept clean and dry throughout the duration of the project. Contractor to coordinate with building manager for location of storage sheds.

Equipment

The contractor shall provide all equipment associated with the entire project, operate in a safe manner and adhere to all OSHA and GSA standards.

Sanitary Facilities

Provide and maintain temporary toilet facilities in accordance with State Health Department and GSA requirements.

Electricity, Water, and Gas

GSA will pay for electricity, water, and gas during the course of this project. The contractor is responsible for making connections to the existing systems. Temporary electrical work shall meet the requirements of NFPA 70-1996 (NEC), Article 305. When temporary connections are removed, restore existing utility services to their original condition.

Contractor's Field Office

The contractor may provide an office for their own use. Size, location, and construction shall be subject to approval.

Protection of Public

The building site will continue to be used by tenants. The contractor shall fence, barricade, or otherwise block off the immediate work area to prevent unauthorized entry. The contractor shall illuminate barricades and obstructions at night and maintain safe building access and egress for tenants.

Housekeeping

The project site shall be kept in a neat, orderly, and safe condition at all times. The contractor shall provide enough containers for collecting construction debris and construction materials to be recycled. The contractor shall wet down dry materials and rubbish to prevent blowing dust and keep volatile wastes in covered containers.

Transportation and Deliveries

The contractor shall arrange deliveries of materials in accordance with construction schedules; coordinate with COR to avoid conflict with other tenants and other work conditions at the site. Contractor must make GSA PM & CO aware of any lead times that may affect the project schedule.

Cleaning

Before scheduling the final inspection, the Contractor shall accomplish six items: (1) Remove all tools, equipment, surplus material, and rubbish; (2) Restore or refinish, to original condition, surfaces that are damaged due to the work of this contract; (3) Remove grease, dirt, stains, foreign materials, and labels from finished surfaces; (4) Thoroughly clean building interiors; (5) Pickup all construction debris from the site; and (6) At time of final inspection, project shall be thoroughly cleaned and ready for use.

Section 15: Substantial Completion & Final Inspection

When the project or designated portion of the project is deemed complete, the contractor shall request a final inspection. The Contracting Officer will proceed with the inspection within 10 days of receipt of request or will advise the contractor of incomplete work or open items that are preventing a final inspection.

Section 16: Project Closeout

After completion of all work, the Contractor shall submit to the project manager the manufacturer's specifications, instructions, and material specification sheets in original form. Additionally, the Contractor shall submit all inventory changes (removals, additions, upgrades, etc., and new condition codes) to the COR.

Red-Lined drawings and CAD and/or BIM as-built drawings and field training for Operations and Maintenance (O&M) personnel shall be provided at completion of project. Maintain one complete set of contract drawings and clearly mark changes, deletions, and additions using GSA CAD Standards to show actual construction conditions. Show additions in red, deletions in green, and special instructions in blue.

The contractor shall provide O&M manuals. The O&M manuals shall contain executed warranties. Maintenance and operation manuals shall be submitted in a timely fashion following project completion.

Section 17: Attachments

1. Turner / Climax LPOE Recladding and roof repair Final 100% CD Set
2. Turner / Climax LPOE Recladding and roof repair Project manual dated 09/28/2023
3. Badging & Security Requirements (Vendor Fitness Determination Training Manual)
4. NCMMS Equipment Uploader Spreadsheet
5. CBP Security Clearance Documents
6. Existing Roof Warranty
7. Camera Phasing Diagram
8. Jackola Engineering Construction Set Dated Need to add to attachment folder

Section 16: Proposal/Quote Pricing

When submitting a proposal/quote, provide a cost breakdown for each task into the following categories. Items in parenthesis include some of the items to be considered in each category.

Base Bid – Turner Main Building Roof & Building Envelope (US)

Division No.	*Description*	*Qty*	*Unit*	*Total Price*
		Direct Costs		
01	General Requirements	1	LS	
02	Existing Conditions	1	LS	
04	Masonry	1	LS	
05	Metals	1	LS	
06	Wood, Plastic & Composites	1	LS	
07	Thermal & Moisture Protection	1	LS	
08	Openings	1	LS	
09	Finishes	1	LS	
26	Electrical	1	LS	
27	Communications	1	LS	
28	Electronic Safety & Security	1	LS	
			Subtotal for Direct Costs	
		Indirect Costs		
	Government Furnished Products (GFP)	N/A		
	Continuity of Operations & Move Management	N/A		
	Design and Site Contingency	X	%	
	Contractor O&P	X	%	

	Contractor's Overhead, Profit, Bond & Insurance	X	%	
	Bid Bond	1	LS	
	Construction Contingency	X	%	
	General Conditions	X	%	
	Material Testing	X	%	
	Performance & Payment Bond	X	%	
	Builder's Risk Insurance	X	%	
	Permits & Tap Fees	X	%	
			Total Value	

Base Bid – Turner Main Building Roof & Building Envelope (CAN)

Base Bid – Turner Water Treatment Building Envelope (US)